

Report On BENCHMARKING OF IRRIGATION SYSTEMS IN MAHARASHTRA STATE 2008-09



WATER RESOURCES DEPARTMENT Government Of Maharashtra, India March 2010

This report is available on following web site

1) Water Resources Department, Government of Maharashtra www.mahawrd.org

This report and data is also available on following web site

1) Maharashtra Water Resources Development Centre, Aurangabad <u>www.mwrdc.org</u>



REPORT ON BENCHMARKING OF IRRIGATION SYSTEMS IN MAHARASHTRA STATE 2008-09



FOREWORD

Water is an important and valuable natural resources. It is said that water is life. On these terms it has become important to plan and co ordinate the available resource. The distribution of water resources is not even anywhere on this earth, so it is uneven in our Maharashtra State. With the development of Industries, the water availability for the crop production is becoming lesser every year. It has become necessary to utilize water in a very stringent manner.

In Maharashtra there are 71Major, 243 Medium and 2940 Minor projects fully or partially completed up to June 2008. In compliance to commitment in State Water Policy about transparency in water use and to identify the areas of problems in seeking objective set in the project planning, benchmarking of irrigation system in the State is in practice since last 6 years.

Benchmarking is a systematic process for securing continual improvement through comparison with relevant and achievable internal or external norms & standards. To achieve this every indicator is compared with last five years average, year (2007-08) & (2008-09). This enables to compare the performance with predecessors as well as own performance of the last year.

Use of benchmarking has conferred success in elevating the performance level of irrigation projects. Increase in potential utilization from 1.708 Mha to 2.732 Mha and revenue recovery from Rs. 252 crores to 673 crores is significant achievement of Water Resources Department during last five years.

More improvement in project performance can be attained if results of benchmarking are systematically utilized for framing and implementing the project wise action plan. Looking to this aspect from this year one new chapter on benchmarking of individual projects with 3 important parameters is added in the report.

In near future, there will be a shift of irrigation Water Management from Water Resources Department to Water Users Associations. Naturally, benchmarking of WUA will be also helpful for performance evaluation and creating awareness amongst water management staff and office bearers of WUA's.

Lastly, I appeal all project authorities to use benchmarking as an effective management tool to improve the current performance level of the irrigation projects.

I appreciate efforts taken by Shri R.B. Shukla, Chief Engineer, MWRDC, Aurangabad and his team for preparation of this report.

I also appreciate the co-operation extended by The Director General, WALMI, Aurangabad for getting this report printed at Aurangabad.

Comments & suggestions on this report will be appreciated.

M.S. Mundhe Secretary (CAD)

Maharashtra Water Resources Development Centre, Aurangabad Team associated with Benchmarking Report

Name

Designation

Shri V.B.Lalsare	Executive Engineer
Shri M .S. Badarkhe	Executive Engineer
Smt. S. A. Sulakhe	Assistant Engineer (Grade-I)
Smt. R. S. Patil	Assistant Engineer (Grade-I)
Shri G. G. Solapure	Sub Divisional Engineer
Shri O. B. Bhoyar	Sub Divisional Engineer
Shri. S. G. Deshpande	Sub Divisional Officer
Shri S. D. Joshi	Sub Divisional Engineer
Shri. B. A. Chivate	Assistant Engineer (Grade –II)
Shri G. S. Deshpande	Sectional Engineer
Shri S. M. Bhosle	Sectional Engineer
Shri K. K. Barbind	Sectional Engineer
Shri P. R. Bahalaskar	Sectional Engineer
Shri V.K. Nimbalkar	Dafter Karkoon
Shri S.M. Kedare	Dafter Karkoon
Shri A.B. Naybal	Dafter Karkoon
Sow A.B. Wakpanjar	Dafter Karkoon
Shri R. R. Kulkarni	Typist
Shri L. R. Jadhav	Typist
Smt. M. S. Tupe	Typist

ABBREVIATIONS

Avg Per	Average performance
BCM	Billion Cubic Metre
CAD	Command Area Development
CBIP	Central Board of Irrigation & Power
CCA	Culturable Command Area
CRT	Converted Regular Temporary
DIRD	Directorate of Irrigation Research & Development
FAO	Food & Agriculture Organisation
FY Avg	Five years average
GCA	Gross Command Area
GOI	Government of India
GOM	Government of Maharashtra
TS	Two Seasonals
ha	Hectare
HW	Hot weather
ICID	International Commission on Irrigation & Drainage
IMD	Indian Meteorological Department
INCID	Indian National Committee on Irrigation & Drainage
IPTRID	International Programme for Technology and Research in
	Irrigation and Drainage
IWMI	International Water Management Institute
m	Metre
M cum/ Mm ³	Million Cubic metre
Mha	Million Hectare
MKVDC	Maharashtra Krishna Valley Development Corporation
MWSIP	Maharashtra Water Sector Improvement programme
MMISF ACT	Maharashtra Management of Irrigation System by farmers Act 2005.
Mm	Millimeter
MWIC	Maharashtra Water & Irrigation Commission
MWRDC	Maharashtra Water Resources Development Centre
NLBC	Neera Left Bank Canal
NRBC	Neera Right Bank Canal
0 & M	Operation & Maintenance
Past Max	Maximum value observed in Past
Past Min	Minimum value observed in Past
PIM	Participatory Irrigation Management
PIP	Preliminary Irrigation Programme
PLBC	Paithan Left Bank Canal
PRBC	Paithan Right Bank Canal
PWD	Public Works Department
Sq km	Square Kilometre
~Y min	Square Infolieure

State Tar	State target
WALMI	Water and Land Management Institute, Aurangabad
WRD	Water Resources Department
WUA	Water Users' Association
ISP	Irrigation system performance
AIC Akola	Akola Irrigation Circle, Akola
AIC Aurangabad	Aurangabad Irrigation Circle, Aurangabad.
BIPC Buldhana	Buldhana Irrigation Project Circle, Buldhana
CADA A'bad	Command Area Development Authority, Aurangabad
CADA Beed	Command Area Development Authority, Beed
CIPC Chandrapur	Chandrapur Irrigation Project Circle, Chandrapur
JIPC Jalgaon	Jalgaon Irrigation Project circle, Jalgaon
KIC Ratnagiri	Konkan Irrigation Circle, Ratnagiri
NIC Nagpur	Nagpur Irrigation Circle, Nagpur
NIC Nanded	Nanded Irrigation Circle, Nanded
NIPC Dhule	Nashik Irrigation Project Circle, Dhule
NKIPC Thane	North Konkan Irrigation Project Circle, Thane
PIC Pune	Pune Irrigation Circle, Pune
SIC Sangli	Sangli Irrigation Circle, Sangli
TIC Thane	Thane Irrigation Circle, Thane
UWPC Amravati	Upper Wardha Project Circle, Amravati
YIC Yeotmal	Yeotmal Irrigation Circle, Yeotmal

Sr.		Page No.		
No.	Description	From	То	
1	Executive Summary	1	6	
2	Chapter – 1 : Introduction		18	
3	Chapter – 2 : Benchmarking of Irrigation Projects	19	22	
4	Chapter – 3 : Performance Indicators	23	28	
5	Chapter – 4 : Overall status of Benchmarking Projects in Maharashtra	29	34	
	Major Projects : Indicators I to XII	35	73	
	Medium Projects : Indicators I to XII (Except indicator IX, X)	75	109	
	Minor Projects : Indicators I to XII (Except indicator IX, X, XI, XII_NI)	111	138	
6	Chapter –5 : Actions taken for improvement of performance		139	
7	Chapter – 6: Benchmarking of Water Users' Associations		163	
8	Chapter – 7: Project wise review of Major and Medium Projects	164	212	
9	Chapter –8: Benchmarking of WALMI	213	227	
10	Appendices			
	Appendix I – Abstract of guide lines issued by GOM for Benchmarking of Irrigation Projects	229	229	
	Appendix II – State target values for indicators.	230	232	
	Appendix III – Overview of projects selected for Benchmarking.	233	247	
	Appendix IV – River Basins and Agro Climatic Zones of Maharashtra.	249	253	
	Appendix V – Abstract of Water rates for irrigation, domestic and industrial use.	254	255	

CONTENTS

Executive Summary

The methodology and main performance Indicators for Benchmarking are adopted as per the guidelines issued by Indian National Committee on Irrigation & Drainage (INCID) in 2002.

The year wise indicators selected for benchmarking since 2001-02 along with their Domain are enlisted below:-

Year	Domain	Performance Indicator		
2004 02	1. System Performance	i) Annual irrigation water supply per unit		
2001-02		irrigated area		
	2. Agricultural Productivity	i) Output per unit irrigated area,		
		ii) Output per unit irrigation supply		
	3. Financial Aspects	i) Cost Recovery Ratio		
		ii) Total O&M cost per unit area		
		iii) Revenue per unit volume of water supplied		
		iv) Maintenance cost to revenue ratio		
		v) Mandays for O&M per unit area		
		vi) Total O&M cost per unit volume of water supplied		
	4. Environmental Aspects	i) Land damage index		
2002-03	1. Deleted Indicator	Maintenance Cost to Revenue Ratio		
	2.Additional Indicators	1. Potential Created and Utilised		
		Equity Performance		
2003-04	Additional Indicator	Assessment Recovery Ratio		
		a. Irrigation		
		b. Non-irrigation		
2004-05	No Change			
2006-07	1 Deleted	Mandays per unit area		
2007-08	No Change			
2008-09	System performance	New indicator 1 a, Annual Area irrigated per unit of water supplied is added		

Initially, the exercise was conducted for 84 projects in 2001-02 with 10 indicators. The number of projects increased to 254 in 2002-03 with 11 indicators. Instead of presenting the data of all these projects individually, an irrigation circle was considered as a unit for evaluation of performance. Here also, it was observed that some of the characteristics of projects under a circle are not identical and to make the comparison still on better grounds, from the year 2003-04, projects under a circle in a sub basin are grouped together and comparison is made with other projects in a particular plan group.

In carrying out the Benchmarking exercise, following categorization of irrigation schemes into similar types have been done for comparison.

a)	Type of control for Supply of water	Fixed proportional division, manual control, automatic control			
		"Manual Control" is applicable in this			
		Benchmarking Exercise.			
b)	Method of allocation	Supply-oriented arranged-demand, on demand			
	and distribution of water.	The method applicable in this case is "on-			
		demand."			
c)	Water Availability	Abundant, Scarce.			
		Highly deficit to Abundant.			
d)	Water Source	Water Source Surface water, groundwater or both.			
		Surface water is applicable			
e)	Size	Major, Medium, Minor.			
		All sizes applicable			

This is the eighth consecutive report of benchmarking of irrigation projects in the State with 262 projects and 12 indicators. The plan group wise number of projects selected for benchmarking during 2008--09 is as follows.

Sr.		Nagp	our, Amra	vati	Pune, Konkan Region		Aurangabad, Nashik				
	Plan Group		Region				Region				
		Major	Medium	Minor	Major	Medium	Minor	Major	Medium	Minor	
1	Highly Deficit				1	11	3	-	16	4	35
2	Deficit	4	10	13				10	44	18	99
3	Normal	4	13	5	6	1	2	10	16	8	65
4	Surplus	3	22	4							29
5	Abundant	2	2	1	8	10	11				34
	Total	13	47	23	15	22	16	20	76	30	262

Grand Total: 262

Out of 12 indicators as mentioned above, one indicator regarding "Mandays Per Unit Area" was deleted and only 11 indicators are selected now.

Methodology

The data presented in this report is based on information collected from each of the circle in-charge of the project.

The following process was used in development of this report.

- For achieving consistency in monitoring & evaluation, same projects which are considered for benchmarking during 2007-08 are considered in year 2008-09.
- The data about water use and area irrigated is correlated with water accounts (2008-09) of relevant projects.

• The presentation for every indicator is done with past-past (5 year average), recent past (2007-08) and present year (2008-09) in order to compare the performance with predecessors as well as own performance of last year.

Based on performance for 2008-09, indicator wise average performance is found out for the plan group of circles under consideration, setting aside the exceptionally high/low values.

. For financial indicator of output per unit irrigated area and output per unit irrigation water supply, fixed prices of 1998-99 are considered to obviate effect of price rise.

There are 2940 completed minor irrigation projects in the State. Therefore, it has been decided to carryout benchmarking and monitoring of minor projects at circle level itself. To get an idea about performance of minor projects, some sample schemes which were considered in last year's report are analysed and included in this report.

Benchmarking of WUA

Till June 2008, potential to the tune of 4.486 Mha has been created on state level projects.

In view of the huge capital cost investment in construction of projects as well as in rehabilitation of canal systems along with intention of securing the advantage of benchmarking, benchmarking of WUAs was felt necessary. Accordingly the issue of Benchmarking of WUA was under consideration for last two years.

To initialise the process, 9 Indicators feasible to determine the performance of individual WUA are designed and data in prescribed proforma was received from selected 12 WUA's on 7 Major projects.

The details about objectives of Benchmarking of WUA's, Proformae used for calling the data along with indicator wise, WUA wise analysis has been given as a case study in a separate chapter (Chapter 6) in this report.

Indicator wise Performance of Maharashtra State for the Years 2002-03 to 2008-09

Indicator – I: Annual Irrigation Water Supply per Unit Irrigation Area: Unit: Cum/ha

Annual Irrigation water supplied for major projects in Maharashtra state is higher in 2008-09 i.e. 10253 cum/ha as compared to the same in the year 2007-08 i.e. 8289 cum/ha. And for medium project it is lower in the year 2008-09 i.e. 7447 cum/ha. compared to previous year 2007-08 i.e. 8449 cum/ha. For minor project the water use is less in the year 2003-04 i.e. 5945 cum/ha. and maximum in the year 2005-06 i.e. 9738 cum/ha and for the year 2008-09 the indicator value is 6575 cum/ha.

Indicator – I a: Annual Area Irrigated per unit of water supplied:

Unit: ha/Mm³

The area irrigated per unit of water supplied in 2008-09 is 98 ha./Mm3 which is less than last year value i.e. 121 ha/Mm3 for Major projects. In case of Medium project indicator value is 134 ha/Mm3 for 2008-09, which is more than last year (2007-08) value i.e. 118 ha/Mm3. For Minor irrigation projects indicator values for the year 2008-09 is 152 ha./Mm3 which is more than last years value i.e. 145 ha./Mm3 Indicator –II: Potential created and utilized: Unit: Ratio

For Major Projects the maximum utilized potential was in the year 2006-07. The utilized potential is increasing yearly from 0.46 in the year 2002-03 to 0.91 in the year 2006-07. The utilized potential is 0.80 for current year. For medium projects the ratio in the year 2008-09 is 0.74. For minor Projects utilized potential was 0.42 in the year 2003-04 and it is improving for last four years and 0.89 in the year 2006-07, it has slightly decreased for the current year i.e. 0.63.

Indicator-III: Output per Unit Irrigated Area: Unit: Rs/ha

For Major Projects agricultural output shows variations in last five years. Maximum agricultural output of Rs. 36730/ha is in the year 2008-09 and minimum of Rs. 26758/ha is in the year 2003-04. For medium project the agricultural output of Rs. 42613/ha was maximum in 2005-06 and minimum of Rs. 25358/ha in the year 2004-05. For this year the indicator value is Rs. 28259/ha. For Minor Projects

agricultural output is maximum of Rs. 36176/ha in 2007-08 and minimum of Rs. 21015/ha in the year 2006-07. For this year the indicator value is Rs 22571/ha.

Indicator–IV: Out Put per Unit Irrigation Water Supply: Unit: Rs/Cum

For Major Project the output per cum was Rs. 2.93/cum in the year 2002-03 and went on increasing year by year and reached to a maximum of Rs 5.25/cum in the year 2008-09. For Medium Projects maximum output of Rs. 4.84/cum is in the year 2008-09. For minor projects the output of Rs 3.84/cum for the year 2008-09 year and minimum of Rs. 3.75/cum in the year 2006-07.

Indicator –V: Cost Recovery Ratio:

Unit: Ratio

For major projects the ratio for the year 2008-09 is 0.95. For medium projects the ratio was in between 0.30 to 0.43 for last five years, for current year the ratio is maximum i.e., 0.39. In case of Minor Projects ratio was in between 0.28 to 0.35 for four years. But in 2005-06 the ratio was maximum i.e. 0.83, for this year the ratio is 0.23.

Indicator - VI: O & M Cost Per Unit Irrigated Area: Unit: Rs/ha

For Major Projects the O & M Cost per Unit Area is on higher side of state target for previous years it was nearly three times the state target except in the year 2006-07. It is Rs. 3687/ha in the current year. It is due to excess expenditure on maintenance. In Medium Project O & M expenditure increased from the year 2002-03 to 2008-09 consistently. For Minor Projects the O & M Cost Per Unit Area was minimum of Rs. 981/ha in the year 2002-03 and increased year by year to a maximum of Rs. 5035/ha in the year 2005-06. For the current year it is Rs 3574/ha.

Indicator – VII: O & M Cost per Unit Water Supply: Unit: Rs/Cum

For Major Projects O & M Cost per Unit water Supply ranges between Rs. 0.18/cum to Rs. 0.40/cum from year 2002-03 to 2007-08. However for the current year it is Rs. 0.28 /cum. For Medium Projects excessive O & M expenditure resulted in poor performance for last five years. It is Rs.0.37/cum for current year. For Minor projects the O & M Cost per Unit Water Use was in between Rs. 0.16/cum to Rs. 0.9/cum for five years. This year it is Rs. 0.45/cum.

5

Indicator – VIII: Revenue Per Unit Water Supply:

For Major Project in Maharashtra State, Revenue Per Unit Water Supply, for last five years, ranged from Rs. 0.20/cum to Rs. 0.24/cum. This year it has increased to Rs. 0.3/cum. For medium project the revenue was Rs. 0.07/cum in the year 2002-03 and went on increasing to Rs. 0.15/cum in the year 2005-06. The indicator value is Rs 0.12/cum for current year. For Minor Projects revenue per unit water use was in between Rs. 0.04/cum to Rs. 0.11/cum. For current year the ratio is Rs 0.05/cum.

Indicator – X: Land Damage Index

Unit: Ratio

Unit: Ratio

In some of the projects like Bhima, Jayakwadi, Manjra, Kukdi, Upper Penganga, Khadakwasla, Nira, Krishna and Radhanagri land damage to certain extent is observed. In Bhima, Jayakwadi, Upper Penganga the land damage index is slightly increasing. In remaining projects, either it is same or decreasing.

Indicator – XI: Equity performance:

In almost all projects the ratio in head reaches is more except in projects of CADA Nagpur. There are some projects like Khadakwasla, NLBC and Krishna where equity is maintained in all three reaches where as in NRBC the ratio of tail reach is more than remaining two.

Indicator – XII: Assessment Recovery Ratio (Irrigation): Unit: Ratio

For Major Project Assessment Recovery Ratio was minimum in the year 2005-06 i.e. Rs. 0.22. But in the year 2007-08 it increased to 0.40 due to improvement in recovery of irrigation water charges however it has been slightly decreased to 0.37 for the year 2008-09. For Medium Projects ratio shows ups and downs year wise. It was 0.22 in the year 2003-04 and increases to 0.67 in 2005-06, for the current year it is 0.33. For Minor Project Assessment Recovery Ratio was in between 0.43 to 0.81 for five years. For the current year it is 0.56.

Indicator – XII: Assessment Recovery Ratio (Non Irrigation): Unit: Ratio

For Major projects the ratio for the last six years is between 0.81 to 1.09, for the current year it is 0.73. For medium projects the ratio is between 0.64 to 1.85, for the current year it is 0.79. In minor projects the ratio is in between 0.40 to 1.07, for the current year it is 0.79.

6

Unit: Rs/cum

CHAPTER - 1

INTRODUCTION

1.0.0 Benchmarking is a very powerful management tool for analysing and improving the performance of water resources projects. It is widely accepted all over the World. IPTRID, IWMI, ICID, World Bank & FAO advocate use of benchmarking – since 2000.

For evaluation and improvement in performance of water resources projects, Government of Maharashtra has undertaken the benchmarking exercise in the State since 2000-01. The first Benchmarking Report was published in 2001-02.

Considering a shift in Irrigation Water Management from Water Resources Department to Water User's Associations to secure the advantages of benchmarking, benchmarking of WUA'S was under consideration for last two years. To set an example before the Project Authority, an attempt in the form of benchmarking of selected 12 WUA'S on 7 major projects under different 5 Irrigation circles has been done in this year. Details about objectives, indicators selected, proformae framed for calling information of WUA, indicator values procurred etc is given in detail in chapter 6 of this report. This will be helpful to Project Authority and office bearers of WUA's for improving the performances of their WUA'S.

Maharashtra is the first State in India, which has introduced the Benchmarking technique for Irrigation Projects & now with our experience and CWC's follow-up other States are also adopting it.

The methodology and main performance Indicators for Benchmarking are adopted as per the guidelines issued by Indian National Committee on Irrigation & Drainage (INCID) in 2002.

The year wise indicators selected for benchmarking since 2001-02 along with their Domain are enlisted below:-

Year	Domain	Performance Indicator				
	1. System Performance	i) Annual irrigation water supply per unit				
2001-02		irrigated area				
	2. Agricultural Productivity	i) Output per unit irrigated area,				
	ii) Output per unit irrigation supply					

7

Year	Domain	Performance Indicator		
0004 00	3. Financial Aspects	i) Cost Recovery Ratio		
2001-02		ii) Total O&M cost per unit area		
		iii) Revenue per unit volume of water supplied		
		iv) Maintenance cost to revenue ratio		
		v) Mandays for O&M per unit area		
		 vi) Total O&M cost per unit volume of water supplied 		
	4. Environmental Aspects	i) Land damage index		
2002-03	1. Deleted Indicator	Maintenance Cost to Revenue Ratio		
	2.Additional Indicators	1. Potential Created and Utilised		
		Equity Performance		
2003-04	Additional Indicator	Assessment Recovery Ratio		
		a. Irrigation		
		b. Non-irrigation		
2004-05	No Change			
2006-07	1 Deleted	Mandays per unit area		
2007-08	No Change			
2008-09	System performance	New indicator 1 a, Annual Area irrigated per		
		unit of water supplied is added		

Initially, the exercise was conducted for 84 projects in 2001-02 with 10 indicators. The number of projects was increased to 254 in 2002-03 with 11 indicators. Instead of presenting the data of all these projects individually, an irrigation circle was considered as a unit for evaluation of performance. Here also, it was observed that some of the characteristics of projects under a circle are not identical and to make the comparison still on better grounds, from the year 2003-04, projects under a circle in a sub basin are grouped together and comparison is made with other projects in a particular plan group.

In carrying out the Benchmarking exercise, following categorization of irrigation schemes into similar types have been done for comparison.

a)	Type of control for Supply of water	Fixed proportional division, manual control, automatic control			
		"Manual Control" is applicable in this Benchmarking Exercise.			
b)	Method of allocation and distribution of water.	Supply-oriented arranged-demand, on demand The method applicable in this case is "on- demand."			
C)	Water Availability	Abundant, Scarce. Highly deficit to Abundant.			
d)	Water Source	Surface water, groundwater or both. Surface water is applicable			
e)	Size	Major, Medium, Minor. All sizes applicable			

Year:		No. of P	rojects.		No. of	Year of
	Major	Medium	Minor	Total	Indicators	publication
2001-02	30	26	28	84	10	March 2003
2002-03	49	142	63	254	11	March 2004
2003-04	49	143	69	261	12	March 2005
2004-05	49	144	69	262	12	February 2006
2005-06	49	144	69	262	12	March 2007
2006-07	49	144	69	262	11	March 2008
2007-08	48	145	69	262	11	March 2009

Details of year wise benchmarking done for irrigation projects are mentioned as below.

Note: RajaNala Project which was previously included in Major Project is now included as Medium Project as per Project Authority report.

262

12

69

1.1.0 Maharashtra at a glance

48

2008-09

Maharashtra occupies main portion of the Indian Sub-continent. The geographical location of Maharashtra is bounded between latitude 16.4° to 22.1° N and longitude 72.6° to 80.9° E and has an area of 307.71 thousand sq km, which is about 9.4 percent of the total geographical area of India. Maharashtra stands first amongst the major states in India in income & growth rate. The State has 720 km

145



March 2010

long coastline along Arabian Sea. The western hill ranges are almost parallel to this coastline. The State is divided into two physiographic regions of Konkan and rest of the State (Deccan Plateau). The Deccan Plateau spread over on the east side of *Ghat* has west-east slope. In general, the altitude of the plateau varies between 300 to 600 m. Maharashtra is bounded by Gujarat on north-west, Madhya Pradesh on north, Chhattisgadh on east and Andhra Pradesh, Karnataka and Goa on south.

1.2.0 Physiography

The State is divided into five major regions physiographically:

i) Konkan strip on western side (ii) Sahyadri ranges iii) Plateau on eastern side (iv) Hilly ranges of Satpuda and adjacent area on north and (v) Hilly and forest region of north-south Wainganga basin on East side of State.

1) Konkan Strip

The narrow strip of land extending from Damanganga basin in north to the border of Goa State in south is the Konkan. It has Sahyadri ranges on east and Arabian Sea on west. The Konkan strip is about 53 to 60 km wide and 500 km long along north-south. The widest stretch is about 100 km. Width decreases as one proceeds towards south. The region becomes hilly and altitude increases from the depressed coastline towards east.

2) <u>Sahyadri Ranges</u>

These continuous mountain ranges extend almost parallel to the western coastline. It is known as Western *Ghat*. The average height of Sahyadri in Maharashtra is 900 m. It is more in the north and diminishes towards south.

3) Eastern Plateau Region (Deccan Plateau)

The height of this plateau goes on diminishing from 600 m on western side to 300 m in the Wainganga basin on east. This region is formed from lava of igneous rocks. All the districts of Khandesh¹, Marathwada², Western Maharashtra and the western districts of Vidarbha³ fall in this region.

Satpuda Ranges and Tapi – Purna basin on North
 Satpuda hill ranges lie on the northern boundary of the State. This region is spread over in the districts of Amravati, Akola, Jalgaon and Dhule.

5) Eastern Region Consisting of Wainganga basin

Eastern region comprises of eastern side of the State and flat paddy field region lies along both the banks of the river at an elevation of about 300 m. On the

¹ Khandesh includes Dhule, Nandurbar & Jalgaon districts

² Marathwada includes Aurangabad, Jalna, Parbhani, Nanded, Osmanabad, Latur, Hingoli & Beed districts

³ Vidarbha includes Akola, Washim, Amravati, Yeotmal, Wardha, Nagpur, Bhandara, Gondia, Chandrapur, Buldhana & Gadchiroli districts.

eastern side of this flat region along the Maharashtra - Chhattisgadh boundary are the hills of different geological formations other than the Deccan Trap. Many eastern tributaries of Wainganga originate from this hill range. The height of this hilly plateau is around 800 m.

Detailed information with regard to river basins, availability of water resources, climate, rainfall, agro climatic zones, etc of Maharashtra is given in Appendix-VII

Rainfall during 2008-09

In the State on average the Rainfall starts from 7th June by South West monsoon. In the year 2008 the rainfall started from 6^h June 2008 and got spread throughout the state by 12th June. In the month of July excluding Satara, Kolhapur, Chandrapur and Gadchiroli districts the intensity of rainfall decreased in the rest of all the districts. In the month of July excluding east Vidharbh most of the districts experienced dry spell for more than two to three weeks. By the first fortnight of August there was heavy rainfall throughout the State.


In the state out of 33 districts (excluding Mumbai and Mumbai suburbs) 11 districts lesser than average rainfall (41 to 80%). 21 districts got average rainfall 81 to 119% and Only one district got more than 120% rainfall.

Taluka wise rainfall in the month of June, July, August, September and October were 87, 65,101,141, and 57% respectively. In monsoon there was an average rainfall of 91%. In State of total 355 talukas 126 talukas had 41 to 80% rainfall, 202 talukas had 81 to 119% rainfall, & 27 talukas had more than 120% rainfall.

1.4.0 Irrigation Development during Post-independence Period

Maharashtra State as of today came into existence in 1960. The increasing population was facing shortage of food grains. This has led to the need of increasing agricultural production. By giving priority to agricultural development, attempt has been made to achieve irrigation development in a planned manner.

Hardly, 0.274 Mha, irrigation potential was created in the State during preplan period i.e. before 1950. Agriculture has been the prominent occupation to provide food and fiber to the growing population of the State. Adequate, timely and guaranteed water supply is of paramount importance in agriculture production and irrigation development plays a key role in alleviating rural poverty. The State has





Executive Engineer in charge of the irrigation projects. The management circle headed by the Superintending Engineer controls three to four divisions. The regional head of the Superintending Engineers (four to five circles) is either Chief Engineer or the Chief Administrator in case of CAD projects.

The Superintending Engineers in-charge of irrigation circles are responsible for full utilisation of the water stored in reservoir and maintenance of public utilisation system, as well as recovery of water charges through their subordinate offices. The organisation chart of department is enclosed herewith on page no 18.

1.4.3 Crops Irrigated

Variation in the crops grown is significant within the regions as well as projects under region. Details of principle crops grown in different regions are categorised plan group wise and shown as below.

Region	Plan group	Principle crops grown
Eastern Vidarbha	Abundant & Surplus	Kharif Paddy, HW Paddy
Western Vidarbha	Normal	Cotton, Wheat, Gram, Sunflower, Orange
Marathwada	Normal & Deficit	Cotton, Wheat, Gram, Sunflower, G.nut, Sugarcane, Banana
Central Maharashtra	Normal	Rabi Jawar, Maize, Wheat, Bajara, Cotton, Vegetable, Grapes, Sugarcane, Banana
Western Maharashtra	Normal & Abundant	Maize, Wheat, Vegetable, Sugarcane,
Konkan	Abundant	Paddy, Vegetable

1.4.4 Management of Systems

The irrigation systems are constructed and mostly managed by the GOM. Operation and maintenance of irrigation projects is looked after by irrigation divisions, which are administratively controlled by circle office. GOM has taken a policy decision to supply water for irrigation through Water Users' Associations only. Accordingly the MMISF Act was passed by the Government in year 2005. Formation of Water Users' Associations in command areas of irrigation projects is in progress. Irrigation management of area under their jurisdiction is being transferred to them. Recently, a major project Waghad in North Maharashtra region is handed over to Federation of WUAs for irrigation management. The National Productivity Council, New Delhi under Ministry of Commerce and Industries, GOI has awarded National Productivity Award for 2000-01 & 2001-02 to Waghad & Katepurna projects in the State. Similarly Pench & Shekdari projects were awarded the National Productivity Award for 2002-03 & 2003-04. The Medium project Waghad from Nasik region got National Productivity Award for 2006-07, this award was given some months before. The award is given second time to this project. For innovative water management, Waghad project got prestigious ICID and WATSAVE awards.

To corroborate the process of handing over the culturable command area (668850 ha) of selected 286 projects to the WUAs within stipulated time frame, Maharashtra Water Services Improvement Project has been taken up with the help of World Bank


1.4.5 Area under modern irrigation methods

Area under drip & sprinkler irrigation in the State by March 2009 was 4.87 lakh ha And 2.23 lakh ha respectively. The region wise area under drip irrigation is as follows:

Sr.No.	Region	Area under Drip irrigation in ha. (up to March 2009)	Percentage
1	Konkan	12199	3
2	Nashik	196496	40
3	Pune	120298	25
4	Aurangabad	84993	17
5	Amravati	58970	12
6	Nagpur	13873	3
Maha	rashtra State	486829	100

Out of 486829 ha under drip irrigation, maximum area is in Nashik (40%). Drip irrigation is applied 90% under these following 8 crops i.e. Banana, Grapes, Sugarcane, Oranges, Pomegranate, Cotton, Mango & Vegetable crops. Out of total 486829 ha under drip irrigation, the area under Banana (92120ha) & grapes, (78765ha) is remarkably high.

1.5.0 Present Status of Irrigation Utilisation





In spite of various measures taken so far, there is a gap between potential created and utilized.

The overall reasons for less utilization are as follows

i) Low water yield in the reservoirs ii) Diversion of irrigation water to nonirrigation uses iii) Tendency of farmers to grow cash crops which are highly water intensive like sugarcane, banana iv) Low utilisation during kharif (Rainy) season v) Reduction in storage capacity due to silting vi) Lapses in assessment of the irrigated area in the command vii) Non accounting of irrigated area outside the command (influence area) viii) Poor maintenance of the infrastructure due to financial constraints ix) Non participation of beneficiaries in irrigation management.

Year wise data of potential created and actual utilisation is exhibited in graphical form above. From this information, it is clear that till the year 2004-05, actual maximum utilisation (canal+wells) was 48% of the potential created. Under utilisation has always remained a point of concern. Therefore, based on past experience, a special drive was taken at State level during the year 2006-07, in which circle wise targets for potential utilisation were fixed. Project Authority tried their level best to achieve the set goals. As a result, total actual potential utilization in the year 2006-07 has improved to 2.681 Mha (65% of potential created). In the year 2007-08 it has further improved to 2.764 Mha. For the year 2008-09 there is a slight decrease in area (0.032Mha) as the total actual potential utilization is to the tune of 2.732 Mha.






From the above table, it is observed that, due to satisfactory rainfall in most of the parts in the State, area irrigated in Kharif season & TS has increased as compared to last year (2007-08). Slight decrease in area is seen under Rabbi, HW & perennial crops at State level.

1.6.0 Participation of Beneficiaries in Water Resources Management

National Water Policy 2002 and Maharashtra State Water Policy 2003 advocate Participatory Irrigation Management. In view of these, water users associations were setup in command areas of various projects in different parts of the State. By the end of 2008-09 in all 1235 WUAs were in full operation with operational area of 4.16 lakh ha. Besides this the number of WUAs which have been registered and entered into agreement during 2008-09 was 1380 covering an area of about 5.02 lakh ha.

Looking at the slow pace of PIM in last decade and to bridge the gap between irrigation potential created and its actual utilization and to optimise the benefits by ensuring proper use of surface & ground water by increased efficiency in distribution, delivery, application and drainage of irrigation systems and for achieving this objective, to give statutory recognition to the constitution & operation of WUAs, an act has been passed by the State legislature. The act is known as "Maharashtra Management of Irrigation Systems by Farmers Act, 2005". As per this act, all the beneficiaries in the command of a distributaries / minor will become the members of WUA, once the area is notified under the act.



Attach orginasation chart

CHAPTER - 2

Benchmarking of Irrigation Projects

Benchmarking can be defined as a systematic process for securing continual improvement through comparison with relevant and achievable internal or external norms and standards.

2.1.0 Background

This is the eighth consecutive report of benchmarking of irrigation projects in the State with 262 projects and 12 indicators. The plan group wise number of projects selected for benchmarking during 2008-09 is as follows.

Sr.		Nagpur, Amravati n Group Region		Pune, Konkan Region		Aurangabad, Nashik			Total		
No	Plan Group					Region			Projects		
		Major	Medium	Minor	Major	Medium	Minor	Major	Medium	Minor	-
1	Highly Deficit				1	11	3	-	16	4	35
2	Deficit	4	10	13				10	44	18	99
3	Normal	4	13	5	6	1	2	10	16	8	65
4	Surplus	3	22	4							29
5	Abundant	2	2	1	8	10	11				34
	Total	13	47	23	15	22	16	20	76	30	262

Grand Total: 262

2.2.0 About this report

Following 12 indicators are selected for benchmarking in 2008-09.

Sr No	Indicator No	Title Of Indicator		
		System Performance		
1	1	Annual Irrigation Water Supply Per Unit Irrigated Area		
	1a	Annual Area irrigated per unit of water supplied		
2	2	Potential Created And Utilised		
		Agricultural Productivity		
3	3	Output (Agricultural Production) Per Unit Irrigated Area		
4	4	Output (Agricultural Production) Per Unit Irrigation Water		
		Supply		
	1	Financial Aspects		
5	5	Cost Recovery Ratio		

6	6	Total O&M Cost Per Unit Area
Sr No	Indicator No	Title Of Indicator
7	7	Total O&M Cost Per Unit Volume Of Water Supplied
8	8	Revenue Per Unit Volume Of Water Supplied
9	12(l)	Assessment Recovery Ratio Irrigation
10	12(NI)	Assessment Recovery Ratio Non Irrigation
		Environmental Aspects
11	10	Land Damage Index
		Social Aspects
12	11	Equity Performance

The report is available on websites www.mahawrd.org & www.mwrdc.org

2.3.0 Methodology

The data presented in this report is based on information collected from each of the circle in-charge of the project.

The following process was used in development of this report.

- Irrigation projects are selected, representing the main geographical regions of State and of categories viz. major (CCA more than 10000 ha), medium (CCA more than 2000 ha and below 10000 ha) and minor (CCA less than 2000 ha).
- For achieving consistency in monitoring & evaluation, same projects which are considered for benchmarking during 2007-08 are considered in year 2008-09.
- Data is collected in revised spread sheet containing 30 columns from the concern Project Authority and analysed in MWRDC office. An explanatory note containing detailed instructions about working out the figures of different indicators was issued to field officers.
- The data about water use and area irrigated is co-related with water accounts (2008-09) of relevant projects.
- The presentation for every indicator is done with past-past (5 year average), recent past (2007-08) and present year (2008-09) in order to compare the performance with predecessors as well as own performance of last year.

- The draft report is scrutinised in MWRDC, Aurangabad & Mantralaya, Mumbai.
- Reasons for deviation from last year's performance and State norm are called from each circle.

Looking at the large number of projects, for better monitoring, the analysis is carried out considering irrigation circle as a unit and projects therein with similar plan groups of sub basins. Performance of projects in a circle against each indicator is collective performance as given in Chapter 4.

- Based on performance during the year 2008-09, indicator wise average performance is evaluated for the plan group of circles under consideration, setting aside the exceptionally high/low values.
- State targets for indicator No III & IV are set as per plan group. However for other Indicators, state target value is common for all plan groups. The targets are different for major, medium & minor projects for indicator no. I, VI, VII, & VIII.
- For benchmarking of projects at circle level, each circle has defined its own targets considering specific conditions of project areas, crop type, condition of canal system etc.
- Target values are revised with experience gained in the process.
- For financial indicator of output per unit irrigated area and output per unit irrigation water supply, fixed prices of year 1998-99 are considered to obviate effect of price rise.
- Some circles are not having major, medium or minor projects; therefore, only relevant circles are shown in graphs of each indicator. Thus total of circles may not tally to 21 in each graph, for example for major projects category, there are only 15 circles.
- At a glance evaluation of performance of all projects in Maharashtra State with respect to each indicator is also given in Chapter 4.
- There are 2940 completed minor irrigation projects in the State. Therefore, it has been decided to carryout benchmarking and monitoring of minor projects at circle level itself. To get an idea about performance of minor projects, some

sample schemes which were considered in last year's report are analysed and included in this report.

 Actions taken by GOM for improvement of performance are included in Chapter 5.

2.4.0 Overview of Irrigation Projects

An overview showing details such as sub basin, designed and actual storage during the year, command area, crops grown, etc. is enclosed as **Appendix No.III**

2.5.0 Benchmarking of WUA

Till June 2008, potential to the tune of 4.486 Mha has been created on state level projects. National Water Policy and Maharashtra Water and Irrigation Commission (1999) have recommended the active participation of farmers in Irrigation Water Management. Water Resources Department has also concentrated its efforts in that direction.

In response to above recommendations, an act namely MMISF (Maharashtra Management of Irrigation System by Farmers) - 2005 has been passed in the State assembly. Against the total potential creation of 4.486 Mha, potential to the tune of 0.416 Mha is handed over to 1235 WUAs.


At present, 286 projects (0.67Mha area) selected under MWSIP to which the act is made applicable, are financially aided by the World Bank. The cost of the project is about 1700 crores.

In view of the huge capital investment in construction of projects as well as in rehabilitation of canal systems along with intention of securing the advantage of benchmarking, benchmarking of WUAs was felt necessary. Accordingly the issue of Benchmarking of WUA was under consideration for last two years.

To initialise the process, 9 Indicators feasible to determine the performance of individual WUA are designed and data in prescribed proforma was received from selected 12 WUA's on 7 Major projects.


Out of 12 WUAs only two WUAs on Mula project are functioning under MMISF Act 2005. Rest of 10 WUAs are functioning under co-operative Act.

Chapter 4 Overall status of Benchmarked projects in Maharashtra Indicator wise Performance of Maharashtra State for the Years 2002-03 to 2008-09



Indicator – I: Annual Irrigation Water Supply per Unit Irrigation Area:


Annual Irrigation water supplied for major projects in Maharashtra state is higher in 2008-09 i.e. 10253 cum/ha as compared to the same in the year 2007-08 i.e. 8289cum/ha. And for medium project it is lower in the year 2008-09 compared to previous year 2007-08. For minor project the water use is less in the year 2003-04 i.e. 5945 cum/ha. and maximum in the year 2005-06 i.e. 9738 cum/ha and for the year 2008-09 it is on higher side i.e. 6575 cum/ha.




Indicator – I a: Annual Area Irrigated per unit of water supplied: Unit: ha/Mm³

The area irrigated per unit of water supplied in 2008-09 is 98 ha./Mm3 which is less than last year value i.e. 121 ha/Mm3 for Major projects. In case of Medium project indicator value is 134 ha/Mm3 for 2008-09, which is more than last year (2007-08) value


i.e. 118 ha/Mm3. For Minor irrigation projects indicator values for the year 2008-09 is 152 ha./Mm3 which is more than last years value i.e. 145 ha./Mm3.







For Major Projects the maximum utilised potential was in the year 2006-07. The utilised potential is increasing yearly from 0.46 in the year 2002-03 to 0.91 in the year 2006-07. The ratio is marginally less (0.80) for current year. For medium projects the ratio in the year 2008-09 is 0.74. For minor Projects utilised potential was 0.42 in the year 2003-04 and it is improving for last four years and 0.89 in the year 2006-07, it has slightly decreased for the current year i.e, 0.63.




Indicator-III: Output per Unit Irrigated Area:

Unit: Rs/ha


For Major Projects agricultural output shows variations in last five years. Maximum agricultural output of Rs. 36730/ha is in the year 2008-09 and minimum of Rs. 26758/ha is in the year 2003-04. For medium project the agricultural output of Rs.42613/ha was maximum in 2005-06 and minimum of Rs 25358/ha in the year 2004-

05. For Minor Projects agricultural output is maximum of Rs. 36176/ha in 2007-08 and minimum of Rs. 21015/ha in the year 2006-07.




Indicator – IV: Out Put per Unit Irrigation Water Supply: Unit: Rs/Cum

For Major Project the output per cum was Rs. 2.93/cum in the year 2002-03 and went on increasing year by year and reached to a maximum of Rs 5.25/cum in the year 2008-09. For Medium Projects maximum output of Rs. 4.84/cum is in the year 2008-09. For minor projects the output of Rs 3.84/cum for the year 2008-09 year and minimum of Rs. 3.75/cum in the year 2006-07.








For major projects the ratio for the year 2008-09 is 0.95. For medium projects the ratio was in between 0.30 to 0.64 for last five years, for current year the ratio is maximum i.e., 0.39 In case of Minor Projects ratio was in between 0.28 to 0.35 for four years. But in 2005-06 the ratio was maximum i.e., 0.83, for this year the ratio is 0.23.


Indicator-VI: O & M Cost Per Unit Irrigated Area:

Unit: Rs/ha

Unit: Rs/Cum



For Major Projects the O & M Cost Per Unit Area is on higher side of state target for previous years it was nearly three times the state target except in the year 2006-07, it is Rs 3687/ha in the current year. It is due to excess expenditure on maintenance. In Medium Project O & M expenditure increased from the year 2002-03 to 2008-09 consistently, For Minor Projects the O & M Cost per Unit Area was minimum of Rs. 981/ha in the year 2002-03 and increased year by year to a maximum of Rs. 5035/ha in the year 2005-06.For the current year it is Rs 3574/ha.




Indicator – VII: O & M Cost Per Unit Water Supply:


For Major Projects O & M Cost per Unit Water Supply ranges between Rs. 0.18/cum to Rs. 0.40/cum from year 2002-03 but for the current year it is Rs. 0.28 /cum. For Medium Projects excessive O & M expenditure resulted in poor performance for last five years. It is Rs.0.37/cum for current year. For Minor projects the O & M Cost per Unit Water Use was in between Rs. 0.16cum to Rs. 0.9 for five years. This year it is Rs. 0.45/cum.

Indicator – VIII: Revenue Per Unit Water Supply:

Unit: Rs/cum




For Major Project in Maharashtra State, Revenue Per Unit Water Supply, for last five years, ranged from Rs. 0.20/cum to Rs. 0.24/cum. This year it has increased to Rs.0.3/cum. For medium project the revenue was Rs. 0.07/cum in the year 2002-03 and went on increasing to Rs. 0.15/cum in the year 2005-06. In 2006-07 it comes to Rs. 0.13/cum, it is Rs 0.12/cum for current year. For Minor Projects revenue per unit water use was in between Rs. 0.04/cum to Rs. 0.11/cum. For current year the ratio is Rs 0.05/cum.






For Major Project Assessment Recovery Ratio was minimum in the year 2005-06 i.e. Rs. 0.22. But in the year 2006-07 it increased to 0.49 due to improvement in recovery of irrigation water charges. It has slightly decreased to 0.37 for the year 2008-09. For Medium Projects ratio shows ups and downs year wise. It was 0.22 in the year 2003-04 and increases to 0.67 in 2005-06, for the current year it is 0.33. For Minor Project Assessment Recovery Ratio was in between 0.43 to 0.52 for four years but in 2005-06 it was 0.81, for the current year it is 0.56.



Indicator – XII: Assessment Recovery Ratio (Non Irrigation): Unit: Ratio

For Major projects the ratio for the last six years is between 0.81 to1.09, for the current year it is 0.73. For medium projects the ratio is between 0.64 to 1.85, for the current year it is 0.79. In minor projects the ratio is in between 0.40 to 1.07, for the current year it is 0.79.



Abundant

CADA Pune

SIC Sangli

TIC Thane

CIPC Chandrapur

Observations and conclusions **Major Projects**

Indicator I: Annual Irrigation Water Supply per Unit Irrigation Area (cum/ha)

Highly Deficit Plan group:

CADA Solapur: In Bhima (Ujjani) project the overall performance is 7906 cum/ha, however, it is slightly more than the state norm of 7692 cum/ha. The water use in this year is reduced compared with last year (9474 cum/ha)

Deficit Plan group:

AIC Akola: Annual irrigation water use on projects (Katepurna & Nalganga) under Akola Irrigation Circle was 6946 cum/ha. If Katepurna and Nalganga projects are considered individually, no water use on Katepurna due to less storage but on Nalganga per unit area irrigated is 6946 cum/ha which is close to the state norm.

BIPC Buldhana: Wan project is the only major project under BIPC Buldhana under this plan group. Water use per unit area irrigated was 13741 cum/ha which is very high than the state norm and the last year performance. As repeatedly said previously, Project authorities are required to adhere strictly to the guide lines issued about irrigation management for improvement in performance.

CADA Aurangabad: In Jayakwadi project Stage-I (PLBC) the water use per unit irrigated area is 13238 cum/ha., which is 1.75 times higher than State norms. Efforts are required at field level to restrict the water use within the stipulated norms to achieve State target.

CADA Beed: In Majalgaon project the water use per ha. is increased from 12824 to 15227 cum/ha as compared to last year and it is very higher than State norms. In this year though area irrigated is slightly increased by 486 ha. water utilization is increased by 43 Mcum resulting into higher utilization of water. Project authorities are advised to pay more attention for improvement in performance because in this year though perennial crops are reduced from 59 to 35% water use is increased which is not desirable.

In Manjra project the water use per hectare has increased from 8208 to 9552 cum/ha. As compared to last year, this is due to15% increased water utilization & 5% reduction in area irrigated (67 to 62%) under perennial crops in this year.

In Lower Terna project the water use has increased from 6619 to 7186 Cum/ha. This is due to 20% increase in water use but only 10% increase in area irrigated though it is well within the State norms.

In Javakwadi project Stage-I (PRBC) the water use per unit irrigated area has increased from 15976 to 20119 cum/ha. i.e. more than 2.5 times of state norms, resulting into overall water use of this circle increase from 11918 to 14090 cum/ha.

CADA Jalgaon: In Girna project, the water use per unit irrigated area is increased from 13846 cum/ha (2007-08) to 14553 cum/ha (2008-09) and it is 1.9 times more than the state target. Project authorities are required to take efforts for improvement in the performance duly preparing the action plan.

CADA Nashik: In Chankapur project, the annual water use per unit irrigated area is lowered from 6119 cum/ha (2007-08) to 5799 cum/ha (2008-09) and has not exceeded the state norm.

NIC Nanded: In Manar project the water use per unit irrigated area is increased from 8631 to 9169 cum/ha. There is decrease in irrigated area from 12988 ha to 918 ha. As compared to last year that also from reservoir lifts only, as the availability of live storage is 28% no irrigation by canal flow. Project authorities are advised to pay more attention towards water use by reservoir lift In Vishnupuri project water use has decreased from 7978 to 7803 cum/ha. This shows improvement.

In Purna project the water use has drastically decreased from 15705 to 10835 cum/ha as compared to last year but still it is 1.2 times more than the State norms. As per field officer's report that embankment work of the canal was carried out with available material and without hearting zone resulting heavy leakages through banking work and from structures also, about 25 to 30% of released water in canal thus indirectly regenerate wells & nallas in command area of the project increasing total utilized potential.

Normal Plan Group:

AIC Akola: In case of Pus Project, water use per unit irrigated area was 14381cum/ha. which is twice the state norm value. More attention of Project authorities are required in improvement of performance.

CADA Jalgaon: In Hatnur project, though the water use per unit irrigated area is lowered from 12194 cum/ha (2007-08) to 8499 cum/ha (2008-09) it is 1.1 times more than the state target.

CADA Nagpur: On Lower Wunna Project water use (9663 cum/ha.) during the irrigation year as compared to last years 16837 cum/ha. As compared to the state norm it is 26% more.

CADA Nashik: In Bhandardara project, the water use per unit irrigated area is increased from 12048 cum/ha (2007-08) to 13055 cum/ha (2008-09) which is 1.7 times higher than the state target. As per Project authorities, though this project is for eight monthly cropping pattern, it is obligatory to fulfill the demand of water for sugar cane. Also efforts are being taken by field officers to reduce water use per ha duly taking necessary remedial measures i.e. desilting of canal, increasing height of banks, minimizing leakages and supply of water by volumetric basis duly forming water users associations.

In Kadawa project, the water use is consistently more than the state target. As per Project authorities, more water use/ha is due to more conveyance losses in the canal system. Remedial measures are being taken in hand i.e. selective lining, pitching to improve the performance.

In Mula project, the water use/ha is 13428 cum/ha, which is on (1.7times) higher than the state norm. As per Project authorities, though this project, at present, is having eight monthly cropping pattern, it is obligatory to supply the water to sugar cane as per demand of cultivators as there are four sugar factories in the command. Efforts are being taken by the field officers to lower the water use/ha by training the farmers to reduce the sugarcane and also to avoid flood irrigation.

In Waghad project, the water use/ha is 10230 cum/ha, which is increased than that of last year (8853 cum/ha) and it is on higher than the state norm. As water is supplied fully on volumetric basis on this project, more efforts are required at field level to use the water economically.

In Gangapur project, the water use per unit area is lower than the state target (6997 cum/ha.)

In Darna project, the water use per unit irrigated area is 5639 cum/ha. **CADA Pune:** In Kukdi Project the annual irrigation water supply per unit area is 11850 cum/ha. The water utilization has remarkably increased this year as

compared to state norms. In Ghod Project the water utilization for irrigation is 9512 cum/ha. There is slight increase in value as compared to last year value of 8491 cum/ha. It is also above the state norms.

CIPC Chandrapur: Actual water use per unit area irrigated on Bor project is 17824 cum/ha, which is 232% of the state norm. There is no major change in performance level as compared to last year performance. (18081 cum/ha) According to field officers, old canal system of Bor Project requires major repairs and is responsible for poor performance.

NIC Nanded: In Upper Penganga Project the water use per unit irrigated area has decreased from 19785 to 13064 cum/ha. as compared to last year. The Project authorities are required to take hard efforts to improve the performance by judicious use of water to achieve the state target of 7692 cum/ha.

PIC Pune: In Khadakwasla Project the water utilization is 7989 cum /Ha. This is better than the last year's 9352 cum/ha. Performance in N.L.B.C. the water utilization is 12615 cum/ha. This is less than last year but above the state target performance. It is due to heavy leakage through masonry structures on canals. In NRBC the performance improved as compared to last year. The improvement is achieved because of repairs of canal system. In Pawna Project the water utilization is 18647 cum/ha. which is three times of last year performance (6010 cum/ha). The Project authorities are advised to do needful to reduce the water utilisation per unit area.

UWPC Amrawati: On Upper Wardha project, the rate of water use per unit area irrigated (10177 cum/ha) is considerably high than the state norm, it is 132 %. It appears that Project authorities had taken positive steps for improving the performance but more efforts are required to achieve state norms.

YIC Yeotmal: Water use in Arunavati project was high (9749cum/ha.) as compared to the state norm (127%). Project authorities should take positive efforts for satisfactory performance.

Surplus Plan Group:

CADA Nagpur: Overall performance of the projects under this circle is reduced from 11514 cum/ha up 9349 cum/ha. The projects are Pench, Itiadoh & Bagh. Compared to last year water use per unit area is increased & it is more than the state target value (7692 cum/ha.)

Abundant Plan Group:

CADA Pune: In Krishna Project the water utilization for irrigation is 16784 cum/ha. It is increased than last year 11585 cum/ha. The water utilization is more than state norms. The Field Officers are advised to do needful to reduce the water utilization per unit area.


CIPC Chandrapur: Ninety percent of total water use on Asolamendha & Dina projects under CIPC Chandrapur is for kharif paddy crops. These projects lie in assured rainfall zone, obviously irrigation is in the form of protective irrigation.

Overall performance of Asolamendha & Dina projects is 6167 cum/ha. As compared to the last year, water use increased to some extent & less than the state value target.

SIC Sangli: Water use for irrigation in different projects under this circle against State norm (7692 cum/ha) are as under; Overall average water use on Radhanagri, Tulsi, Warna , & Dhudhganga is (9173).Over all water use on all the projects is comparatively more than the State norm. Due to irregular supply of electricity, at night time there are frequent operations of starting and

stopping which results in loss of water. Accurate measurement of water lifted for irrigation is not possible. Compared with the last year, water supply is 18 % more & it is more than the state norms.

TIC Thane: Water use for irrigation in different projects under this circle against State norm (7692 cum/ha) are as under; Over all water use on Bhatsa, Kal-Amba, & Surya is 26657cum/ha. it is more than triple the state norm. Reasons for more water use, put forth by project authorities are as under.-Steep Geographical topography, water loss is more.-Mostly rice crop is taken, & water requirement for rice crop is 5 to 6 times more. Efforts are being made to reduce rate of water use by promoting farmers by developing horticulture in command area. Compared with last year, it is increased to some extent.



Chandrapur

SIC Sangli

TIC Thane

Indicator I a: Annual Area irrigated per unit of water supplied (ha/Mm3)

Highly Deficit Plan group:

CADA Solapur: Overall area irrigated per unit of water supplied is 126 ha/Mm3 in this year. Compared with last year it is increased by 19% & it is just below the state target

Deficit Plan group:

AIC Akola: The area irrigated per unit of water supplied is satisfactory during this year in Nalganga project and water is not available for irrigation in Katepurna project.

BIPC Buldhana: The area irrigated per unit of water supplied is very low as compared to past years as well as state norm in Wan project reduction in irrigated area is the main reason for low ISP.

CADA Aurangabad: In Jayakwadi (PLBC) area irrigated per unit of water supply is very low i.e. only 73 ha/Mm3 which is nearly 50% of state target. Even though out of 98117 ha. area is irrigated 14943 ha. area is on reservoir lift. This shows that project authorities or not paying attention towards the water use either by canal flow or reservoir lift.

CADA Beed: In Jayakwadi (PRBC) area irrigated per unit of water supply is reduced from 84 ha/Mm3 (2007-08) to 71 ha./Mm3 which is far below the state target. Proper watch on water use is needed to improve this indicator.

CADA Jalgaon : The area irrigated per unit of water supplied is low than the state target because of 50 to 60 years old canal system under Jamda weir old pervious strata in tail reach in Girna project.

CADA Nashik: The area irrigated per unit of water supplied seems on higher side of the state norm due to fewer rotations (2 Nos) in Rabi season under Chnakapur project.

NIC Nanded: There is improvement to some extent in area irrigated per unit of water supply compared to last year. But still it is below the state target.

Normal Plan Group:

AIC Akola: Project authorities asked to concentrate to increase irrigated area & minimize the water losses.

CADA Jalgaon: The area irrigated per unit of water supplied is lower than the state norms due to following reason.

- i) Irrigation on seated area
- ii) No Night irrigation
- iii) Indicator to irrigation on wells instead of flow irrigation.

CADA Nagpur: Area irrigated per unit of water supplied on lower Wunna project during this year is 103 ha/Mm3 which is below the State Norms.

CADA Nashik: The area irrigated is low as compared to state target due to more conveyance losses in Bhandardara & Kadawa projects.

CADA Pune: Overall area irrigated per unit of water supplied is 89 ha/Mm3 in this year. Compared with last year it is decreased by 10% & it is 32% below the state target

CIPC Chandrapur: Area irrigated per unit of water supplied during this year is 77 ha/Mm3 which is 50% of the State Norms.

NIC Nanded: In Upper Penganga project though the indicator value is improved (77 ha/Mm3) in 2008-09 compared to last year value. (51 ha/Mm3) though it is for below the state target.

PIC Pune: Overall area irrigated per unit of water supplied is 112 ha/Mm3 in this year. Compared with last year it is increased by 11% & it is 14% below the state target

UWPC Amrawati: The area irrigated per unit of water supplied is low on Upper Wardha project. Project authorities asked to concentrate increase irrigated area & minimize water losses.

YIC Yeotmal: On Arunawati project the area irrigated per unit of water supplied is 103 ha.Mm3.

Surplus Plan Group:

CADA Nagpur: More area (107 ha/Mm3) is irrigated per unit of water supplied as compared to last years value (87 ha/Mm3) under the projects of this circle.


Abundant Plan Group:

CADA Pune: Overall area irrigated per unit of water supplied is 60 ha/Mm3 in this year. Compared with last year it is decreased by 31% & it is 54% less than the state target

CIPC Chandrapur: Comparatively less area (162 ha/Mm3) is irrigated per unit of water supplied as compared to last year (183 ha/Mm3) under the project of this circle.

SIC Sangli: Overall area irrigated per unit of water supplied is 109 ha/Mm3 in this year. Compared with last year it is decreased by 15% & it is 16% below the state target

TIC Thane: Overall area irrigated per unit of water supplied is 38 ha/Mm3 in this year. Compared with last year it is decreased by 12% & it is 77% less than the state target



Plan group	Circle	FY Avg	LY 2007- 08	TY 2008-09	Past Max	Past Min	AVG Per	State Target
Highly	Oncie	Alg	00	2000 03	max		1 01	Otate Target
Deficit	CADA Solapur	0.53	0.50	0.58	0.76	0.15	0.58	1
Deficit	AIC Akola	0.22	0.13	0.48	0.63	0.13		
	BIPC Buldhana	0.35	0.30	0.33	0.51	0.28		
	CADA Abad	0.69	1.27	1.12	1.27	0.00	0.99	1
	CADA Beed	0.30	0.49	0.69	0.50	0.00		
	CADA Jalgaon	0.78	1.01	0.75	1.19	0.00		
	CADA Nashik	0.77	0.89	1.00	6.14	0.42		
	NIC Nanded	0.85	0.72	1.50	1.33	0.61		
Normal	AIC Akola	0.53	0.27	0.45	0.76	0.00		
	CADA Jalgaon	0.56	0.46	0.58	1.77	0.24		
	CADA Nagpur	0.65	0.82	0.77	0.88	0.27		
	CADA Nashik	1.05	1.43	1.53	1.56	0.56		
	CADA Pune CIPC	0.98	1.15	0.99	1.55	0.60	0.77	1
	Chandrapur	0.40	0.39	0.37	0.45	0.38		
	NIC Nanded	0.67	0.59	1.45	4.00	0.51		
	PIC Pune UWPC	1.28	1.87	1.31	1.87	0.67		
	Amravati	0.31	0.47	0.17	0.47	0.21		
	YIC Yavatmal	0.21	0.24	0.07	0.26	0.00		
Surplus	CADA Nagpur	0.84	0.94	0.66	0.94	0.77	0.66	1
Abundant	CADA Pune CIPC	0.96	1.03	1.26	1.29	0.71		
	Chandrapur	1.04	0.96	0.89	1.44	0.95		
	SIC Sangli	0.50	0.58	0.68	0.58	0.40	0.81	1
	TIC Thane	0.39	0.41	0.39	0.61	0.25		

Indicator II: Potential created and utilized (Ratio) Highly deficit Plan group:

CADA Solapur: In Bhima (Ujjani) Project, utilized irrigation potential is 50%. Performance is 26%less than last year. Large percentage of the potential utilized, is from river lifts, and reservoir lifts. More efforts are needed to utilize the potential of canals.

Deficit Plan group:

AIC Akola: Actual potential utilization on Katepurna and Nalganga project was 0% and 73% respectively.

BIPC Buldhana: In case of Wan Project, potential utilization is 33% of effective potential created. There appears to be no improvement over its last year's performance 30%) though the 88% storage was in the project.

CADA Aurangabad: In Jayakwadi project (PLBC) the ratio has decreased from 1.27 to 1.12.

CADA Beed: In all four major projects viz. Majalgaon, Manjra, Lower Terna & PRBC the over all ratio is below State norms. The average value of indicator is 0.69 which has increased over last year's value 0.49. PRBC has increased from 0.33 to 0.96 as compared to last year affect overall improvement in indicator value of the circle.

CADA Jalgaon: In Girna project, 75% effective potential is utilised in this year.

CADA Nashik: In Chankapur project, full effective potential is utilised in this year.

NIC Nanded: In Vishnupuri & Purna projects the ratio is 1.34 & 2.3 respectively whereas in Manar due to lesser availability the ratio is very less i.e. 0.22, though overall average performance of circle is increased from 0.72 to 1.5. This shows that the irrigation in command area of projects through wells & nallas is more than that of canal flow & reservoir lift. Project authorities are advised to be very watchful in measuring irrigated area of respective source in time to assess accordingly as it has been observed from the annual accounts of the projects submitted that maximum Bhusar crops are irrigated on wells & nallas which gives no revenue to Government.

Normal Plan Group:

AIC Akola: Actual potential utilization on Pus project was 45%. It appears to be better performance compared to last year performance 27%) &less than past five years average performance (53%).

CADA Jalgaon: In Hatnur project the utilisation is improved from 0.46 to0.58 in this year.

CADA Nagpur: The ratio figure of this indicator is 0.77. It is 23% less than the state target value & 5% less than the last year value.

CADA Nashik: All major projects except Darna have achieved the state norm.

CADA Pune: In Kukadi Project the utilized potential is 77%. It shows decrease in performance since last year by 23%. In Ghod Project the ratio utilized irrigated potential with effective created potential comes to one.

CIPC Chandrapur: The ratio value of this indicator is 0.37. It is 63% less than the last year value.

NIC Nanded: In Upper Penganga Project the ratio has increased from 0.59 to 1.45.

PIC Pune: In Khadakwasla Project the ratio comes to 1.00 as that of last year performance. In N.R.B.C & N.L.B.C. the ratio comes to 1.00 as compared to 1.00 of last year value. In Pawana Project the ratio decreased from 0.44 of last year to 0.37 this year still it is below the state norms. The field officers are advised to take efforts for improving the performance.

UWPC Amaravati: Potential utilization during year 2008-09 was very low (17%) as compared to last year performance (47%).

YIC Yeotmal: Actual potential utilization on Arunavati project (7%) during the year 2008-09.

Surplus Plan Group:

CADA Nagpur: The ratio figure of this indicator is 0.66. It is 44% less than the state target value. As. compared with last year; it is decreased to some extent.


Abundant Plan Group:

CADA Pune: In Krishna Project the ratio comes to 1.26 this year which is same as compared to last year.

CIPC Chandrapur: The ratio figure of this indicator is 0.89. It is 11% less than the state target value & decreased by 8% than the last year value.

SIC Sangli: The average ratio of utilized irrigation potential to effective created potential in different projects under this circle is 0.68, projects are Radhanagri, Tulsi, Warna & Dhudhganga. On Dhudhganga project canal system is under progress, hence potential ratio is lower. Compared with last year, little improvement in utilization of potential created is observed to some extent.

TIC Thane: The average Ratio figure of utilized irrigation potential to effective created potential in different projects under this circle is 0.39. Major projects are Bhatsa, Kal-Amba & Surya. The ratio is decreased to some extent, Overall performance is below State norm. Sincere efforts & improvement is necessary to some extent in this regard.



Diaman	O'me Le	FY	LY	TY 2008-	Past	Past		State
Plan group	Circle	Avg	2007-08	09	Max	Min	AVG Per	Target
Highly		40040	44770	40000	50074	44007	43666	04000
Deficit	CADA Solapur	46642	44770	43666	52374	41367		21000
Deficit	AIC Akola	33709	41632	17633	42150	16658		
	BIPC Buldhana	10952	14619	20593	14619	6979		
	CADA Abad	25981	30463	24170	30463	13126		
	CADA Beed	33052	22571	20369	47369	8580	20051	23000
	CADA Jalgaon	16103	15465	16454	19250	13334		
	CADA Nashik	33314	22827	21952	54857	21710		
	NIC Nanded	23643	20320	19187	35801	15545		
Normal	AIC Akola	28918	60864	52858	60864	0		
	CADA Jalgaon	55202	36315	53560	79686	36315		
	CADA Nagpur	11246	11485	13147	12892	9409		
	CADA Nashik	45225	68973	66420	68973	22548		
	CADA Pune	27874	19262	23447	45757	19262		
	CIPC						00774	
	Chandrapur	20143	24650	23228	24650	17535	23774	26000
	NIC Nanded	28126	24312	21749	39808	21803		
	PIC Pune	30911	34583	30712	36834	20062		
	UWPC							
	Amravati	25683	26050	26294	37535	18719		
	YIC Yavatmal	20363	25153	27839	25153	0		
Surplus	CADA Nagpur	25504	27902	46835	29214	22058	46835	25000
Abundant	CADA Pune	23208	23352	25026	26705	19599		
	CIPC							
	Chandrapur	24692	24500	24500	25904	24261		
	SIC Sangli	52580	56190	55495	64516	40936	28369	32000
	TIC Thane	42887	43172	35582	48919	38006		

Indicator III: Output per Unit Irrigated Area (Rs./ha) Highly Deficit Plan Group:

CADA Solapur: In Bhima project, Agricultural output is Rs 43666/ha. Overall performance is very good. Due to more sugarcane crop percentage in this project the out put is more than state norm.

Deficit Plan Group:

AIC Akola: On Nalganga Project, out put rate achieved was Rs 17633/ha. which is low than the state norm though the cash crops were over the 40% area.

BIPC Buldhana: Though 5% cash crops, &1.7%perennial crops on Wan Project output per unit area irrigated was 20% low of the norm (Rs20593). **CADA Aurangabad:** On PLBC the agricultural out put has decreased from Rs. 30463 to 24170/ha as compared to last year.

CADA Beed: In three projects namely Majalgaon, Manjra & Lower Terna agricultural output has slightly decreased compared to last year where as in PRBC out put fall down from 21159 to 11195 Rs/ha. which affect overall performance of the circle.

CADA Jalgaon: In Girna project, output/ha is increased from Rs. 15465/ha (2007-08) to Rs. 16454/ha (2008-09) which is about 72% of the state norm.

CADA Nashik: In Chankapur project, the output per ha is reduced from Rs. 22827/ha to Rs. 21952/ha which is just near the state norm.

NIC Nanded: In the projects viz. Manar, Vishnupuri & Purna the agricultural out put is Rs.18977/ha, Rs 22847/ha & Rs 17635/ha.respectively which it is still below state norms.

Normal Plan Group:

AIC Akola: Output observed on Pus Project (Rs.52858/ha) was more than the state norm of Rs.26000 per ha irrigated area. Oil seeds 5%, cash crops 8% &perennial crops 4% may be the responsible for appreciable increase. **CADA Jalgaon:** In Hatnur project, the output /ha is increased from Rs. 36315/ha (2007-08) to Rs. 53560/ha (2008-09) and it is on higher side of the state norms.

CADA Nagpur: In case of Lower Wunna project, output per unit area irrigated was Rs 13147/ha. which shows increase in performance as compared to last year performance of Rs. 11485 /ha. Still out put is low compared to the state target (Rs.26000 /ha) and other projects under this circle.

CADA Nashik: In all the projects, the output/ha is above the state norm. **CADA Pune:** In kukadi Project the output is Rs. 22957/ha. It is increased than last year performance but still below the state target. In Ghod Project the output increased from Rs 21284/ha. to Rs 21717./ha.this year but, it is still below the state norms.

CIPC Chandrapur: Output per unit area on Bor Project (Rs.23228/ha) has been decreased as compared to its performance in 2007-08 (Rs 24650/ha). Performance is low compared to the state norm probably due to rabbi seasonal crops mainly gram with meager perennial crops (2.5%) sown in the command.

NIC Nanded: In Upper Penganga Project the out put is decreased from Rs 24312/ha (2007-08) to Rs.21749/ha (2008-09), water availability is very less in this year.

PIC Pune: In Khadakwasla Project the output comes to Rs. 43990 as compared to last years output of Rs. 42982. In N.R.B.C the output is Rs. 27262/ha. Which is less than last year and just above the state target. In N.L.B.C. output is Rs. 28355/ha. It is decreased than last year and just above the state norms. In Pawna Project the output is Rs. 41597/ha. decreased as compared to last year value of Rs.50794/ha. In Ghod Project the output increased from Rs21717/ha. to Rs24483./ha.this year but it is still below the state norms.

UWPC Amaravati: Out put per unit ha on Upper Wardha project was Rs 26294/ha which is just at par with the state norm.

YIC Yeotmal: On Arunavati Project output during the irrigation year 2008-09 is high (Rs27839/ha) as compared to out put realized in 2007-08 (Rs25153/ha) & to the state norm of Rs. 26000/ha.

Surplus Plan Group:

CADA Nagpur: Overall output per unit irrigated area realized on Bagh, Itiadoh & Pench projects is Rs.46835/ha. compared to last year it is improved well & value is more than the state target value, hence performance is very good (Rs.25000/ha)

Abundant Plan Group:


CADA Pune: In Krishna Project the output is Rs. 25026/ha.shows decrease than last year performance of Rs. 33352/ha. and is still below state target.

CIPC Chandrapur: Output observed on Asolamendha and Dina was Rs.24500/ha which is same as per last year out put.

Asolamendha & Dina projects are paddy growing projects. Obviously the output per unit irrigated area on these projects is likely to be low compared to state target (Rs.32000/ha)

SIC Sangli: The average Agricultural output per unit area in different projects under this circle is (Rs 55495/ha). The projects are Radhanagri, Tulsi, Warna & Dhudhganga. Pest attack on sugarcane crop is controlled and hence increase in yield, hence achievement is more than the state norm (Rs32000/ha) Overall performance is very good on all the projects.

TIC Thane : The average agricultural output per unit area in different projects under this circle is Rs 35582/ha. Projects are Bhatsa, Kal-Amba & Surya. Due to horticulture crops in place of rice crops the output is much more the state norm (Rs 32000/Ha).Over all performance of Agricultural output is very good.



Plan group	Circle	FY Avg	LY 2007- 08	TY 2008- 09	Past Max	Past Min	AVG Per	State Target
Highly Deficit	CADA Solapur	4.55	4.26	4.89	5.35	3.63	4.89	2.69
Deficit	AIC Akola	3.89	4.65	2.54	4.65	1.78		
	BIPC Buldhana	1.14	1.22	2.17	3.80	0.74		
	CADA Abad	2.97	5.72	2.94	5.72	1.01	2.46	2.99
	CADA Beed	2.42	1.69	2.28	3.74	0.72		
	CADA Jalgaon	2.92	2.81	2.31	3.81	1.37		
	CADA Nashik	12.71	12.83	12.45	15.30	10.89		
	NIC Nanded	2.60	2.28	2.52	3.88	1.62		
Normal	AIC Akola	2.51	3.20	2.88	3.20	0.00		
	CADA Jalgaon	9.28	10.40	13.48	11.07	6.72		
	CADA Nagpur	1.06	1.09	1.94	1.36	0.83		
	CADA Nashik	7.14	13.27	13.87	13.27	2.14	3.20	3.38
	CADA Pune	5.58	3.83	4.68	11.38	3.83		
	CIPC Chandrapur	1.66	1.83	1.82	2.48	1.26		
	NIC Nanded	3.37	2.74	3.09	6.76	2.55		
	PIC Pune	4.40	6.91	6.50	6.91	2.09		
	UWPC Amravati	1.98	2.79	4.62	2.79	1.08		
	YIC Yavatmal	1.64	2.11	2.86	2.70	0.00		
Surplus	CADA Nagpur	2.64	2.48	5.15	3.41	2.08	5.15	3.25
Abundant	CADA Pune	3.83	3.83	3.18	4.14	3.26		
	CIPC Chandrapur	4.81	4.54	3.97	6.27	3.78		
	SIC Sangli	4.27	4.53	4.04	5.11	3.88	3.13	4.16
	TIC Thane	1.59	1.87	1.33	1.99	1.07		

Indicator IV: Output per Unit Irrigation Water Supply (Rs./cum) Highly Deficit plan group:

CADA Solapur: In Bhima (Ujjani) project, output per unit water supply for Irrigation is Rs. 4.89/cum. Over all performance is very good.

Deficit plan group:

AIC Akola On Nalganga project despite of the volumetric water supply the ratio (Rs2.54/cum) is low compared to the state target (Rs2.99/cum).

BIPC Buldhana Output realized per unit of irrigation water supply on Wan project (Rs 2.17/cum) was better than previous year but low compared to state norm of Rs2.99/cum.

CADA Aurangabad: In Jayakwadi project (PLBC) indicator value has decreased from Rs.5.72/cum to 2.94/cum as more area is covered by food grain crops.

CADA Beed: In Majalgaon project the indicator value is decreased from 2.15 to 2.06 this year so it is still away from the State target. The field officers are required to improve the indicator value by judicious water use as ISP of canal for both Rabi & HW is below than 50% of the target. Where as on PRBC the value is increased from Rs1.26/cum (2007-08) to Rs1.49/m3 (2008-09). On Manjra & Lower Terna the values increased from Rs 3.94/cum to Rs 4.82/cum & Rs 3.16/cum to Rs 3.95/cum respectively, which are more ahead of State norms.

CADA Jalgaon: In Girna project, the output per unit irrigation water supply is reduced from Rs2.81/Cum to Rs 2.31/Cum which is below the state norm.

CADA Nashik: In Chankapur project, out put per unit irrigation water supplied is on higher side (Rs. 12.45/cum) as the water use per unit irrigated area has not exceeded the state norms i.e. water is utilised for irrigation precisely in 2 rotations only.

NIC Nanded: In Manar project the value increased from Rs2.28/m3 (2007-08) to Rs.3.31/m³ (2008-09) since area irrigated on wells & nallas is 85% of total area irrigated. In Vishnupuri the value has decreased from Rs.3.28 to 2.97/m3 & Purna project has increased from Rs2.03/cum to Rs 2.30/m3 respectively as compared to last year.

Normal Plan Group:

AIC Akola: In spite of, excessive water use per unit irrigated area, good realization of output on Pus Project gave value as 2.88. Lower than state norm & last year's performance.

CADA Jalgaon: In Hatnur project, the output per unit irrigation water supply is increased from Rs.10.40/cum (2007-08) to Rs. 13.48/Cum (2008-09) which is on higher side of the state norms due to cash crops (Banana & Sugar cane) in the command.

CADA Nagpur: On Lower Wanna Project the indicator value is Rs. 1.94 /cum which is below the state norm.

CADA Nashik: In all the projects, the output per unit irrigation water supply is quite higher as compared to the state norm due to cash crops in the command.

CADA Pune: In Kukdi Project the output works out to Rs. 3.98/cum. Shows slight improvement as compared to last year performance. In Ghod Project output is increased (Rs. 7.16/cum) than last year (Rs. 5.50/cum).

CIPC Chandrapur: Though the output per unit irrigated area on Bor Project is fair as compared to the state target, ultimate out put per unit water supply was Rs.1.82/cum due to excessive irrigation water use. Compared to last year it is decreased to some extent.

NIC Nanded: In Upper Penganga project the value of indicator is increased from Rs2.74/cum to Rs 3.09/cum this year, this is due to decrease in water use 28% but only 10% reduction in utilized potential compared to last year.

PIC Pune: In Khadakwasla Project the output is Rs. 8.30/cum. In N.L.B.C. the output decreased from Rs.6.32/cum to Rs. 4.91/cum this year. In N.R.B.C. the output increased from Rs. 6.84/cum to 6.85/cum this year because of repairs to canal system and rainfall during rotation period causes less utilisation of water. In Pawna the output is decreased from Rs. 10.89/cum of last year to Rs. 2.23/cum this year. The overall performance of project under this circle is above the state target.

UWPC Amaravati: Exceptionally high water use per unit area irrigated but good output resulted value (Rs.4.62/cum) above the state norm value.

YIC Yeotmal: Good realization of output gave value (Rs.2.86/cum) but low to the state norm value.

Surplus Plan Group:

CADA Nagpur: Overall ratio in case of Bagh & Itiadoh Projects is Rs.5.15/cum. Performance in case of Itiadoh project compared to Bagh is some what low due to Hot Weather paddy grown on it. Where as on Pench project, low output is on account of more water use and low out put per hectare area irrigated. Overall compared with the last year performance is improved marginally & it is more than the state target value, hence performance is satisfactory.

Abundant Plan Group:

CADA Pune: In Krishna Project the output comes out to Rs. 3.18/cum which is less than state norms and last year performance.

CIPC Chandrapur: Overall performance on Asolamendha and Dina project is Rs. 3.97/cum. Irrigation is mainly in the form protective irrigation. The performance is lower down compared to the state norm, than the last year performance.

SIC Sangli: The output per unit water supply in different projects under this circle is Rs4.04/cum. Projects are Radhanagri, Tulsi, Warna & Dudhaganga. Sincere efforts are being made for improvements. Compared with the last years overall performance is reduced to some extent.

TIC Thane: The average out put per unit water supply in different projects under this circle is Rs1.33/cum. The projects are Bhatsa, Kal-Amba, & Surya. Compared with last year, overall performance is decreased to some extent.

		M	Indicator ajor Proje	ects				
3	L	Cost	Recovery	y Ratio				
2.5								
L.5								
and Akola And Akola	BIPC Buldhana CADA Abad CADA Beed Jalgaon CADA	Nashik NIC Nanded AIC Akola	CADA Jalgaon CADA Nagpur CADA	CADA Pune CADA Pune CIPC Chandrapur NIC Nanded	PIC Pune UWPC Amravati	YIC Yavatmal CADA Nagpur	CADA Pune CIPC Chandrapur	SIC Sangli TIC Thane
Deficit FYAvg	LY 2007-08	TY 2008-	09 — Avg	Per — St	ate Tar 🛛 🗕	• PastMax	- Pa	astMin
		FY	LY	ТҮ	Past	Past	AVG	State
Plan group		Avg	2007-08	2008-09	Max	Min	Per	Target
Highly Deficit Deficit	CADA Solapur AIC Akola	0.63	0.72	0.81	0.75	0.49	0.81	1.00
Dencit	BIPC Buldhana	0.44	0.54 0.54	0.26	0.54 0.54	0.20		
	CADA Abad	1.08	2.79	2.65	2.79	0.22	2.85	1.00
	CADA Beed	0.70	0.35	0.23	0.84	0.31	2.00	1.00
	CADA Jalgaon	0.44	0.42	0.44	0.52	0.34		
	CADA Nashik	1.51	1.41	3.04	4.08	0.75		
	NIC Nanded	0.29	0.25	0.12	0.39	0.25		
Normal	_		0.20	0.12	0.55	0.20		
	AIC Akola	0.51	0.63	0.12	0.63	0.36		
	AIC Akola CADA Jalgaon	0.51 1.41						
	CADA Jalgaon CADA Nagpur	1.41 0.99	0.63 3.67 1.63	0.42 5.11 1.64	0.63 3.80 1.63	0.36 0.51 0.55		
	CADA Jalgaon CADA Nagpur CADA Nashik	1.41 0.99 0.94	0.63 3.67 1.63 1.58	0.42 5.11 1.64 1.70	0.63 3.80 1.63 1.58	0.36 0.51 0.55 0.58		
	CADA Jalgaon CADA Nagpur CADA Nashik CADA Pune	1.41 0.99	0.63 3.67 1.63	0.42 5.11 1.64	0.63 3.80 1.63	0.36 0.51 0.55	2.00	1.00
	CADA Jalgaon CADA Nagpur CADA Nashik CADA Pune CIPC	1.41 0.99 0.94 0.26	0.63 3.67 1.63 1.58 0.18	0.42 5.11 1.64 1.70 0.33	0.63 3.80 1.63 1.58 0.40	0.36 0.51 0.55 0.58 0.18	2.00	1.00
	CADA Jalgaon CADA Nagpur CADA Nashik CADA Pune CIPC Chandrapur	1.41 0.99 0.94 0.26 0.08	0.63 3.67 1.63 1.58 0.18 0.11	0.42 5.11 1.64 1.70 0.33 0.07	0.63 3.80 1.63 1.58 0.40 0.29	0.36 0.51 0.55 0.58 0.18 0.02	2.00	1.00
	CADA Jalgaon CADA Nagpur CADA Nashik CADA Pune CIPC Chandrapur NIC Nanded	1.41 0.99 0.94 0.26 0.08 0.19	0.63 3.67 1.63 1.58 0.18 0.11 0.23	0.42 5.11 1.64 1.70 0.33 0.07 0.20	0.63 3.80 1.63 1.58 0.40 0.29 0.25	0.36 0.51 0.55 0.58 0.18 0.02 0.13	2.00	1.00
	CADA Jalgaon CADA Nagpur CADA Nashik CADA Pune CIPC Chandrapur	1.41 0.99 0.94 0.26 0.08	0.63 3.67 1.63 1.58 0.18 0.11	0.42 5.11 1.64 1.70 0.33 0.07	0.63 3.80 1.63 1.58 0.40 0.29	0.36 0.51 0.55 0.58 0.18 0.02	2.00	1.00
	CADA Jalgaon CADA Nagpur CADA Nashik CADA Pune CIPC Chandrapur NIC Nanded PIC Pune	1.41 0.99 0.94 0.26 0.08 0.19 1.24	0.63 3.67 1.63 1.58 0.18 0.11 0.23 2.88	0.42 5.11 1.64 1.70 0.33 0.07 0.20 2.62	0.63 3.80 1.63 1.58 0.40 0.29 0.25 2.88	0.36 0.51 0.55 0.58 0.18 0.02 0.13 0.78	2.00	1.00
Surplus	CADA Jalgaon CADA Nagpur CADA Nashik CADA Pune CIPC Chandrapur NIC Nanded PIC Pune UWPC Amravati	1.41 0.99 0.94 0.26 0.08 0.19 1.24 0.53	0.63 3.67 1.63 1.58 0.18 0.11 0.23 2.88 0.76	0.42 5.11 1.64 1.70 0.33 0.07 0.20 2.62 0.60	0.63 3.80 1.63 1.58 0.40 0.29 0.25 2.88 0.76	0.36 0.51 0.55 0.58 0.18 0.02 0.13 0.78 0.39	2.00	1.00
Surplus Abundant	CADA Jalgaon CADA Nagpur CADA Nashik CADA Pune CIPC Chandrapur NIC Nanded PIC Pune UWPC Amravati YIC Yavatmal CADA Nagpur CADA Pune	1.41 0.99 0.94 0.26 0.08 0.19 1.24 0.53 0.15	0.63 3.67 1.63 1.58 0.18 0.11 0.23 2.88 0.76 0.00	0.42 5.11 1.64 1.70 0.33 0.07 0.20 2.62 0.60 0.00	0.63 3.80 1.63 1.58 0.40 0.29 0.25 2.88 0.76 1.00	0.36 0.51 0.55 0.58 0.18 0.02 0.13 0.78 0.39 0.00		
· · ·	CADA Jalgaon CADA Nagpur CADA Nashik CADA Pune CIPC Chandrapur NIC Nanded PIC Pune UWPC Amravati YIC Yavatmal CADA Nagpur CADA Pune CIPC	1.41 0.99 0.94 0.26 0.08 0.19 1.24 0.53 0.15 0.14 0.34	0.63 3.67 1.63 1.58 0.18 0.11 0.23 2.88 0.76 0.00 0.04 0.25	0.42 5.11 1.64 1.70 0.33 0.07 0.20 2.62 0.60 0.00 1.37 0.78	0.63 3.80 1.63 1.58 0.40 0.29 0.25 2.88 0.76 1.00 0.85 0.62	0.36 0.51 0.55 0.58 0.18 0.02 0.13 0.78 0.39 0.00 0.04 0.25		
· · ·	CADA Jalgaon CADA Nagpur CADA Nashik CADA Pune CIPC Chandrapur NIC Nanded PIC Pune UWPC Amravati YIC Yavatmal CADA Nagpur CADA Pune CIPC Chandrapur	1.41 0.99 0.94 0.26 0.08 0.19 1.24 0.53 0.15 0.14 0.34 0.36	0.63 3.67 1.63 1.58 0.18 0.11 0.23 2.88 0.76 0.00 0.04 0.25 0.44	0.42 5.11 1.64 1.70 0.33 0.07 0.20 2.62 0.60 0.00 1.37 0.78 0.17	0.63 3.80 1.63 1.58 0.40 0.29 0.25 2.88 0.76 1.00 0.85 0.62 0.44	0.36 0.51 0.55 0.58 0.18 0.02 0.13 0.78 0.39 0.00 0.04 0.25 0.31	1.37	1.00
	CADA Jalgaon CADA Nagpur CADA Nashik CADA Pune CIPC Chandrapur NIC Nanded PIC Pune UWPC Amravati YIC Yavatmal CADA Nagpur CADA Pune CIPC	1.41 0.99 0.94 0.26 0.08 0.19 1.24 0.53 0.15 0.14 0.34	0.63 3.67 1.63 1.58 0.18 0.11 0.23 2.88 0.76 0.00 0.04 0.25	0.42 5.11 1.64 1.70 0.33 0.07 0.20 2.62 0.60 0.00 1.37 0.78	0.63 3.80 1.63 1.58 0.40 0.29 0.25 2.88 0.76 1.00 0.85 0.62	0.36 0.51 0.55 0.58 0.18 0.02 0.13 0.78 0.39 0.00 0.04 0.25		

Indicator V: Cost Recovery Ratio Highly Deficit Plan Group:

CADA Solapur: In Bhima (Ujjani) project, cost recovery ratio is 0.81. It is less than the state norm Compared to last year. It is improved to some extent. **Deficit Plan Group:**

AIC Akola: On Katepurna appreciable achievement is on account of notable NI water recovery, however on Nalganga project, the cost recovery ratio (0. 04) is very poor compared to state norm. There is low revenue recovery on the part of irrigation & Non-irrigation water supply along with heavy operation (salary) cost. As previously mentioned reasons for such large operation cost when the Most of the area on Nalganga project is managed by WUA needs to be sorted out at field level.

BIPC Buldhana: On Wan Project, ratio observed was (0.66). It is low compared to state target. Low irrigation recovery along with high operation cost has affected the cost recovery ratio.

CADA Aurangabad: The ratio on PLBC is has slightly decreased from 2.79 to 2.65 this year.

CADA Beed: Over all decrease in recovery & increase in O & M cost affects the ratio to fall down compared to last year. In Majalgaon project the ratio has drastically decreased from 0.34 to 0.12 this year, as recovery of non irrigation has reduced from Rs. 87.00 lakh to Rs 25.39 lakh this year. In Manjra there is decrease in ratio 0.85 to 0.55 this year, as the NI recovery has decreased from Rs189 lakh to Rs 96 lakh in this year. In Lower Terna, the ratio has decreased from 0.20 to 0.13this year, due to decrease in recoveries. In PRBC the ratio has declined over last year from 0.31 to 0.14 this year, due to lesser recovery specially of irrigation.

CADA Jalgaon: In Girna project, the ratio is increased from 0.42 (2007-08) to 0.44 (2008-09). This is mainly due to increase in revenue by 111%.

CADA Nashik: In Chankapur project, the ratio is increased from 1.41 (2007-08) to 3.04 (2008-09).

NIC Nanded: In Vishnupuri project the cost recovery ratio has decreased from 0.87 to 0.14 this year. On Purna project the ratio has decreased from 0.17 to 0.09 this year, in Manar project the ratio has decreased from 0.07 to 0.05 this year, here the availability of water has decreased for the year, field officers are required to take efforts for recovery of irrigation & non irrigation to achieve state target.

Normal Plan Group:

AIC Akola: On Pus project, the ratio was low (0.42) compared to state norm but lower than last year performance (0.63). It is so on account of very low irrigation recovery and high operation cost. It is again reminded for Suitable measures to increase the irrigation recovery.

CADA Jalgaon: In Hatnur project, the ratio is above state norm (5.11). The increase is due to high recovery of N.I. water use.

CADA Nagpur: On lower Wanna Project the cost recovery ratio observed is good (1.64) as compared to state norm. 100% Non Irrigation water use recovery along with appreciable irrigation recovery is responsible to cross the target.

CADA Nashik: In Bhandardara project, the ratio is lowered from 1.00 (2007-08) to 0.71 (2008-09). In Mula project, the ratio is lowered from 0.34 (2007-08) to 0.28 (2008-09). In Ozerkhed project, the ratio is lowered from 0.22 (2007-

08) to 0.13 (2008-09).In Palkhed project the ratio has been increased from 0.96 (2007-08) to 1.09 (2008-09).In Waghad project, due to increase in revenue, the ratio is improved from 0.22 (2007-08) to 0.26 (2008-09). In Darna project, the ratio is above state norm since last three years. In Gangapur project the ratio has been reduced from 19.78 to 11.47. In Kadwa project, due to high O & M cost, the ratio is below the state norm (0.07).

Project authorities are required to take necessary efforts to improve the performance in the projects where the ratio is below the state norm.

CADA Pune: In Kukdi Project the cost recovery ratio comes to 0.18 shows increase than last year's value of 0.09 the ratio is below the state norms. The field officers have to take more efforts for better recovery. In Ghod Project ratio decreased from 0.92 to 0.88 this year. The performance is lowered due to less recovery and excess amount of expenditure on maintenance.

CIPC Chandrapur: On Bor Project the ratio has rolled down (0.07), compared to last year (0.40). It is very low compared to the state norm.

NIC Nanded: The ratio in UPP has decreased from 0.23 to 0.20 as compared to last year; it is below the State norms. Project authorities are advised to be more vigilant so as to reduce the maintenance cost and take efforts in revenue collection to achieve state norms.

PIC Pune: In Khadakwasla, N.L.B.C. N.R.B.C. and Pawna Project the cost recovery ratio is 2.08, 1.40, 0.38 and 18.49 respectively this year. All the four projects shows decrease in performance than last year, but except in N.R.B.C. the performance is above the state target.

In Pawna Project the more recovery of N.I. use causes remarkable performance of this indicator.

UWPC Amaravati: On Upper Wardha Project cost recovery ratio has slightly lowered (0.60) compared to last year (0.76).

YIC Yeotmal: The information regarding cost per year seems to be insignificant.

Surplus Plan Group:


CADA Nagpur: In case of all the three projects under this circle namely Bagh Itiadoh and Pench the value is 1.37. The achievement in respect of Cost recovery ratio is better than the past year performance of overall 0.04 as well as state norm (except Pench). On Pench performance looks to be very good as compared to state norm due to considerable NI water use and recovery on that part. Low Percentage of irrigation revenue recovery on all the three projects has pulled down the performance of the circle. More efforts are needed towards maximum irrigation revenue recovery on these projects as a whole for improving the performance.

Abundant Plan Group:

CADA Pune: In Krishna Project the ratio comes to 0.78 which is more than last year. But it is below the state target. The field officer has to take more efforts for better recovery.

CIPC Chandrapur: On both the projects(Dina & Asolamendha) cost recovery ratio was 17% of the state target. Low achievement obviously is due to low irrigation recovery. Compared with last year, it is decreased by 23%.

SIC Sangli: The average Cost Recovery ratio in different projects under this circle is 1.94. The projects are Radhanagri, Tulsi, Warna & Dudhaganga. Substantial increase in O & M cost, old project & KT weirs newly rectified & fully repaired. It is 21% more than the last year value



TIC Thane: The average cost Recovery ratio in different projects under this circle is 11.44.

Plan		FY	LY	TY 2008-	Past	Past	AVG	State
group	Circle	Avg	2007-08	09	Max	Min	Per	Tar
Highly								
Deficit	CADA Solapur	1540	1278	1449	3492	1278	1449	1250
Deficit	AIC Akola	5716	5046	15619	15100	4131		
	BIPC Buldhana	1160	1772	2521	1839	372		
	CADA Abad	2752	988	1292	21401	988		
	CADA Beed	12052	4158	3093	18949	3563	1325	1250
	CADA Jalgaon	1462	1460	1852	7113	739		
	CADA Nashik	1975	1378	832	5617	1378		
	NIC Nanded	2364	2376	4228	2631	1877		
Normal	AIC Akola	2434	3310	4122	3310	0		
	CADA Jalgaon	7181	2189	3844	18471	2189		
	CADA Nagpur	2920	2671	2060	3854	1837		
	CADA Nashik	2467	1525	1642	4392	1493		
	CADA Pune	1241	1694	1038	1820	643		
	CIPC						1225	
	Chandrapur	5701	2689	4927	16020	2049	1225	1250
	NIC Nanded	2567	2058	2810	7103	2058		
	PIC Pune UWPC	2445	1047	996	4454	1047		
	Amravati	1080	658	2515	1818	658		
	YIC Yavatmal	548	0	0	1364	0		
Surplus	CADA Nagpur	14400	56450	2354	56450	2094		1250
Abundant	CADA Pune CIPC	2686	3925	1602	4389	1111		
	Chandrapur	554	528	916	633	437		
	SIC Sangli	2530	1611	1517	3703	1611	1345	1250
	TIC Thane	8833	7459	11885	10404	9204		

Indicator VI: O & M Cost per Unit Irrigated Area (Rs./ ha) Highly Deficit Plan Group:

CADA Solapur: In Bhima (Ujjani) project O & M cost per unit area is Rs.1449/ha, which is 16% more than the state norm, hence performance is good.

Deficit Plan Group:

AIC Akola: Due to no irrigation on Katepurna & less irrigation on Nalganga, the indicator value has raised exceptionally to Rs.15619/ha against state norm of Rs.1250/ha.

BIPC Buldhana: On Wan Project, O & M cost per unit irrigated area has been increased to Rs.2521/ha as compared to its last year performance of Rs 1772/ha.

CADA Aurangabad: In Jayakwadi project (PLBC) the O & M cost per unit area has increased from Rs.871/ha to Rs1291.8/ha as compared to last year, which is slightly above the State norms.

CADA Beed: In Majalgaon project the indicator value has increased from Rs 4830/ha to Rs 5721/ha as a compared to last year, which is very high nearly 3.8 times to State norms.

In Manjra project the indicator value has increased from Rs 2934/ha to Rs4104/ha. as compared to last year. But it is still higher nearly 2.3 times than State norms.

In Lower Terna though the indicator value is decreased from Rs. 4904/ha to Rs 4740/ha. as compared to last year, it is still very high nearly 4.0 times to State norms. In Jayakwadi project (PRBC) the ratio has decreased from Rs3071/ha. to Rs 1088/ha. as compared to last year, which has attained the State norms.

CADA Jalgaon: In Girna project, the O&M cost per unit irrigated area is increased from Rs. 1460/ha (2007-08) to Rs. 1852/ha (2008-09) and it is on higher side of the state norm (Rs1250/ha).

CADA Nashik: In Chankapur project, the O & M cost per unit irrigated area is reduced from Rs1378/Cum to Rs 832/cum which has not exceeded the state norms.

NIC Nanded: In Manar project the indicator value has increased from Rs.1998/ha to Rs 17207/ha as compared to last year, very higher than the State norms.

In Vishnupuri project the indicator value has decreased from Rs 2103/ha to Rs2049/ha as compared to last year, which is above the State norms.

In Purna project the indicator value has increased from Rs 2289/ha to Rs3551/ha as compared to last year, which is above the State norms.

Normal Plan Group:

AIC Akola: On Pus project, the ratio was (3.30 times) higher (Rs4122/ha.) than the state norm.

CADA Jalgaon: In Hatnur project, though the O & M cost per unit irrigated area is increased from Rs.2189/ha (2007-08) to Rs. 3844/ha (2008-09) still it is on higher side (3.08 times) of state norms. Project authorities are required to take remedial measures to improve the performance.

CADA Nagpur: On Lower Wunna project O&M cost per unit area irrigated (Rs 2060/ha) was on higher side on account of low potential utilisation as well as more expenditure on maintenance and operation than the standard norms (Rs.1250/ha) it is less as compared to last years performance (Rs.2671/ha).

CADA Nashik: In, Ozerkhed, Waghad, Kadwa and Palkhed projects, the O&M cost per unit irrigated area is well within the state norm. However, in, Bhandardara, Darna, Gangapur & Mula projects, the O & M cost per unit irrigated area is on higher side of state norm.

CADA Pune: In Kukdi Project the O & M cost per unit area is Rs. 1202/ha which decreased from Rs.1897/ha.of last year. In Ghod Project the O & M cost per unit area is considerably decreased from Rs. 901/ ha. of last year to Rs. 691/ha. this year due to curtailment in expenditure on maintenance.

CIPC Chandrapur: Overall O & m cost per unit area is Rs.4927/ha. O & M cost as compared with the last year nearly doubled

NIC Nanded: In UPP the indicator value has increased from Rs2058/ha to Rs2810/ha as compared to last year, which is still higher than the state norms.

PIC Pune: In Khadakwasla Project the O. & M. cost per unit area is Rs. 2474/ha. it increases from Rs. 2033/ha.of last year's due to increase in expenditure as compared to last year. In N.L.B.C. the O & M cost per unit area is Rs. 632/ha. Shows slight decrease in cost than last year of Rs. 646/ha.due to less expenditure on establishment. In NRBC Cost per unit area is Rs. 560/ha which is on lower side of last year value of Rs. 632/ha. In Pawna this year the value increases from Rs. 3970/ha. of last year to Rs.12018/ha. Enhancement in indicator value is due to increase in expenditure on maintenance cost and reduction of irrigated area.

UWPC Amaravati: The high expenditure on maintenance against the cost of operation of Irrigation Management has raised the ratio twice the state norm.

YIC Yeotmal: On Arunavati project there was no flow irrigation during 2008-09.

Surplus Plan Group:

CADA Nagpur: O&M cost per unit area of 3 projects under the circle is Rs. 2354 /ha which is more than the state norm. In spite of good potential utilisation on Bagh & Itiadoh projects, the ratio observed, which suggest more O&M expenditure on these projects compared to the state norm.


Abundant Plan Group:

CADA Pune: In Krishna Project the O & M cost per unit area reduces this year from Rs. 3861 /ha. to Rs. 1602/ha. The reason for better performance is because of reduction in expenditure on maintenance and establishment cost.

CIPC Chandrapur: Better potential utilisation and low expenditure on O & M has curbed the O & M cost per unit area irrigated well below the state norm on overall projects under this circle Rs.916/ha. It is doubled as compared with last year.

SIC Sangli: The average O & M cost per unit area in different project under this circle is Rs1517/ha. The projects are Radhanagri, Tulsi, Warna & Dudhaganga. Comparing with last year ratio is decreased by 6%, further efforts are being taken to reduce O & M cost & increasing irrigation area. Overall performance in Warna project & Dhudhganga project is good & improved marginally compared with last year. Due to huge repair work on Radhanagari & Tulsi, indicator value is too much more than the state target.

TIC Thane: The average O & M cost per unit area in different project under this circle is Rs11885/ha. The projects are Bhatsa, Kal-Amba & Surya. Overall performance is more than the state norm.



		FY	LY 2007-	TY 2008-	Past	Past	AVG	State
Plan group	Circle	Avg	08	09	Max	Min	Per	Target
Highly Deficit	CADA Solapur	0.13	0.12	0.15	0.19	0.12	0.15	0.16
Deficit	AIC Akola	0.44	0.41	1.60	1.02	0.30		
	BIPC Buldhana	0.11	0.13	0.23	0.27	0.05		
	CADA Abad	0.26	0.16	0.14	0.56	0.16		
	CADA Beed	0.77	0.28	0.32	4.69	0.26	0.19	0.16
	CADA Jalgaon	0.20	0.23	0.22	0.25	0.10		
	CADA Nashik	0.26	0.27	0.15	0.37	0.15		
	NIC Nanded	0.24	0.25	0.38	0.37	0.20		
Normal	AIC Akola	0.20	0.17	0.21	2.52	0.14		
	CADA Jalgaon	0.48	0.27	0.31	0.85	0.18		
	CADA Nagpur	0.25	0.24	0.27	0.48	0.15		
	CADA Nashik	0.31	0.24	0.28	0.46	0.24		
	CADA Pune	0.22	0.33	0.21	0.33	0.12	0.22	0.16
	CIPC Chandrapur	0.47	0.20	0.39	1.46	0.15		
	NIC Nanded	0.26	0.22	0.32	0.64	0.18		
	PIC Pune	0.25	0.14	0.14	0.38	0.13		
	UWPC Amravati	0.08	0.06	0.31	0.11	0.06		
	YIC Yavatmal	0.04	0.00	0.00	0.21	0.00		
Surplus	CADA Nagpur	1.28	4.59	0.20	4.59	0.17	0.20	0.16
Abundant	CADA Pune	0.43	0.63	0.20	0.66	0.17		
	CIPC Chandrapur	0.11	0.10	0.15	0.13	0.09		
	SIC Sangli	0.18	0.13	0.10	0.28	0.12	0.14	0.16
	TIC Thane	0.63	1.25	0.10	1.25	0.08		

Indicator VII: O & M Cost per Unit Water Supply (Rs. /cum) Highly Deficit Plan Group:

CADA Solapur: In Bhima (Ujjani) project, the O & M cost is Rs. 0.15 /cum, It is 6% below the state norm. Overall performance is good.

Deficit Plan Group:

AIC Akola: O & M cost per unit water supplied on Katepurna & Nalganga Projects under AIC Akola was more than state norm on account of increase in maintenance expenditure during year 2008-09.

BIPC Buldhana: On Wan Project performance was slightly higher than state norm.

CADA Aurangabad: In Jayakwadi project (PLBC) the value is decreased from 0.16 to 0.14 achieving state target.

CADA Beed: In Majalgaon, the indicator value has increased from 0.32 to 0.38, Manjra has increased over last year's value 0.27 to 0.35, Lower Terna has slightly decreased from 0.65 to 0.59 this year. PRBC is retained its last years value i.e. 0.20 which is still higher to State norms.

CADA Jalgaon: In Girna project, though the O & M cost per unit water supplied is reduced from Rs. 0.23/cum (2007-08) to Rs. 0.22/cum (2008-09), still it is 1.4 times more than the state norm.

CADA Nashik: In Chankapur project, the O & M cost per unit water supplied is just nearer the state norm (Rs.0.15/cum).

NIC Nanded: In Purna & Manar projects the ratio have increased from 0.23 & 0.24 to 0.38 & 1.14 respectively, where as in Vishnupuri project the ratio is slightly decreased from 0.27 to 0.24 as compared to last year.

Normal Plan Group:

AIC Akola: The ratio on Pus was just higher than state target.

CADA Jalgaon: In Hatnur project, the O&M cost per unit water supplied is increased from Rs0.27/cum to Rs 0.31/cum and is on higher side of the state norm.

CIPC Chandrapur & CADA Nagpur: The ratio on Bor, Lower Wunna project was more than the state target.

CADA Nashik: In all the projects the O & M cost per unit water supplied is above state norm. The indicator value ranges from Rs.0.21/cum to Rs. 1.02/cum.Field officers are required to take care to improve the performance. **CADA Pune:** In Kukdi Project the O & M cost is Rs. 0.21/cum which is decreased over last year performance of Rs. 0.35/cum.because of increase in water utilisation. In Ghod Project, this year O & M cost is Rs. 0.22/cum which is same as last year. Decrease in performance in both the project is due to high maintenance expenditure.

NIC Nanded: In UPP the ratio has increased from 0.22to 0.32 which is still

higher than State norms.

PIC Pune: In Khadakwasla, N.L.B.C., N.R.B.C. and Pawna Projects O & M cost Per Unit water supply is Rs. 0.19, 0.11, 0.10 and 0.09/cum.respectively. The performances of all projects are up to satisfactorily level.

UWPC Amravati: The ratio on Upper Wardha was twice the state norm.

YIC Yeotmal: On Arunavati Project the indicator value is zero due to insignificant information given by field officers.

Surplus Plan Group:

CADA Nagpur: Overall performance O & M cost per unit water supply is Rs. 0.20/cum compared with last year, it is substantially decreased & slightly more than state target value (0.16)


Abundant Plan Group:

CADA Pune: In Krishna Project the O & M Cost is Rs. 0.20/cum decreases from 0.63 /cum of last year, it is due to reduction of expenditure on maintenance cost over last year.

CIPC Chandrapur: Protective irrigation in Kharif on Asolamendha & Dina project under CIPC Chandrapur has restricted the O & M cost per unit water supply well within the state norm.

SIC Sangli: The average O & M cost per cubic meter of water supply for irrigation in different projects under this circle is Rs0.10/cum. The projects are Radhanagari, Tulsi, Warna & Dudhaganga compared with last year it is reduced to some extent & below the state norm.

TIC Thane: The average O & M Cost per cubic meter of water supply for irrigation in different projects under this circle is Rs0.10/cum. The projects are Bhatsa, Surya & Kal-Amba.



	Circle	FY	LY 2007-	TY 2008-	Past	Past	AVG	State
Plan group	Circle	Avg	08	09	Max	Min	Per	Target
Highly Deficit	CADA Solapur	0.08	0.08	0.12	0.94	0.63	0.12	0.18
Deficit	AIC Akola	0.19	0.22	0.42	4.15	1.00		
	BIPC Buldhana	0.05	0.07	0.15	1.46	0.21		
	CADA Abad	0.28	0.43	0.36	4.35	1.55		
	CADA Beed	0.54	0.10	0.07	30.21	0.99	0.11	0.18
	CADA Jalgaon	0.09	0.09	0.10	1.07	0.49		
	CADA Nashik	0.40	0.38	0.47	6.25	2.03		
	NIC Nanded	0.07	0.06	0.04	1.04	0.58		
Normal	AIC Akola	0.10	0.11	0.09	10.30	0.54		
	CADA Jalgaon	0.68	0.98	1.58	9.84	2.02		
	CADA Nagpur	0.25	0.38	0.45	3.83	1.83		
	CADA Nashik	0.30	0.37	0.47	3.85	2.04		
	CADA Pune	0.06	0.06	0.07	0.71	0.47	0.10	0.18
	CIPC Chandrapur	0.04	0.02	0.03	0.59	0.23		
	NIC Nanded	0.05	0.05	0.06	1.14	0.35		
	PIC Pune	0.31	0.40	0.37	4.01	2.37		
	UWPC Amravati	0.04	0.05	0.18	0.49	0.33		
	YIC Yavatmal	0.01	0.00	0.16	0.41	0.01		
Surplus	CADA Nagpur	0.17	0.17	0.28	2.23	1.40	0.28	0.18
Abundant	CADA Pune	0.14	0.16	0.16	1.65	1.01		
	CIPC Chandrapur	0.04	0.04	0.03	0.49	0.32	0.13	0.18
	SIC Sangli	0.16	0.20	0.20	2.01	1.48		_
	TIC Thane	0.45	0.40	1.15	7.28	3.08		

Indicator VIII: Revenue per Unit Water Supply (Rs./cum) Highly Deficit Plan Group:

CADA Solapur: In Bhima (Ujjani) project, the revenue is Rs. 0.12/cum which is below the state target. Overall performance is below average.

Deficit Plan Group:

AIC Akola: Projects under AIC Akola are Katepurna & Nalganga. The ratio (Rs0.42/cum) is improved when compared with the performance of last year.

BIPC Buldhana: On Wan Project the indicator value is Rs 0 .15/cum.

CADA Aurangabad: In Jayakwadi project (PLBC) the value decreased from 0.43 to 0.36

CADA Beed: In Majalgaon & Lower Terna the ratio is 0.11 (decreased from 0.22) & 0.13 (increased from 0.0.5) respectively, which is below the state norms (0.18), in PRBC it has decreased from 0.10 to 0.06 as compared to last year where as Manjra project has ratio of 0.23 (increased from 0.16) achieving state target.

CADA Jalgaon: In Girna project, the ratio is below the state norm since last three years.

CADA Nashik: In Chankapur project, the performance is much better (Rs.0.47/cum) as compared to state norm.

NIC Nanded: In all the three projects viz. Manar, Vishnupuri & Purna revenue has decreased per cum of water supply this year. i.e. in the range of 0.21 to 0.07.

Normal Plan Group:

AIC Akola: In Pus project the value is Rs 0.09/cum.

CADA Jalgaon: In Hatnur project the ratio is above state norm. (Rs.1.58/cum).

CADA Nagpur: This year the ratio is 0.45 as compared to last years ratio 0.38.

CADA Nashik: The revenue per unit water supplied is above state norm in Gangapur, Darna & Palkhed projects since last two years. However, the ratio is below state norm (varying from 11%to83%) in Kadwa, Bhandardara, Ozerkhed, Mula and Waghad projects.

CADA Pune: In Kukdi Project revenue is Rs. 0.04/cum shows slight increase over last year performance of Rs. 0.03/cum. It is also far below the state norms. In Ghod project revenue per unit water supply is Rs. 0.19/cum which shows slight decrease from Rs. 0.20/cum of last year.

CIPC Chandrapur: This year the ratio is 0.03 as compared to last years ratio 0.02.

NIC Nanded: UPP has retained last year's value 0.06, as recovery being negligible for successive years.

PIC Pune: In Khadakwasla revenue is Rs. 0.39/cum increased from Rs. 0.38/cum of last year because of increase in revenue of irrigation and non irrigation use. In N.L.B.C. revenue Per Unit water supply is Rs. 0.15/cum. In N.R.B.C. the value is 0.10. In Pawna Project the value decreased from Rs. 2.10/cum to Rs. 1.67/cum. The variation in performance is due to increase or reduction of recovery of irrigation water charges.

UWPC Amravati: In Upper Wardha project the value is Rs. 0.18/cum.

YIC Yeotmal: In Arunavati project the value is Rs 0.16/cum which is close to state norm.

Surplus Plan Group:


CADA Nagpur: Overall low revenue recovery along with excessive water use on all projects under CADA Nagpur is responsible to low performance as compared to state target.

Abundant Plan Group:

CADA Pune: In Krishna Project the performance is same as Rs. 0.16/cum of last year.

CIPC Chandrapur: On Asolamendha & Dina projects under CIPC Chandrapur value is low (Rs 0.03/cum) as compared to the state norm (0.18). **SIC Sangli:** The average revenue value per cubic meter of water supply, in different projects under this circle is Rs 0.20/cum. the projects are Radhanagri, Tulsi, Warna & Dudhaganga. The performance is very good. It is as per the last year value.

TIC Thane: The average revenue per cubic meter water supply in different projects under this circle is Rs1.15/cum. The projects are Bhatsa, Kal-Amba & Surya. The performance is very good.



		FY	LY 2007-	TY 2008-	Past	Past	AVG	state
Plan group	Circle	Avg	08	09	Max	Min	Per	target
Highly Deficit	CADA Solapur	0.02	0.02	0.03	0.00	0.00	0.03	0.00
Deficit	AIC Akola	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	BIPC Buldhana	0.00	0.00	0.00	0.00	0.00		
	CADA Abad	0.01	0.01	0.01	0.00	0.00		
	CADA Beed	0.01	0.01	0.01	0.00	0.00		
	CADA Jalgaon	0.00	0.00	0.00	0.00	0.00		
	CADA Nashik	0.00	0.00	0.00	0.00	0.00		
	NIC Nanded	0.01	0.01	0.00	0.00	0.00		
Normal	AIC Akola	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	CADA Jalgaon	0.00	0.00	0.00	0.00	0.00		
	CADA Nagpur	0.00	0.00	0.00	0.00	0.00		
	CADA Nashik	0.00	0.00	0.00	0.00	0.00		
	CADA Pune CIPC	0.00	0.00	0.11	0.00	0.00		
	Chandrapur	0.00	0.00	0.00	0.00	0.00		
	NIC Nanded	0.01	0.00	0.00	0.00	0.00		
	PIC Pune	0.01	0.01	0.01	0.00	0.00		
	UWPC Amravati	0.00	0.00	0.00	0.00	0.00		
	YIC Yavatmal	0.00	0.00	0.00	0.00	0.00		
Surplus	CADA Nagpur	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Abundant	CADA Pune CIPC	0.01	0.00	0.01	0.00	0.00	0.00	0.00
	Chandrapur	0.00	0.00	0.00	0.00	0.00		
	SIC Sangli	0.01	0.01	0.01	0.00	0.00		
	TIC Thane	0	0	0	0	0		

Indicator X: Land Damage Index:

Highly Deficit Plan Group:

CADA Solapur: In Bhima (Ujjani) project land damage index is 0.03 compared with last year it is increased by 50%.

Deficit Plan group:

CADA Aurangabad: In Jayakwadi Project (PLBC) the land damage increased from 1305 ha to 2228ha this year.

CADA Beed: In Manjra project the affected area has decreased from 487ha to 408ha. as compared to last year, resulting in to slight variation in ratio.

NIC Nanded: In all the three projects the land damage index is nil.

Normal Plan Group:

CADA Pune: Average land damage index of this circle is 0.11.In Ghod Project there is no land damage this year. In Kukdi Project land damage ratio is 0.13 this year.


NIC Nanded: In UPP, there is increase in land damage area from 270 ha to 298 ha this year, resulting increase in % of indicator.

PIC Pune: In Khadakwasla, N.L.B.C., N.R.B.C. and Pawna Projects the land damage index is 0, 2.14, 0.6 and Nil this year respectively.

Abundant Plan Group:

CADA Pune: In Krishna Project the land damage ratio is 0.01 this year.

SIC Sangli: The average Land damage index value in Radhanagri is 0.01. It is same as per last year value.



Plan group	Circle		2008-09	
Plan group	Circle	Head	Middle	Tail
Highly Deficit	CADA Solapur	0.54	0.44	0.31
Deficit	AIC Akola	0.00	0.35	0.40
	BIPC Buldhana	0.32	0.22	0.31
	CADA Abad	0.68	0.53	0.56
	CADA Beed	0.36	0.30	0.26
	CADA Jalgaon	0.34	0.25	0.25
	CADA Nashik	0.09	0.09	0.09
	NIC Nanded	0.25	0.23	0.19
Normal	AIC Akola	0.33	0.69	0.16
	CADA Jalgaon	0.16	0.07	0.01
	CADA Nagpur	0.28	0.45	0.30
	CADA Nashik	0.33	0.38	0.36
	CADA Pune	0.47	0.46	0.40
	CIPC Chandrapur	0.16	0.20	0.06
	NIC Nanded	0.31	0.28	0.17
	PIC Pune	0.97	0.94	0.93
	UWPC Amravati	0.08	0.06	0.03
	YIC Yavatmal	0.00	0.00	0.00
Surplus	CADA Nagpur	0.62	0.73	0.75
Abundant	CADA Pune	0.36	0.36	0.34
	CIPC Chandrapur	0.00	0.00	0.00
	SIC Sangli	0.24	0.35	0.49
	TIC Thane	0.48	0.33	0.37

Indicator XI: Equity Performance:

Highly Deficit Plan Group:

CADA Solapur: In Bhima project the performance values of 2008-09 are as under; Head reach 0.54, Middle reach 0.44 & Tail reach 0.31.

Deficit Plan Group:

CADA Aurangabad: In Jayakwadi project (PLBC) the potential utilization is little more in the head reach.

CADA Beed: In Majalgaon project the equity performance at Head, Middle & Tail reaches with 0.46, 0.35 & 0.14 respectively. In Manjra project & Lower Terna the potential utilization is concentrated equally. In Jayakwadi (PRBC) the potential utilization is concentrated in Head & Middle and lesser on Tail reach.

NIC Nanded: In Purna & Vishnupuri the potential utilization is more or less equal on Head, Middle & Tail reaches. In Manar there is no utilization of water through canal for irrigation since lesser availability.

Normal Plan Group:

CADA Nagpur: This circle has some different case where utilization is concentrated in middle reach. Head reach ratio is 0.23, middle reach ratio is 0.45 and tail reach ratio is 0.30 which is nearer to head reach ratio.

CADA Pune: In Kukdi Project the ratio of potential utilizations is 38% at head middle and tail. In Ghod Project 96% & 97%, 57% area has been irrigated at Head and middle & tail reach.

NIC Nanded: In UPP project the potential utilization is slightly on higher side at the head reach.

PIC Pune: In Khadakwasla potential Utilization is same (0.30) in three reaches of command area. In NLBC the ratio comes to 1.06 in three reaches of command area. In NRBC Irrigation Potential are 1.51, 1.30 and 2.13 at head, middle and tail reach respectively. The ratio is increased due to inclusion of well irrigated area.

Surplus Plan Group:


CADA Nagpur: 62%, 73% & 75% area has been irrigated at Head; middle & tail reach respectively in the projects under this circle.

Abundant Plan Group:

CADA Pune: In Krishna Project potential utilization comes to 0.36, 0.36, and 0.34 in head, middle and tail reach of command area.

TIC Thane: 48%, 33% & 37% area has been irrigated at Head and middle & tail reach respectively in the projects under this circle.

SIC Sangli: 24%, 35% & 49% area has been irrigated at Head and middle & tail reach respectively in the projects under this circle.



Plan		FY	LY	TY	Past	Past	AVG	State
group	Circle	Avg	2007-08	2008-09	Max	Min	Per	Tar
Highly Deficit	CADA Solapur	0.53	0.79	0.63	0.79	0.16	0.63	1
Deficit	AIC Akola	0.42	0.19	0.04	1.10	0.14		
	BIPC Buldhana	0.25	0.18	0.21	1.36	0.00		
	CADA Abad	0.23	0.15	0.10	1.00	0.05		
	CADA Beed	0.07	0.11	0.32	0.87	0.02	0.64	1
	CADA Jalgaon	0.52	0.40	0.39	3.61	0.38		
	CADA Nashik	0.91	1.00	0.64	1.15	0.60		
	NIC Nanded	0.26	0.16	0.14	0.87	0.16		
Normal	AIC Akola	0.25	0.04	0.25	1.17	0.01		
	CADA Jalgaon	0.24	0.25	0.18	0.31	0.20		
	CADA Nagpur	0.25	1.00	0.28	1.00	0.00		
	CADA Nashik	0.61	0.57	0.68	0.84	0.41		
	CADA Pune CIPC	0.67	0.71	0.79	1.22	0.44	0.73	1
	Chandrapur	0.33	0.35	0.19	0.49	0.20		
	NIC Nanded	0.12	0.00	0.10	1.00	0.00		
	PIC Pune UWPC	0.62	0.69	0.72	0.74	0.45		
	Amravati	0.50	0.59	0.49	0.59	0.36		
	YIC Yavatmal	0.07	0.07	0.00	0.21	0.00		
Surplus	CADA Nagpur	0.46	0.56	0.45	0.57	0.25	0.45	1
Abundant	CADA Pune CIPC	0.38	0.24	0.39	0.34	0.00		
	Chandrapur	0.32	0.23	0.83	0.41	0.23		
	SIC Sangli	0.48	0.35	0.41	0.71	0.35	0.68	1
	TIC Thane	0.25	0.39	0.52	0.39	0.12		

Indicator XII_I: Assessment Recovery Ratio (Irrigation) Highly Deficit Plan Group:

CADA Solapur: In Bhima (Ujjani) project the ratio is 0.63, it is reduced than the last year & is below the state norm.

Deficit Plan Group:

BIPC Buldhana & AIC Akola: Percentage of irrigation recovery compared to assessment on Wan, Katepurna, and Nalganga under AIC Akola and in BIPC Buldhana, varied from 0 to20%.

CADA Aurangabad: In Jayakwadi project (PLBC) the ratio has decreased from 0.15 to 0.1 as compared to last year. This year the recovery is very less against assessment.

CADA Beed: In Majalgaon project the ratio has increased from 0.15 to 0.69 as compared to last year, which is slightly below the State norms, In Manjra project the ratio has decreased from 0.20 to 0.1 as compared to last year, in Lower Terna the ratio has increased from 0.05 to 0.65 as compared to last year. In Jayakwadi project (PRBC) the ratio has increased from 0.05 to 0.18 though it is very below the state norms. Project authorities are required to give proper attention to recover 100% current assessment from the farmers & WUA.

CADA Jalgaon: In Girna project, the ratio is just lowered from 0.40 (2007-08) to 0.39 (2008-09).

CADA Nashik: In Chankapur project, the ratio is lowered from 1.00 (2007-08) to 0.64 (2008-09).

NIC Nanded: In the projects viz. Manar & Vishnupuri the ratio has decreased from 0.21 to 0.04, 0.27 to 0.18 & in Purna project the ratio has slightly increased from 0.12 to 0.17. Lesser recovery has affected the indicator value to fall down. Project authorities are required to achieve 100% recovery with hard efforts.

Normal Plan Group:

AIC Akola: On Pus Project the ratio is improved from 0.04 (2007-08) to 0.25(2008-09).

CADA Jalgaon: In Hatnur project the ratio is lowered from 0.25 (2007-08) to 0.18 (2008-09) which is much below the state norm.

CADA Nagpur: The assessment recovery ratio this year had reduced to 0.28 from 1.00 that of last year.

CADA Nashik: In all the projects except Bhandardara about 63 to 98 % water charges has been recovered.

CADA Pune: In Kukdi Project the ratio is reduced from 1.00 of last year to 0.95 this year. In Ghod Project ratio has been increased from 0.44 of last year to 0.51 this year.

CIPC Chandrapur: Ratio is 0.19 which is substantially decreased than the last year value 0.35.

NIC Nanded: In UPP the ratio has increased from 0.00 to 0.10 still it is below the target.

PIC Pune: In Khadakwasla the ratio increases from 0.80 last year to 0.99 this year. It is due to increase in recovery of irrigation water charges this year.

In N.L.B.C. Project the ratio increases from 0.76 last year to 1.00 this year because of better recovery of water charges assessment.

In N.R.B.C. ratio comes to 0.50 this year as compared to 0.61 last year. The decrease in performance is due to less recovery of irrigation water

charges. In Pawna Project the ratio increases from 0.98 last year to 1.00 this year. The increase in performance is due to more revenue recovery this year.

UWPC Amravati: On Upper Wardha project the revenue recovery against assessment was0.49.

YIC Yeotmal: There was no irrigation during the year

Surplus Plan Group:

CADA Nagpur: Recovery rate against assessment on Itiadoh & Bagh project under this circle is appreciable but less as compared to last years performance.


Abundant Plan Group:

CADA Pune: In Krishna Project the ratio decreases to 0.39 as compared to 0.24 of last year. The increase is due to more recovery. The performance is below state target. More efforts are required to enhance the performance up to state norms.

CIPC Chandrapur: Ratio is 0.83 it is substantially increased than the last year value 0.23.

SIC Sangli: The average Assessment recovery ratio is 0.41.

TIC Thane: The average Assessment recovery ratio is 0.52.



Plan group	Circle	FY Avg	LY 2007- 08	TY 2008- 09	Past Max	Past Min	AVG Per	State Target
Highly Deficit	CADA Solapur	0.91	0.97	0.91	1.00	0.74	0.91	1.00
Deficit	AIC Akola	1.16	0.74	0.80	1.28	0.74		
	BIPC Buldhana	0.47	0.37	0.93	1.00	0.20		
	CADA Abad	0.80	1.00	1.00	1.00	0.57		
	CADA Beed	0.52	0.39	0.34	0.82	0.39	0.83	1.00
	CADA Jalgaon	0.86	0.88	0.93	1.00	0.69		
	CADA Nashik	1.00	1.00	1.00	1.39	0.81		
	NIC Nanded	0.73	0.69	0.29	0.85	0.69		
Normal	AIC Akola	0.99	0.33	0.53	2.93	0.10		
	CADA Jalgaon	0.63	0.67	1.00	0.77	0.49		
	CADA Nagpur	0.97	1.00	0.10	1.00	0.00		
	CADA Nashik	0.82	0.91	0.92	0.91	0.68		
	CADA Pune	0.79	0.89	0.84	1.22	0.46	0.88	1.00
	CIPC Chandrapur	0.15	1.00	1.00	1.00	0.00		
	NIC Nanded	0.06	0.01	0.01	0.19	0.00		
	PIC Pune	0.89	0.99	0.99	0.99	0.68		
	UWPC Amravati	0.88	0.84	0.89	1.00	0.81		
	YIC Yavatmal	0.25	0.00	0.00	1.00	0.00		
Surplus	CADA Nagpur	0.89	0.72	0.91	0.98	0.72	0.91	1.00
Abundant	CADA Pune	0.86	0.72	1.00	0.81	0.00		
	CIPC Chandrapur	1.14	1.53	1.00	1.53	0.00		
	SIC Sangli	0.77	0.82	0.73	0.95	0.67	0.82	1.00
	TIC Thane	1.12	1.00	0.54	1.55	0.94		

Indicator XII: Assessment Recovery Ratio (Non Irrigation) Highly Deficit Plan Group:

CADA Solapur: In Bhima (Ujjani) project the ratio is 0.91 which is below the state norm.

Deficit Plan Group:

AIC Akola: Revenue recovery against assessment on Katepurna was more (80%) as compared to state target. On Nalganga project recovery is 100%.

BIPC Buldhana: On Wan project recovery was (93%) which is close to state norm.

CADA Aurangabad: In Jayakwadi Project (PLBC) 100 % recovery against assessed amount of Rs.4858 lakh. Resulting in retaining the ratio 1.0 as per last year.

CADA Beed: In Majalgaon project the ratio has slightly decreased from 0.71 to 0.70 this year. In Manjra project the ratio has decreased from 0.40 to 0.36 as compared to last year. In Lower Terna the ratio has increased from 0.35 to 1.00 as compared to last year. In Jayakwadi Project (PRBC) the ratio has slightly increased from 0.17 to 0.22 as compared to last year and is far below the State norms.

CADA Jalgaon: In Girna project, the ratio is improved from 0.88 (2007-08) to 0.93 (2008-09).

CADA Nashik: In Chankapur project, 100% water charges has been recovered.

NIC Nanded: In Manar project the ratio has increased from 0.83 to 1.0 this year. Where as in Vishnupuri slight decrease from last year value (1.0 to 0.96).

In Purna project the ratio has increased from 0.01 to 0.29. The recovery is Rs 61.45lakhs against assessment of Rs 212.5 lakh.

Normal Plan Group:

AIC Akola: On Pus project performance was increased from 0.33 to 0.53 **CADA Jalgaon:** In Hatnur project, 100% water charges have been recovered. **CADA Nagpur**: The 10 % recovery has been achieved.

CADA Nashik: In Gangapur, Palkhed, Waghad, Kadwa & Ozarkhed projects, the field authorities have achieved the state target. However, in Bhandardara, Darna & Mula Projects about 31 to 92% water charges has been recovered. **CADA Pune:** In Kukdi Project the performance reduces from 1.00 of last year to 0.73 this year. In Ghod the performance increases from 0.87 of last year to 0.90 this year due to more recovery of N.I. use.

CIPC Chandrapur: The 100% recovery has been achieved.

NIC Nanded: In Upper Penganga Project recovery is very poor. Only Rs.3.45 lakh is recovered against assessment of Rs.654.52 lakh. This shows that Project authorities are not paying proper attention to recover the Government revenue.

PIC Pune: In Khadakwasla 100% recovery achieved this year. In N.L.B.C. the 96% recovery achieved this year. In N.R.B.C. the ratio comes to 0.95. In Pawna Project the ratio decreases from 1.00 of last year to 0.98 this year because of reduction of recovery of N.I. Water Charges.

UWPC Amrawati: On Upper Wardha project assessment recovery ratio is 0. 89 which is close to state norm.

YIC Yeotmal: There is no non- irrigation use during this year.

Surplus Plan Group:

CADA Nagpur: 91 % recovery has been achieved as compared to last year's performance (72%).


Abundant Plan Group:

CADA Pune: In Krishna Project the ratio increases from 0.72 of last year to 1.00 this year due to increase of Non Irrigation recovery.

CIPC Chandrapur: 100% recovery has been achieved.

SIC Sangli: The average Assessment recovery ratio is 0.73

TIC Thane: The average Assessment recovery ratio is 0.54.



		FY	LY 2007-		Past	Past	AVG	State
Plan group	Circle	Avg	08	TY 2008-09	Max	Min	Per	Target
Highly Deficit	CADA Beed	7691	7910	7876	9328	5630	7450	7692
	CADA Solapur	6544	6528	6499	8577	0		
	PIC Pune	6561	8843	7974	8843	4845		
Deficit	AIC Akola	7430	6385	10645	11901	6267		
	BIPC Buldhana	9162	10319	10156	11181	1667		
	CADA Abad	7565	7477	6730	8253	7199		
	CADA Beed	7427	7082	7108	8533	5257	8003	7692
	CADA Jalgaon	7619	7784	7716	8347	6935		
	CADA Nashik	5187	5137	6538	5943	3792		
	NIC Nanded	7173	6956	7127	8080	6285		
Normal	AIC Akola	7441	6555	11483	8740	3812	8339	7692
	CADA Abad	4598	2393	5472	5741	0		
	CADA Jalgaon	8614	10651	11062	10651	7119		
	CADA Nashik	9416	9526	11621	10245	6619		
	CIPC Chandrapur	6547	8997	7673	9131	3517		
	NIC Nanded	8480	8813	8989	9614	5313		
	PIC Pune	7486	6461	4856	8707	6461		
	YIC Yavatmal	11211	9554	6553	19042	0		
Surplus	CADA Nagpur	4424	4510	3425	5223	3739	4558	7692
	CIPC	7785	12538	5690	12538	5553		
	Chandrapur							
Abundant	CIPC	5246	5577	4744	5829	3915	7467	7692
	Chandrapur	440000	400400	204050	400400	04 400		
	KIC Ratnagiri	119832	199136	304659	199136	21429		
	SIC Sangli	27298	9341	10190	97537	6620		
	TIC Thane	17996	16871	19192	21513	14988		

Observations of Medium projects

Indicator I: Annual Irrigation Water Supply per Unit Area (cum/ha)

Highly Deficit Plan Group:

CADA Beed: Average annual water supplied per unit irrigated area of medium projects under this circle has decreased from 7910 to 7876 cum/ha, this year. It has decreased slightly over last year. In Kadi project the water used is maximum i.e. 12996 cum/ha. In Khandala project the water use is minimum i.e. 1469 cum/ha.

CADA Solapur: Average annual water supplied per unit irrigated area of five Medium Projects in this Circle is 6499 cum/ha. It is reduced than the last year performance.

PIC Pune: Average Annual water supplied Per Unit Irrigated Area for Sina, Khairy, Nher, Ranand, Tisangi & Mhaswad projects under this circle is 7974 cum/ha. this year. Shows improvement in performance still the performance is below as compared to state target.

Deficit Plan Group:

AIC Akola: Irrigation water use per unit area irrigated on projects under this circle is high 10645 cum/ha. as compared to state target and as well as last years performance 6385cum/ha.

BIPC Buldhana: Average water use on projects under this circle was10156 cum/ha. It was so as irrigation water use on both the projects Mun (10804cum/ha) and Torna (8560 cum/ha) under this circle was excessively high. Reasons for the same needs to be sorted out.

CADA Aurangabad: Average annual water supplied per unit irrigated area of medium projects under this circle has decreased from 7477 to 6730 cum/ha.

In Galhati project the water use is maximum i.e. 14428 cum/ha and in Lahuki the water use is minimum i.e. 2601 cum/ha. This is due to area irrigated is maximum in Rabi season with less rotations. (The ISP is 359 ha/Mcum.)

CADA Beed: Average annual water supplied per unit irrigated area of medium projects under this circle has slightly increased from 7082 (2007-08) to 7108 cum/ha this year. Tawarja project has maximum utilization i.e. 13160cum/ha, Wan project has 12342cum/ha. In Rui project the water use is minimum 2592 cum/ha. Most of projects have utilization through reservoir lift.

CADA Jalgaon: Though the water use per ha is just reduced (1%) as compared to last year, the indicator value (7716 cum/ha) has been exceeded the state norm. The field officers are required to improve the performance in case of Bhokarbari (10667cum/ha), Manyad (10183) and Bori (9074 cum/ha) projects.

CADA Nashik: The water use is well within the state norm since last three years.

NIC Nanded: The average performance of the projects under this circle has slightly increased from 6956 to 7127cum/ha as compared to last year.

Normal Plan Group:

AIC Akola: Average rate of water use on group of projects under the circle has value 11483 m3/ha which was very high to state norm. More water use on Lowerpus & Saikheda projects.

CADA Aurangabad: The average water use has increased from 2393 to 5472 cum/ha. Kolhi project has maximum annual water use of 10946cum/ha. Dheku and Ambadi have water use well below State norms.

CADA Jalgaon: The water use per ha of irrigation is increased by 4% as compared to last year and exceeded the state norm. Specifically in Aner, Abhora & Suki projects, the water use per ha is 1.2 to 4.9 times more than the state norm. Necessary steps should be taken by field officers to improve the performance.

CADA Nashik: The water use per ha is on higher side of the state norm since last two years. It is very much essential to use the water for irrigation more precisely specifically in Adhala (13683 cum/ha), Bhojapur (16958 cum/ha) and Mandohol (13200 cum/ha) projects to achieve the state target.

CIPC Chandrapur: The water use is 7673 cum/ha which has improved than the last years figure 8997 cum/ha.

NIC Nanded: Nagzari project has the maximum water use 10402 cum/ha. Loni has water use of 9768 cum/ha.

PIC Pune: Annual water supplied to Wadiwale project is 4856 cum/ha. this year. The performance is good as compare to last year and state norms.

YIC Yeotmal: Average water use of Adan & Navargaon projects per unit area irrigated is 6553 cum per ha which is low compared to the last year.

Surplus Plan Group:

CADA Nagpur: Overall performance of the projects under this circle is 3425 cum/ha compared with last year it is decreased & much below the state norm value (7692).

CIPC Chandrapur: Overall performance of the projects under this circle is 5690 cum/ha compared with last year it is decreased marginally & overall it is less than the state norm value.


Abundant Plan Group:

CIPC Chandrapur: Overall performance of the projects is 4744 cum/ha compared with last year it is decreased to some extent & much below the state norm value.

KIC Ratnagiri: In Natuwadi project annual water supply per unit area is alarmingly increased to 304659 cum/ha. It is due to heavy leakages through the canal system. Project authorities are required to take preventive measures to stop leakages through canal system.

SIC Sangli: - Average annual water supplied per unit irrigated area of 6 Medium Projects in this Circle is 10190 cum/ha. It is increased 9% than the last year value.

TIC Thane: The water use in Rajanalla Complex & Wandri in this Circle is 19192 cum/ha. It is more by 14% than last year value. It is higher than the five years average value; Water use is more than the state norm due to paddy crops and hilly region Command Area in Konkan.



Plan group	Circle	FY Avg	LY 2007- 08	TY 2008-09	Past Max	Past Min	AVG Per	State Tar
Highly Deficit	CADA Beed	130	126	127	178	107	135	130
	CADA Solapur	153	153	154	154	117		
	PIC Pune	152	113	125	206	113		
Deficit	AIC Akola	135	157	94	160	84		
	BIPC Buldhana	109	97	98	140	89		
	CADA Abad	132	134	149	139	121		
	CADA Beed	135	141	141	190	117	129	130
	CADA Jalgaon	131	128	130	144	120		
	CADA Nashik	193	195	153	264	168		
	NIC Nanded	139	144	140	159	124		
Normal	AIC Akola	134	153	87	262	114	131	130
	CADA Abad	217	418	183	418	174		
	CADA Jalgaon	116	94	90	140	94		
	CADA Nashik	106	105	86	151	98		
	CIPC Chandrapur	153	111	130	284	110		
	NIC Nanded	118	113	111	188	104		
	PIC Pune	134	155	206	155	115		
	YIC Yavatmal	89	105	153	153	53		
Surplus	CADA Nagpur	226	222	292	267	191	234	130
	CIPC	128	80	176	180	80		
	Chandrapur							
Abundant	CIPC Chandrapur	191	179	211	255	172	154	130
	KIC Ratnagiri	8	5	3	47	5		
	SIC Sangli	37	107	98	151	10		
	TIC Thane	56	59	52	67	46		

Indicator I a: Annual Area irrigated per unit of water supplied (ha//Mm3)

Highly Deficit Plan Group:

CADA Beed: The overall area irrigated per unit of water supply (127 ha/Mm3) on projects under this circle is achieved the state norms.

CADA Solapur: Overall area irrigated per unit of water supplied is 154 ha/Mm3 in this year. Compared with last year it is increased by 1% & it is 3% below the state target

PIC Pune: Overall area irrigated per unit of water supplied is 125 ha/Mm3 in this year. Compared with last year it is increased by 11% & it is 4% below the state target

Deficit Plan Group:

AIC Akola: The area irrigated per unit of water supplied is lower than State norm due to low area under irrigation & more water losses.

BIPC Buldhana: The area irrigated per unit of water supplied is lower than State norm under BIPC Buldhana due to more canal losses scattered area of irrigation.

CADA Aurangabad: The overall area irrigated per unit of water supply (149 ha/Mm3) on projects under this circle is crossed the state norms, this may be due to area irrigated on reservoir lift included in overall irrigated area.

CADA Beed: The overall area irrigated per unit of water supply (141 ha/Mm3) on projects under this circle is crossed the state norms, this may be due to area irrigated on reservoir lift included in overall irrigated area.

CADA Jalgaon: Due to lesser rotation in Rabi season, (2 to 3 Nos) the area irrigated per unit water supply seems to be satisfactory which is nearer to state norm.

CADA Nashik: The indicator value seems to be on higher side of state norm due to lesser number of rotations i.e. two rotations on Kelzer project in rabi season.

NIC Nanded: Area irrigated on reservoir lift helps in achieving state target. **Normal Plan Group:**

AIC Akola: The area irrigated per unit of water supplied is lower than State norm due to low area under irrigation & more water losses.

CADA Aurangabad: The overall area irrigated per unit of water supply (183 ha/Mm3) on projects under this circle is crossed the state norms, this may be due to area irrigated on reservoir lift included in overall irrigated area.

CADA Jalgaon: The indicator value is state norm due to low performance in Aner, Sonwad & Aghora projects. The indicator value of Aghora project is low due to irrigation on scattered area.

CADA Nashik: The indicator value is low due to following reasons.

I) 80 to 85% canal losses in Mandohol project

II) Poor performance in Bhjapur project in Rabi season

CIPC Chandrapur: More area (130 ha/Mm3) is irrigated per unit of water supplied as compared to last year (111 ha/Mm3) under the projects of this circle.

NIC Nanded: The overall area irrigated per unit of water supply in the projects under this circle is 85% of state target and needs improvement.

PIC Pune: Overall area irrigated per unit of water supplied is 206 ha/Mm3 in this year. Compared with last year it is increased by 33% & it is 59% more than the state target

YIC Yeotmal: The area irrigated per unit of water supplied of Adan & Nawargaon project under this circle is satisfactory during this year.

Surplus Plan Group:

CADA Nagpur: More area (292 ha/Mm3) is irrigated per unit of water supplied as compared to last year. (222 ha/Mm3) under the projects of this circle

CIPC Chandrapur: More area (176 ha/Mm3) is irrigated per unit of water supplied as compared to last year. (80 ha/Mm3) under the projects of this circle


Abundant Plan Group:

CIPC Chandrapur: More area (211 ha/Mm3) is irrigated per unit of water supplied as compared to last year. (179 ha/Mm3) under the projects of this circle

KIC Ratnagiri: Overall area irrigated per unit of water supplied is 3 ha/Mm3 in this year. Compared with last year it is decreased by 40% & it is 98% below the state target

SIC Sangli: Overall area irrigated per unit of water supplied is 98 ha/Mm3 in this year. Compared with last year it is decreased by 9% & it is 25% less the state target

TIC Thane: Overall area irrigated per unit of water supplied is 52 ha/Mm3 in this year. Compared with last year it is decreased by 12% & it is 60% below the state target



Plan			LY 2007-	TY 2008-	Past		AVG	State
group	Circle	FY Avg	08	09	Max	Past Min	Per	Target
Highly Deficit	CADA Beed	0.31	0.42	0.51	0.64	0.00		
	CADA Solapur	0.59	0.93	0.84	2.13	0.00	0.86	1
	PIC Pune	0.53	0.74	0.88	1.17	0.00		
Deficit	AIC Akola	0.38	0.50	0.43	0.59	0.17		
	BIPC Buldhana	0.20	0.12	0.24	0.70	0.00		
	CADA Abad	0.53	0.92	0.96	0.92	0.15		
	CADA Beed	0.32	0.40	0.44	0.74	0.12		
	CADA Jalgaon	0.92	1.39	1.29	1.39	0.30	1.00	1
	CADA Nashik	0.48	0.59	0.42	0.64	0.31		
	NIC Nanded	0.62	0.71	0.71	0.98	0.37		
Normal	AIC Akola	0.53	0.51	0.33	0.78	0.00		
	CADA Abad	0.33	1.07	0.54	1.07	0.00		
	CADA Jalgaon	1.04	1.55	1.36	1.55	0.44		
	CADA Nashik	0.12	0.02	0.98	1.14	0.00	0.73	1
	CIPC	0.60	0.47	0.40	1.00	0.46		
	Chandrapur							
	NIC Nanded	0.56	0.85	0.60	0.85	0.26		
	PIC Pune	0.65	0.70	1.27	0.89	0.53		
	YIC Yavatmal	0.34	0.86	0.37	0.86	0.00		
Surplus	CADA Nagpur	0.81	0.87	1.02	1.22	0.69	0.85	1
	CIPC	0.86	0.75	0.68	1.45	0.73		
	Chandrapur							
Abundant	CIPC Chandrapur	1.14	1.06	1.04	2.18	0.80		
	KIC Ratnagiri	0.07	0.06	0.04	0.10	0.00		
	SIC Sangli	0.51	0.48	0.43	0.59	0.44	0.83	1
	TIC Thane	0.71	0.64	0.62	0.82	0.64		-

Indicator II: Potential Utilized and created Highly Deficit Plan Group:

CADA Beed: Average ratio of projects under this circle has increased from 0.42 to 0.51 this year. Sakat has maximum value of 2.5. Kadi, Turori, Khasapur and Khandeshwar have values 0.71, 0.77, 0.78 & 0.92 respectively.

CADA Solapur: -The Average value of, Irrigation Potential created & utilised of five Medium Projects in this Circle is 0.84 compared to last year it is decreased to some extent.

PIC Pune: Average irrigation potential utilisation of six projects is 0.88. It is increased from 0.74 of last year but below state norms.

Deficit Plan Group:

AIC Akola: Potential utilisation on the projects is low (0.43) as compared to created potential.

BIPC Buldhana: Actual potential utilisation on Mun & Torna projects was just 24% of the effective created irrigation potential.

CADA Aurangabad: The average performance of projects under this circle has increased from 0.92 to 0.96. Lahuki has potential utilized ratio of 4.1, Sukhana project has ratio of 3.0, Khelna project has ratio of 2.7, and Girija project has 1.3 ratio. This shows that the irrigation on well & nallas in command area of the projects is more than that of irrigation through canal flow & Reservoir lift. Other projects have average ratio from 0.8 to 0.2.

CADA Beed: Average ratio of project under this circle has slightly increased from 0.40 to 0.44 as compared to last year, in the projects Deverjan, Tiru, & Terna the value of the indicators are 0.84, 0.78, & 0.63 respectively.

CADA Jalgaon: In all the projects except Bhokarbari (66%) and Bori (75%) the potential is fully utilised since last four years.

CADA Nashik: The ratio is reduced from 0.59 (2007-08) to 0.42 (2008-09) and the performance is below state target since last year. There is much scope to improve the performance in Haranbari (32%) & Kelzar (52%) Projects.

NIC Nanded: The average ratio of performance has retained last years value i.e. 0.71. Only Kundrala project has crossed the ratio of 1 to 1.07 this year. The rest of the projects have average ratio in between 0.52 to 0.92.

Normal Plan Group:

AIC Akola: Potential utilization on the projects under the circle was 33 % which was low than last year performance of 51%.

CADA Aurangabad: The average performance of projects under this circle has decreased from 1.07 to 0.54. Kolhi project has the ratio of 1.7, Ambadi has 0.3 and Dheku project has 0.6.

CADA Jalgaon: The potential is fully utilised in all the projects.

CADA Nashik: 100% potential is utilised in all the projects except Bhojapur (59%) and Mandohol (42%).

CIPC Chandrapur: The value of this indicator is 0.40.

NIC Nanded: The average performance under this project has declined from 0.85 to 0.60. Nagzari has ratio of 0.92, Dongargaon has ratio of 0.77, and Loni has 0.38.

PIC Pune: Irrigation potential utilisation of Wadiwale Project under this circle is 1.00 of this year. It is as per the state target.

YIC Yeotmal: Potential utilisation compared to created potential on both the projects Adan & Navargaon was less (37%).

Surplus Plan Group:

CADA Nagpur: The value of this indicator is 1.02. **CIPC Chandrapur:** The value of this indicator is 0.68.


Abundant Plan Group:

CIPC Chandrapur: Potential utilisation on both Ghorazari & Naleshwar was as per state norm & last year performance. Potential utilisation of projects combined together was 104 % of potential created.

KIC Ratnagiri: Utilisation of potential in Natuwadi project is decreased from 0.06 to 0.04 this year. But it is very low than the state norms. It is due to very less irrigation area and heavy leakages in the canal system.

SIC Sangli: The Average value, of Irrigation Potential created & utilised of six Medium Projects in this Circle is 0.43 % compared to last year it is decreased to some extent.

TIC Thane: The Average value of Irrigation Potential created & utilized under this circle is 0.62. It is decreased to some extent than the last year.



Plan group	Circle	FY Avg	LY 2007- 08	TY 2008-09	Past Max	Past Min	AVG Per	State Target
Highly Deficit	CADA Beed	20192	21689	11907	32000	18155		
	CADA Solapur	24084	23954	29103	29928	0	20538	23000
	PIC Pune	21306	20645	20605	24667	9396		
Deficit	AIC Akola	62427	79188	20302	80568	39525		
	BIPC Buldhana	14457	10006	7785	28611	10006		
	CADA Abad	21423	20247	22342	29914	18303		
	CADA Beed	36903	37336	28452	48491	20093	24936	25000
	CADA Jalgaon	17255	14359	17373	23452	13885		
	CADA Nashik	33735	24669	28459	42867	24669		
	NIC Nanded	23367	24280	28054	27704	20840		
Normal	AIC Akola	24646	39806	51533	39806	12544		
	CADA Abad	17883	16893	20207	18304	0		
	CADA Jalgaon	33401	38285	40754	59500	10923		
	CADA Nashik	84572	26897	54692	211074	23604	25649	25000
	CIPC Chandrapur	17639	21831	20199	23292	10510		
	NIC Nanded	19018	18922	21436	27244	14251		
	PIC Pune	56921	44978	52192	75847	44978		
	YIC Yavatmal	11694	3343	48325	26784	0		
Surplus	CADA Nagpur	19686	13705	7999	28122	13705		31000
	CIPC	16586	16197	11949	20221	14128		
	Chandrapur							
Abundant	CIPC Chandrapur	26566	24500	24500	39158	22842		
	KIC Ratnagiri	38966	26368	28771	98571	26368		
	SIC Sangli	40164	44006	53874	47023	32024	26636	40000
	TIC Thane	28913	28500	54111	54420	4684		

Indicator III: Output per Unit Irrigated Area (Rs. /ha) Highly Deficit Plan Group:

CADA Beed: Average out put per unit irrigated area of project under this circle has decreased from Rs 21689/ha. to Rs11907/ha. this year, which is very less than the state norms.

Sakat project has out put per unit irrigated area of Rs 23726/ha where as in Turori it is Rs. 19036/ha.

CADA Solapur: Average output per unit irrigated area of five medium projects in this Circle is Rs. 29103/-. It is increased than last year value to some extent.

PIC Pune: Average output per unit irrigated area of six medium Projects is Rs. 20606 ha. this year.

Deficit Plan group:

AIC Akola: Average output per unit area irrigated on projects under this circle was Rs. 20302/ha which is very low as compared to last years performance (Rs79188/ha).

BIPC Buldhana: Output on Mun & Torna project was very less (Rs.7785 /ha).

CADA Aurangabad: The average performance of the projects under this circle has increased marginally from Rs 20247/ha to Rs22342/ha. Gadadgad project has output Rs.39609/ha, Pir kalyan has Rs 29795/ha. Rest of the projects ranging in between Rs 24006/ha to Rs11392/ha.

CADA Beed: Average out put per unit irrigated area in projects under this circle has decreased from Rs 37336/ha to Rs 28452/ha. Whati project under this Plan group has highest output of Rs 36048/ha, which is due to 52% perennials crops irrigated.

CADA Jalgaon: Though the output/ha is increased from Rs. 14359/ha (2007-08) to Rs. 17373/ha (2008-09) still it is below state norm. Field officers are required to improve the performance in case of Bhokarbari, Bori, Burai & Kanoli projects as the performance of these projects is about 50% of the state norm only.

CADA Nashik: The output/ha is with the state norm since last two years except Ghatshill paragon (Rs.15202/ha).

NIC Nanded: The average performance of the projects under this circle has increased from Rs 24280/ha to Rs 28054/ha. Kudala has output Rs 40032/ha. Karadkhed has Rs 29633/ha. Rest of the projects have output in between Rs 16894/ha to Rs19112/ha.

Normal Plan Group:

AIC Akola: Output per unit area irrigated was good (Rs.51533/ha) on projects taken together under AIC Akola.

CADA Aurangabad: The Average output of projects under this circle has increased from Rs.16893/ha to Rs20207/ha this year. Dheku project has the maximum output Rs.20832/ha.

CADA Jalgaon: The output/ha in Karwand, Malangaon & Panzara projects is below state target. Field officers are required to improve the performance.

CADA Nashik: The output/ha has exceeded the state target in all the projects except Adhala (Rs. 17472/ha), Mandohol (Rs. 19697/ha).

CIPC Chandrapur: Average output per unit irrigated area for projects under this circle is Rs.20199/ha.

NIC Nanded: Average output of projects under this circle has increased from Rs.18922/ha to Rs21436/ha. as compared to last year.

Nagzari project has the highest output in this plan group i.e., Rs. 27593/ha which has crossed the State norms.

PIC Pune: In Wadiwale Project the output is Rs. 52192/ha. It is above the state target. The improvement is due to increase in irrigable area under cash crops.

YIC Yeotmal: Output per unit irrigated area was observed on projects under YIC Yeotmal Rs48325/ha.

Surplus Plan Group:

CADA Nagpur & CIPC Chandrapur: Output on projects under this circle is Rs. 7999 /ha and Rs.11949 /ha, respectively which is low as compared to the state norm (Rs.31000/ha.).


Abundant Plan Group:

CIPC Chandrapur: Ghorazari & Naleshwar are the paddy growing projects. Naturally the output is Rs. 24500/ha which is low as compared to state norm of Rs. 40,000/ha.

KIC Ratnagiri: In Natuwadi Project the annual output is slightly increased from Rs. 26368/cum to Rs. 28771/ha. this year. The increase in performance is due to increase in yield of cash crops.

SIC Sangli: Average output per unit irrigated area of six medium projects in this Circle is Rs. 53874/ha.

TIC Thane: On Rajnalla Complex Project & Wandri Project output per unit irrigated area in this Circle is Rs. 54111/ha which is more than the last year.



		FY	LY 2007-	TY 2008-	Past	Past	AVG	State
Plan group	Circle	Avg	08	09	Max	Min	Per	Target
Highly Deficit	CADA Beed	2.66	2.65	1.73	5.68	1.98	3.95	2.99
	CADA Solapur	5.35	5.07	6.68	9.44	0.00		
	PIC Pune	3.88	3.21	3.45	4.33	1.42		
Deficit	AIC Akola	6.23	6.77	3.00	6.77	3.32	4.15	3.15
	BIPC	1.54	1.12	0.90	17.17	1.10		
	Buldhana							
	CADA Abad	4.72	6.22	6.63	6.22	3.02		
	CADA Beed	4.37	4.83	4.02	4.83	3.55		
	CADA Jalgaon	3.48	3.63	4.31	5.94	1.97		
	CADA Nashik	7.52	6.14	5.65	11.31	6.14		
	NIC Nanded	3.40	3.56	4.55	3.78	2.95		
Normal	AIC Akola	2.75	3.57	3.53	3.57	2.44	7.22	3.15
	CADA Abad	9.79	15.52	6.11	15.53	0.00		
	CADA Jalgaon	7.68	11.60	10.42	15.85	2.97		
	CADA Nashik	2.32	0.13	12.10	43.53	0.13		
	CIPC	3.04	3.02	3.06	3.41	2.90		
	Chandrapur							
	NIC Nanded	3.00	3.09	3.38	3.58	2.45		
	PIC Pune	7.35	6.96	10.75	10.49	6.14		
	YIC Yavatmal	1.04	0.35	8.42	4.10	0.00		
Surplus	CADA Nagpur	4.72	3.28	2.41	5.90	3.28	2.26	4.05
	CIPC	2.36	2.23	2.10	2.67	2.18		
	Chandrapur							
Abundant	CIPC	5.17	4.47	5.16	6.72	4.33	2.83	5.4
	Chandrapur							
	KIC Ratnagiri	0.33	0.13	0.09	4.60	0.13		
	SIC Sangli	1.14	3.62	3.24	4.23	0.29		
	TIC Thane	1.64	1.69	2.82	3.06	0.24		

Indicator IV: Output per Unit Irrigation Water Supply Rs. /cum Highly Deficit Plan Group:

CADA Beed: Average output/cum of water supply in projects under this circle has decreased from to Rs. 2.65/cum (2007-08) to Rs1.73/cum (2008-09), which is below the State norms. Khandala project has the highest output Rs10.97/cum being 11% perennial crops.

CADA Solapur: The average output per unit of water supplied of five medium projects in this circle is Rs 6.68/cum. It is more than the last year.

PIC Pune: Average output per unit irrigation water supply for Six Projects under this circle is Rs. 3.45/cum this year. It is above state norms. The increase in performance is due to less water use.

Deficit Plan Group:

AIC Akola: Output (Rs.3.00/m3) is improved than last year.

BIPC Buldhana: Output (Rs.0.90/m3)is lower than the last year

CADA Aurangabad: The Average output/cum in projects under this circle has increased from Rs 6.22/cum to Rs. 6.63/cum which is more than state norms. Ajantha Andhari project has the max. output of Rs.23.82/cum. Lahuki has output of Rs16.22/cum. Masoli has the lowest output i.e. 3.12/cum though it has attained state norms.

CADA Beed: The Average output/cum of water supply in projects under this circle has decreased from Rs. 4.83/cum to Rs. 4.02/cum which is still more than state norms. Rui and Raigavan have maximum output / cum i.e. Rs7.52/cum & Rs. 6.96/cum respectively.

CADA Jalgaon: Output per unit irrigation water supply is above state target since last year except Manyad (Rs.2.68/Cum).

CADA Nashik: The performance of all projects is above state target since last two years except Ghatshil Pargaon (Rs2.95/cum).

NIC Nanded: The Average output/cum in projects under this circle has increased from Rs.3.56/cum to Rs. 4.55/cum which is more than state norms. Pethwadaj project has the maximum output of Rs8.30/cum. Kardkhed has output of Rs. 5.08/ha.Kudala has output of Rs 4.58/cum.

Normal Plan Group:

AIC Akola: Output is improved (Rs.3.53/m3) than last year.

CADA Aurangabad: The Average output/cum in projects under this circle has decreased from Rs. 15.52/cum to Rs. 6.11/cum which is still very well above state norms. Dheku has highest output of Rs 10.16/cum.

CADA Jalgaon: The overall performance is just lowered from Rs11.60/Cum (2007-08) to Rs10.42 /Cum (2008-09) as compared to last year.

CADA Nashik: All the project expect Mandohol project (Rs.1.97/cum) and Adhala (Rs2.58/Cum) have achieved the state target. Over all output is Rs. 12.10/cum.

CIPC Chandrapur: Average output/cum of medium projects under this circle is Rs. 3.06 /cum which is less than state norms.

NIC Nanded: The Average output/cum in projects under this circle has increased from Rs.3.09/cum to Rs. 3.38/cum. Nagzari project has the maximum output of Rs.4.69/cum.

PIC Pune: In Wadiwale Project output is Rs. 10.75/cum this year and it is above last year and state target. The improvement in performance is due to reduction in water use and increased in yield of cash crops.

YIC Yeotmal: Output was very high (Rs8.42 /m3.) as compared to last year.

Surplus Plan Group:

CADA Nagpur : Due to low water utilisation output per unit irrigation water supply on projects under CADA Nagpur (Rs.2.41 /m3) is less than the state norm (Rs.5.4 /m3), as well as last year performance. (Rs.5.90 /cum)

CIPC Chandrapur: Output per unit water supply under this circle is low (Rs.2.10/cum) as compared to last year performance (Rs.2.23 /cum)


Abundant Plan Group:

CIPC Chandrapur : Output per unit water supply on Ghorazari & Naleshwar projects under this circle combined together has low value (Rs 5.16/cum) as compared to state norm & last year performance.

KIC Ratnagiri: In Natuwadi Project this year the output per unit water supply is very low i.e. Rs. 0.09/cum as compared to state norms. It is due to excess quantity of water use and leakage through canal system.

SIC Sangli: -The average output per unit irrigation water supplied of six medium projects in this Circle is Rs.3.24/Cum. It is less than the last year& less than the state norm.

TIC Thane: - Output per unit irrigation water supplied in Rajnalla Complex & Wandri is Rs 2.82 cum. It is more than the last year value(Rs.1.69/cum).



Plan group	Circle	FY Avg	LY 2007-08	TY 2008-09	Past Max	Past Min	AVG Per	State Target
Highly Deficit	CADA Beed	0.56	0.43	0.08	0.87	0.15		
0	CADA Solapur	0.27	0.30	0.34	0.44	0.06	0.22	1
	PIC Pune	0.22	0.22	0.22	0.38	0.06		
Deficit	AIC Akola	0.36	0.43	0.24	0.54	0.18		
	BIPC Buldhana	0.48	0.39	0.25	1.00	0.23		
	CADA Abad	0.32	0.36	0.50	0.53	0.23		
	CADA Beed	0.66	0.91	0.60	0.91	0.54	0.39	1
	CADA Jalgaon	0.32	0.20	0.34	0.56	0.20		
	CADA Nashik	0.68	0.47	0.41	0.93	0.23		
	NIC Nanded	0.37	0.34	0.15	0.55	0.26		
Normal	AIC Akola	0.48	0.27	0.28	0.75	0.22		
	CADA Abad	0.37	0.44	0.29	0.46	0.00		
	CADA Jalgaon	0.35	0.27	0.18	0.54	0.27		
	CADA Nashik	0.65	0.74	0.05	0.74	0.13	0.86	1
	CIPC Chandrapur	0.24	0.97	0.86	0.97	0.07		
	NIC Nanded	0.25	0.26	0.03	0.32	0.13		
	PIC Pune	0.78	7.01	2.74	7.01	0.11		
	YIC Yavatmal	0.33	0.24	0.00	1.45	0.02		
Surplus	CADA Nagpur	0.67	1.45	0.75	1.45	0.29	0.75	1
	CIPC Chandrapur	0.19	0.20	0.07	0.25	0.13		
Abundant	CIPC Chandrapur	0.25	0.35	0.12	0.35	0.19		
	KIC Ratnagiri	0.16	1.51	0.65	1.51	0.03		
	SIC Sangli	0.56	0.59	0.52	0.84	0.41	0.59	1
	TIC Thane	0.04	0.02	0.03	0.23	0.02		

Indicator V: Cost Recovery Ratio Highly Deficit Plan Group:

CADA Beed: The Average ratio of project under this circle has heavily declined from 0.43 to 0.08 compared to last year. The projects which have average performance are Kurnoor, Khandeshwar and Kadi having ratio 0.76, 0.57 & 0.53 respectively.

CADA Solapur: Cost recovery ratio is 0.34 this year compared to last year it is increased to some extent & it is below the state norm.

PIC Pune: Average cost recovery ratio of Six medium projects under this circle is 0.22 this year and below the state target due to reduction in recovery. **Deficit Plan Group:**

AIC Akola: Cost Recovery Ratio has low value in case of projects under AIC Akola (0.24) which is also decreased than last year.

BIPC Buldhana: On both the projects under the circle ratio has low value (0.25) than last year .It indicates more O&M expenditure than revenue recovery.

CADA Aurangabad: The Average ratio of projects under this circle has increased from 0.36 to 0.50 as compared to last year. Ajantha Andhari & Khelna has the maximum ratio of 1.6 & 1.2 due to recovery of NI & Irrigation respectively.

CADA Beed: The Average ratio of project under this circle has decreased from 0.91 to 0.60, Terna project has maximum ratio of 5.74 due to Rs. 28.8 lakh NI recovery.

CADA Jalgaon: Though the cost recovery ratio is improved from 0.20 (2007-08) to 0.34 (2008-09) it is much below the state norm. More attention is required to be given by the field officers in case of all the projects to improve the performance.

CADA Nashik: The overall cost recovery ratio is lowered from 0.47 (2007-08) to 0.41 (2008-09). Specifically In Ghatshilpargaon & Nagyasakya projects, much improvement is required as the ratio is only 0.06 & 0.15 respectively. **NIC Nanded**: The average ratio of projects under this circle has decreased from 0.34 to 0.15 compared to last year. Kudala project has the maximum ratio of 0.55.

Normal Plan Group:

AIC Akola: Cost recovery ratio on project under AIC Akola is nearly same to last year (0.28)

CADA Aurangabad: The average ratio of project under this circle has decreased from 0.44 to 0.29. Ambadi project having the maximum ratio of 0.8 in this plan group though it is still below the state target.

CADA Jalgaon: Overall performance is lowered from 0.27 (2007-08) to 0.18 (2008-09) which is much below the state target. Efforts are required to improve the performance in case of Abhora, Aner, Karwand, Malangaon & Suki projects.

CIPC Chandrapur: Cost recovery ratio on projects under this circle is quite good (i.e. 86%) this year.

CADA Nashik: The ratio is lowered from 0.18 (2007-08) to 0.05 (2008-09). There is much scope to improve the performance in all the projects. Project authorities are required to take necessary actions in this regard.

NIC Nanded: The average ratio of project under this circle has decreased drastically from 0.26 to 0.03. Nagzari project having the maximum ratio of 0.68 due to NI recovery of Rs. 6.69 lakh.

PIC Pune: In Wadiwale Project the cost recovery ratio this year is 2.74. The performance is decreased as compared to last year value of 7.01. Still the performance is good as compared to state norms.

YIC Yeotmal: On projects under YIC Yeotmal the information received from field officer seems to be insignificant.

Surplus Plan Group:

CADA Nagpur & CIPC Chandrapur: Cost recovery ratio on CADA Nagpur (0.75) was less than state target & as well as its last year performance (0.46). In case of projects under CIPC Chandrapur, there is reduction (.07) in cost recovery compared to last year performance i.e. (0.2).


Abundant Plan Group:

CIPC Chandrapur: Cost recovery ratio on CIPC Chandrapur (0.12) was less than state target & as well as its last year performance (0.35).

KIC Ratnagiri: In Natuwadi Project cost recovery ratio is very low i.e. 0.65. The performance is increased as compared to last year i.e. 0.13

SIC Sangli: Cost recovery ratio is 0.52 compared with last year it is decreased to some extent.

TIC Thane: Cost recovery ratio is 0.03 compared with last year it is decreased to some extent.



Plan group	Circle	FY Avg	LY 2007-08	TY 2008-09	Past Max	Past Min	AVG Per	State Target
Highly Deficit	CADA Beed	1892	1209	3999	200667	1099		
	CADA Solapur	1775	1064	1074	2056	0	1220	1200
	PIC Pune	2619	1509	1367	44396	976		
Deficit	AIC Akola	5794	5893	8445	77730	3524		
	BIPC Buldhana	1755	2440	1675	15417	965		
	CADA Abad	1433	1207	1368	2400	1096		
	CADA Beed	2476	1933	2232	3679	1932	1569	1200
	CADA Jalgaon	1343	911	1031	2199	911		
	CADA Nashik	2285	1363	1537	7038	758		
	NIC Nanded	1828	2350	4152	2573	1448		
Normal	AIC Akola	2810	3176	5392	17070	1690		
	CADA Abad	2068	1700	1867	1700	0		
	CADA Jalgaon	1007	632	883	1519	632		
	CADA Nashik	9763	51224	1640	51224	1272	1344	1200
	CIPC	9461	2810	3826	38310	1687		
	Chandrapur							
	NIC Nanded	1855	1562	1212	3970	1129		
	PIC Pune	2025	281	986	3615	281		
	YIC Yavatmal	1391	1555	0	3660	0		
Surplus	CADA Nagpur	1266	618	1265	2520	618	1943	1200
	CIPC	1418	1739	2621	1739	1000		
	Chandrapur							
Abundant	CIPC Chandrapur	1155	888	1056	1818	888		
	KIC Ratnagiri	26649	3728	10829	198071	3728	1668	1200
	SIC Sangli	2214	2259	2281	2555	1616	-	
	TIC Thane	3774	5103	4190	6183	677		

Indicator VI: O & M Cost per Unit Area (Rs./ha) Highly Deficit Plan Group:

CADA Beed: The average cost per unit irrigated area of projects under this circle has increased from Rs 1209/ha to Rs. 3999/ha. Indicator value in Kada project is Rs 11463/ha.due to O & M cost for irrigation is Rs 27.43 lakh.

CADA Solapur: O & M cost per unit area for this year is Rs.1074/ha. compared with last year it is decreased & less than the state norm.

PIC Pune: Average O & M cost per unit area of Six medium projects of this circle is Rs. 1367/ha. It is above the state target. The reduction in performance is due to increase in expenditure on maintenance.

Deficit Plan Group:

AIC Akola: O & M cost per unit area irrigated on projects under this circle was (Rs.8445/ha), higher than last year value (Rs 5893/ha).

BIPC Buldhana: O & M cost per unit area irrigated on projects under this circle was Rs.1675/ha which is improved as compared to last year.

CADA Aurangabad: The average O & M cost per unit irrigated area of projects under this circle has increased from Rs.1207/ha to Rs. 1368/ha. compared to last year, which gone over state norms.

Ajantha Andhari has the maximum O &M cost of Rs 12034/ha & Jui has Rs 10953/ha. Low ratios of Sukhana (Rs 566/ha) & Girija (RS 474/ha) are affected for overall reduction of the indicator.

CADA Beed: The average cost per unit irrigated area of projects under this circle has increased from Rs. 1933/ha to Rs. 2232/ha.compared to last year. Masalga has highest O & M cost of Rs17026/ha since utilized potential is only 76 ha. & O&M cost is Rs.19.14 lakh.

CADA Jalgaon: The overall O&M cost per unit irrigated area is Rs 1031/ha. In Agnawati, Bhokarbari, Bori,& Tondapur projects, O & M cost is on higher side of the state norms. Which should be minimised in future.

CADA Nashik: The O&M cost per unit irrigated area is increased from Rs. 1363/ha.to Rs. 1537/ha which is 1.30 times more than the state norm. Specifically in Ghatshilpargaon project (Rs. 2820/ha), the O & M cost should be minimised in future.

NIC Nanded: The average O & M cost per unit irrigated area of projects under this circle has increased from Rs. 2350/ha to Rs. 4152/ha. compared to last year and overcomes State norms. Pethwadaj has the maximum O&M cost of Rs6070/ha for this Plan group in the circle.

Normal Plan group:

AIC Akola: Low potential projects with more O&M expenditure under AIC Akola has resulted more ratio (5392 Rs/Ha) than last year.

CADA Aurangabad: The average O & M cost per unit irrigated area of projects under this circle has increased from Rs. 1700/ha to Rs. 1867/ha.compared to last year which is above State norms. Kolhi has the maximum O & M cost of Rs 3142/ha.

CADA Jalgaon: Overall performance is well within the state norm except Karwand (Rs. 2643/ha).

CADA Nashik: Overall performance is lowered as compared to last year as the O & M cost per ha. is increased from Rs. 1096/ha (2007-08) to Rs. 1640/ha (2008-09).

CIPC Chandrapur: Performance (Rs. 3826/ha) is decreased compared to last year performance (Rs. 2810/ha).

NIC Nanded: The average O & M cost per unit irrigated area of projects under this circle has decreased from Rs. 1562/ha to Rs. 1212 /ha. nearly achieved State norms. Loni has maximum O&M cost of Rs.1803/ha.where as in Nagzari it is minimum i.e. Rs104/ha.

PIC Pune: In Wadiwale project the O & M cost per unit area comes to Rs.986 /ha. The performance is good as compared to state norms.

YIC Yeotmal: The information received from field officer seems to be insignificant.

Surplus Plan Group:

CADA Nagpur: O & M cost per unit area irrigated on projects under CADA Nagpur is Rs. 1265/ha. compared to last year it increased marginally.

CIPC Chandrapur : O & M cost works out to Rs. 2621 /ha which is more than state norm and more than as compared to last years performance Rs.1739 /ha.


Abundant Plan Group:

CIPC Chandrapur : O & M cost works out to Rs. 1056 /ha which is less than state norm and more than as compared to last years performance Rs.888 /ha.

KIC Ratnagiri: In Natuwadi Project the O & M Cost per unit area enhances to Rs. 10829/ha. But the value is more than state norms. The Field Officers are required to take efforts for improvement in performance.

SIC Sangli: O & M cost per unit area for this year is Rs.2281/ha.compared with last year it is increased & more than the state norm.

TIC Thane: O & M cost per unit area for this year is Rs. 4190/ha.compared with last year it is increased & more than the state norm.



Plan group	Circle	FY Avg	LY 2007-08	TY 2008- 09	Past Max	Past Min	AVG Per	State Target
Highly Deficit	CADA Beed	0.22	0.13	0.43	1.41	0.11		
	CADA Solapur	0.37	0.21	0.22	0.65	0.00	0.23	0.16
	PIC Pune	0.44	0.23	0.23	6.71	0.19		
Deficit	AIC Akola	0.49	0.44	0.82	1.71	0.38		
	BIPC Buldhana	0.18	0.27	0.19	0.40	0.13		
	CADA Abad	0.27	0.32	0.32	0.38	0.12		
	CADA Beed	0.22	0.19	0.23	0.32	0.13	0.21	0.16
	CADA Jalgaon	0.22	0.20	0.22	0.29	0.20		
	CADA Nashik	0.34	0.22	0.25	0.85	0.10		
	NIC Nanded	0.23	0.28	0.46	0.33	0.17		
Normal	AIC Akola	0.29	0.26	0.34	0.71	0.20		
	CADA Abad	0.69	0.83	0.42	1.79	0.00		
	CADA Jalgaon	0.22	0.18	0.22	0.36	0.17		
	CADA Nashik	0.24	0.23	0.35	0.40	0.19		
	CIPC Chandrapur	1.56	0.39	0.58	5.16	0.39	0.33	0.16
	NIC Nanded	0.27	0.24	1.81	0.60	0.18		
	PIC Pune	0.24	0.04	0.17	0.39	0.04		
	YIC Yavatmal	0.11	0.15	0.00	0.56	0.02		
Surplus	CADA Nagpur	0.28	0.14	0.34	0.52	0.14		0.16
	CIPC Chandrapur	0.19	0.19	0.46	0.21	0.17		
Abundant	CIPC Chandrapur	0.22	0.16	0.22	0.31	0.16		
	KIC Ratnagiri	0.21	0.02	0.03	1.02	0.02		
	SIC Sangli	0.20	0.18	0.14	0.27	0.16	0.15	0.16
	TIC Thane	0.21	0.30	0.19	0.35	0.05		

Indicator VII: O & M Cost Per Unit of Water Supply (Rs./cum) Highly Deficit Plan Group:

CADA Beed: The average value of this indicator for projects under this circle has increased from Rs 0.13/cum to Rs. 0.43/cum. compared to last year which is above the State norms, except Kadi & Khandeshwar rest of the projects have O&M cost more than state norms.

CADA Solapur: O & M cost for water supply is Rs. 0.22/m³ compared with last year it is slightly increased & more than state target value.

PIC Pune: Average O & M Cost per unit of water supply in six medium projects comes to Rs. 0.23/cum this year. But it is more than the state target. Project authorities are advised to take efforts to improve the performance.

Deficit Plan Group:

AIC Akola: O & M cost per unit water supply on projects under AIC Akola was more (Rs.0.82/cum) than last year.

BIPC Buldhana: O & M cost per unit water supply on projects under this circle was (Rs.0.19/cum) improved than last year.

CADA Aurangabad: The average value of this indicator for projects under this circle has retained its last year's value Rs 0.32 /cum, still it is above the State norms. Dhamna project has the ratio of 2.31

CADA Beed: The average value of this indicator for projects under this circle has increased over last years value from Rs 0.19 to 0.23/cum which is above the state norms. Masalga project has indicator value of 1.72.

CADA Jalgaon: O & M cost per unit water supplied is on higher side of the state norm since last three years. More attention is required in case of Agnawati, Bhokarbari, Bori, Hiwara, & Tondapur projects to improve the performance.

CADA Nashik: O & M cost per unit water supplied is on higher side of the state norm since last three years. Field authorities are required to take necessary steps to improve the performance of all the projects.

NIC Nanded: The average value of this indicator for projects under this circle increased from Rs 0.28/cum to Rs. 0.46/cum over last year. Pethwadaj has indicator value Rs.1.06/cum.

Normal Plan Group:

AIC Akola: O & M cost per unit water supply on projects under AIC Akola was more as (Rs. 0.34/cum).

CADA Aurangabad:

The average value of this indicator for projects under this circle has decreased from Rs. 0.83/cum to Rs. 0.42 /cum. which have decreased by 50% over last year. In Dheku project O & M cost per unit water supply is Rs. 0.52/cum.

CADA Jalgaon: O & M cost per unit water supplied is increased from Rs. 0.18/cum (2007-08) to Rs. 0.22/cum (2008-09) which is on higher side of the state norms. The performance in Aner & Panzara projects is better as the indicator value in these projects is close to state norm. However, improvement is required in case of Abhora, Malangaon & Karwand projects.

CADA Nashik: In all the projects except Bhojapur, the O&M cost per unit water supplied is on higher side. Remedial measures should be taken to improve the performance in Alandi, Adhala, & Mandohol projects.

CIPC Chandrapur: O & M cost /unit water supplied is increased from Rs. 0.39/cum to Rs. 0.58 /cum.

NIC Nanded: The average value of this indicator for projects under this circle has increased from Rs 0.24/cum to Rs.1.81/cum it has increased by 7.5 times over last year. The indicator is above the State norms. Loni has indicator value of Rs. 5.98/cum.

PIC Pune: In Wadiwale Project O & M Cost per unit of water supply is increases this year to Rs. 0.17/cum from Rs.0.04 /cum of last year.

Surplus Plan Group:

CADA Nagpur & CIPC Chandrapur: O & M cost per unit water supplied observed on projects under CADA Nagpur(Rs. 0.34/cum) & CIPC Chandrapur (Rs. 0.46/cum) was slightly more than state norm as well as last years performance.


Abundant Plan Group:

CIPC Chandrapur: O & M Cost per unit of water supply is increased from Rs. 0.16 /cum of last year to Rs. 0.22/cum this year. It is more than the state target value.

KIC Ratnagiri: In Natuwadi Project O & M Cost per unit of water supply remains same to Rs. 0.03/cum of last year.

SIC Sangli: O & M cost for water supply is Rs. 0.14/m³ compared with last year it is decreased.

TIC Thane: O & M cost for water supply is Rs. 0. 19/m³ compared with last year it is increased & more than state target value.



Plan group	Circle	FY Avg	LY 2007- 08	TY 2008-09	Past Max	Past Min	AVG Per	State Target
Highly Deficit	CADA Beed	0.12	0.06	0.03	3.52	0.29		
	CADA Solapur	0.1	0.06	0.08	1.36	0.00	0.05	0.18
	PIC Pune	0.1	0.05	0.05	3.82	0.24		
Deficit	AIC Akola	0.18	0.19	0.19	7.69	0.80		
	BIPC Buldhana	0.09	0.11	0.05	3.99	0.29		
	CADA Abad	0.08	0.12	0.16	1.22	0.47		
	CADA Beed	0.15	0.17	0.14	1.77	0.85	0.11	0.18
	CADA Jalgaon	0.07	0.04	0.07	1.28	0.41		
	CADA Nashik	0.23	0.11	0.10	7.93	0.22		
	NIC Nanded	0.09	0.1	0.07	1.79	0.54		
Normal	AIC Akola	0.14	0.07	0.09	1.94	0.71		
	CADA Abad	0.25	0.37	0.12	8.19	0.00		
	CADA Jalgaon	0.08	0.05	0.04	1.20	0.47		
	CADA Nashik	0.16	0.17	0.02	1.67	0.51	0.19	0.18
	CIPC Chandrapur	0.37	0.38	0.50	7.22	2.90		
	NIC Nanded	0.07	0.06	0.05	1.50	0.41		
	PIC Pune	0.19	0.3	0.46	2.96	0.10		
	YIC Yavatmal	0.04	0.04	0.27	3.47	0.01		
Surplus	CADA Nagpur	0.19	0.2	0.26	3.17	0.60	0.03	0.18
	CIPC Chandrapur	0.04	0.04	0.03	0.45	0.26		
Abundant	CIPC Chandrapur	0.05	0.06	0.03	0.72	0.43		
	KIC Ratnagiri	0.03	0.03	0.02	4.60	0.08		
	SIC Sangli	0.11	0.11	0.07	1.51	0.64	0.03	0.18

TIC Thane (0.01	0.01	0	0.18	0.06
-------------	------	------	---	------	------

Indicator VIII: Revenue Per Unit of Water Supplied Rs/cum Highly Deficit Plan Group:

CADA Beed: The average value of this indicator for projects under this circle has decreased from Rs. 0.06/cum to Rs. 0.03 *I*cum compared to last year.

CADA Solapur: Revenue per unit water supply is Rs.0.08/cum compared with last year it is slightly lower down. It is too much below the state norm.

PIC Pune: Average revenue per unit of water supplied in Six medium projects under this circle remains same to Rs. 0.05/cum of last year. The reason for poor performance is due to reduction in revenue recovery.

Deficit Plan Group:

AIC Akola: Revenue recovery per unit water supplied on projects under AIC Akola is Rs. 0.19/cum.

BIPC Buldhana Revenue recovery per unit water supplied on projects under BIPC Buldhana was quite low (Rs. 0.05/cum) mainly due to low revenue realization.

CADA Aurangabad: The average value of this indicator for project under this circle had increased from Rs. 0.12/cum to Rs. 0.16 /cum. It has increased by 33% over last year. But it is still slightly below state norms, improvement in revenue collection is still needed. Khelna has maximum ratio of Rs1.0/cum.(NI recovery being Rs 19.57 lakh) Karpara, Dhamna, Galhati & Kalyan Girija projects under this plan group which have zero revenue.

CADA Beed: The average value of this indicator for the project under this circle has slightly decreased from Rs 0.17/cum to Rs. 0.14/cum. Terna has maximum revenue Rs 0.26/cum. Project authorities are required to take more efforts in recovering the revenue.

CADA Jalgaon: Though the revenue per unit water supplied is increased from Rs. 0.04/cum (2007-08) to 0.07/cum (2008-09) still it is below state norm. In case of Bhokarabari, Burai, Kanoli, Hiwara & Rangwali projects, performance is very low (ratio is 0.12 ,0.01, 0.03 ,0.07& 0.05 respectively). Improvement in these projects is necessary.

CADA Nashik: Revenue per unit water supplied is lowered from Rs. 0.11/cum (2007-08) to Rs. 0.10/cum (2008-09). Efforts are required to improve the performance in all the projects concerned.

NIC Nanded: The average value of this indicator for project under this circle has decreased from Rs 0.10/cum to Rs. 0.07/cum. It is below State norms. Project authorities are required to take hard efforts in recovering the revenue. Kudala & Karadkhed are the only projects which have achieved (0.17) nearly the state norms.

Normal Plan Group:

AIC Akola: The indicator value is (Rs 0.09/cum) higher than last years (Rs.0.07/cum).

CADA Aurangabad: The average value of this indicator for project under this circle has decreased from Rs 0.37/cum to Rs. 0.12 /cum. It has decreased by 67% over last year's performance and gone below the State norms. Ambadi project has the ratio of 0.30 which is more than the state norms.

CADA Jalgaon: The indicator value is lowered from 0.05 (2007-08) to Rs.0.04/cum (2008-09). The improvement in the performance is required in all the projects concerned.

CADA Nashik: The performance is lowered from Rs. 0.05/cum to Rs. 0.02/cum as compared to last year and which is far below the state norm.

CIPC Chandrapur: There is slight increase in revenue per unit water supplied (Rs. 0.38/cum to Rs. 0.50/cum) as compared to last year.

NIC Nanded: The average value of this indicator for projects under this circle has slightly decreased over last years value i.e. Rs.0.06/cum to Rs. 0.05/cum. It is very much below state norms. Loni is the only project which has achieved state norms. Revenue collection target should be strictly programmed & followed by the Project authorities so as to achieve indicator target.

PIC Pune: In Wadiwale Project the ratio is 0.46 which shows good performance than state target due to increase in revenue recovery.

YIC Yeotmal: The indicator value is Rs.0.27/cum, which is greater than last year.

Surplus Plan Group:

CADA Nagpur: Revenue recovery per unit water supplied on projects under this circle (0.26) was more than the state norm as water was used for protective irrigation in Kharif only.

CIPC Chandrapur: Revenue recovery per unit water supplied on projects under this circle (0.03) was less than the state norm as water was used for protective irrigation in Kharif only.


Abundant Plan Group:

CIPC Chandrapur: Revenue recovery per unit water supplied on projects under this circle (0.03) was less than the state norm.

KIC Ratnagiri: In Natuwadi Project the ratio comes to (0.02) due to less amount of revenue recovery and excess water use.

SIC Sangli: Revenue per unit water supply is Rs.0.07/ m³ compared with last year it is increased & below the state norm.

TIC Thane: Revenue per unit water supply is NIL



Plan group	Circle		2008-09	
Plan group	Circle	Head	Middle	Tail
Highly Deficit	CADA Beed	0.20	0.13	0.09
	CADA Solapur	0.28	0.22	0.19
	PIC Pune	1.09	0.63	0.65
Deficit	AIC Akola	0.20	0.22	0.09
	BIPC Buldhana	0.51	0.69	0.02
	CADA Abad	0.11	0.05	0.11
	CADA Beed	0.18	0.15	0.12
	CADA Jalgaon	0.48	0.41	0.42
	CADA Nashik	0.06	0.06	0.06
	NIC Nanded	0.09	0.09	0.08
Normal	AIC Akola	0.30	0.29	0.11
	CADA Abad	0.17	0.19	0.07
	CADA Jalgaon	0.46	0.52	0.26
	CADA Nashik	0.24	0.28	0.23
	CIPC Chandrapur	0.12	0.12	0.10
	NIC Nanded	0.97	0.89	0.59
	PIC Pune	0.08	0.82	2.92
	YIC Yavatmal	0.16	0.02	0.00
Surplus	CADA Nagpur	0.58	0.59	0.56
	CIPC Chandrapur	0.00	0.00	0.00
Abundant	CIPC Chandrapur	0.00	0.00	0.00
	KIC Ratnagiri	0.05	0.04	0.02
	SIC Sangli	0.00	0.00	0.00
	TIC Thane	0.17	0.17	0.04

Indicator XI: Equity Performance

Highly Deficit Plan Group:

PIC Pune: - Average potential utilisation in six medium projects is higher in Head reach and low in tail reach.

Normal Plan Group:

CIPC Chandrapur: Potential utilisation was more concentrated in head and middle reaches of projects under CIPC Chandrapur.


Surplus Plan Group:

CADA Nagpur and CIPC Chandrapur: Potential utilisation was more or less equal in all the reaches in projects under CADA Nagpur and CIPC Chandrapur.

Abundant Plan Group:

KIC Ratnagiri: - In Natuwadi project irrigation potential utilization ratio is 0.05, 0.03, and 0.02 at head; middle and tail reach of command area

CIPC Chandrapur: Potential utilisation was more or less equal in all the reaches in projects under this circle.



Plan			LY	TY	Past	Past	AVG	State
group	Circle	FY Avg	2007-08	2008-09	Max	Min	Per	Targe
Highly Deficit	CADA Beed	0.27	0.38	0.56	0.38	0.00	,	_
	CADA Solapur	0.31	0.29	0.13	0.76	0.28	0.51	1
	PIC Pune	0.54	0.88	0.84	0.91	0.23		
Deficit	AIC Akola	0.30	0.28	0.16	0.57	0.06		
	BIPC Buldhana	0.61	0.43	0.87	6.25	0.43		
	CADA Abad	0.36	0.42	0.27	0.42	0.27		
	CADA Beed	0.42	0.35	0.13	0.71	0.31	0.63	1
	CADA Jalgaon	0.56	0.50	0.49	0.78	0.44		
	CADA Nashik	0.95	0.65	0.52	1.48	0.65		
	NIC Nanded	0.39	0.18	0.01	0.60	0.18		
Normal	AIC Akola	0.41	0.16	0.19	12.73	0.16		
	CADA Abad	0.42	0.42	1.06	0.42	0.00		
	CADA Jalgaon	0.75	0.78	0.75	1.00	0.56		
	CADA Nashik	0.57	0.56	0.09	1.05	0.44	0.69	1
	CIPC	0.30	0.33	0.47	0.38	0.18		
	Chandrapur							
	NIC Nanded	0.20	0.25	0.02	0.57	0.13		
	PIC Pune	0.96	0.96	0.84	1.00	0.94		
	YIC Yavatmal	0.02	0.01	0.00	0.04	0.00		
Surplus	CADA Nagpur	0.18	0.54	0.14	0.55	0.05		
	CIPC	0.46	0.44	0.74	0.64	0.25	0.74	1
	Chandrapur						0.74	
Abundant	CIPC	0.50	0.39	0.58	0.64	0.39		
	Chandrapur							
	KIC Ratnagiri	0.51	0.10	0.31	2.32	0.10		
	SIC Sangli	0.59	0.59	0.71	1.10	0.34	0.65	1
	TIC Thane	0.17	0.25	0.12	0.56	0.10		

Indicator XII: Assessment recovery ratio (I) Highly deficit plan group:

CADA Beed: The average value of this indicator for projects under this circle has increased from 0.38 to 0.56. Khandeshwar is the only project to have attained the state norms. Turori have zero recoveries where as information for Jakapur project has been not submitted by the Project authorities' in spite of several reminders.

CADA Solapur: The ratio is lower from 0.29 (2007-08) to 0.13 (2008-09) which is far below the state norm

PIC Pune: Average assessment recovery ratio in six medium projects under this circle comes to 0.84 this year it is below state target.

Deficit Plan group:

AIC Akola & BIPC Buldhana: Recovery against assessment sanctioned during the year 2008-09 on group of projects under AIC Akola was low than last year & twice on projects under BIPC Buldhana.

CADA Aurangabad: The average value of this indicator for projects under this circle has decreased from 0.42 to 0.27.

CADA Beed: The average value of this indicator for projects under this circle has decreased from 0.35 to 0.13. Raigavan project has ratio 1.1, Tiru, Sakol, Masalga & Whati have recovery ratio of 1.0. & Deverjan project has the least ratio of 0.01which affected overall performance of the circle.

CADA Jalgaon: The ratio is just lowered from 0.50 (2007-08) to 0.49 (2008-09). More attention is required by field officers to improve the performance in all the projects except Burai.

CADA Nashik: The ratio is lowered from 0.65 (2007-08) to 0.52 (2008-09). There is much scope in all the projects to improve the performance.

NIC Nanded: The average value of this indicator for project under this circle has decreased from 0.18 to 0.01, Karadkhed project has the maximum ratio of 0.07.

Normal Plan group:

AIC Akola: In the Projects under AIC Akola, assessment recovery ratio is 0.19.

CADA Aurangabad: The average value of this indicator for projects under this circle has increased from 0.42 to 1.06. Dheku & Kolhi project achieved ratio of 1.0 as per state norms where as in Ambadi it is 0.60.

CADA Jalgaon: The ratio is lowered from 0.78 (2007-08) to 0.75 (2008-09) and it is below state norm. As such improvement is necessary.

CADA Nashik: The ratio is lowered from 0.56 (2007-08) to 0.10 (2008-09). Field officers are required to take necessary steps to improve the performance.

CIPC Chandrapur: Recovery against assessment on group of projects under this circle is 0.47 which is more than the last year performance (0.33).

NIC Nanded: The average value of this indicator for projects under this circle has decreased from 0.25 to 0.02. All the three projects namely Nagzari, Dongargaon & Loni have very low recovery against assessment.

PIC Pune: In Wadiwale Project the ratio is 0.84 which shows better recovery.

Surplus Plan Group:

CADA Nagpur: The ratio is reduced from 0.54 to 0.14 It is 86% lagging to the state norms value.


CIPC Chandrapur: Recovery against assessment on group of projects under CIPC Chandrapur is 0.74. It is more than the last year performance (0.44).

Abundant Plan Group:

CIPC Chandrapur: Recovery against assessment on group of projects under this circle is 0.58. It is more than the last year performance and state norms. **KIC Ratnagiri:** In Natuwadi Project the ratio increases to 0.31 from 0.10 of last year due to increase recovery.

SIC Sangli: The recovery is increased from 59% to 71% as compared to last year.

TIC Thane: The recovery is reduced from 25% to 12% as compared to last year.



Plan group	Circle	FY Avg	LY 2007-08	TY 2008-09	Past Max	Past Min	AVG Per	State Ta
Highly Deficit	CADA Beed	0.73	0.74	0.23	0.98	0.15	,	
	CADA Solapur	0.70	0.62	0.64	1.00	0.31	0.67	1
	PIC Pune	0.27	0.20	0.70	0.92	0.03		
Deficit	AIC Akola	0.78	0.71	0.97	1.38	0.49		
	BIPC Buldhana	1.00	1.00	1.00	1.00	0.00		
	CADA Abad	0.61	0.88	0.68	0.88	0.22		
	CADA Beed	0.40	0.37	0.42	0.71	0.30	0.88	1
	CADA Jalgaon	0.45	0.37	0.73	0.74	0.11		
	CADA Nashik	0.84	0.99	1.00	5.65	0.06		
	NIC Nanded	0.71	0.86	1.00	0.86	0.42		
Normal	AIC Akola	0.75	0.53	0.69	0.92	0.18		
	CADA Abad	0.71	1.00	0.89	1.00	0.00		
	CADA Jalgaon	0.79	0.68	0.70	1.38	0.33		
	CADA Nashik	0.93	0.38	0.78	0.94	0.00		
	CIPC Chandrapur	0.99	0.99	1.00	1.00	0.96	0.80	1
	NIC Nanded	0.60	1.00	1.00	1.00	0.35		
	PIC Pune	1.00	1.00	1.00	1.00	0.99		
	YIC Yavatmal	0.70	0.77	0.32	0.95	0.29		
Surplus	CADA Nagpur	1.76	1.00	0.96	6.34	0.93	0.96	1
	CIPC Chandrapur	0.69	0.67	0.20	0.86	0.00		
Abundant	CIPC Chandrapur	0.95	1.00	1.00	1.00	0.00		
	KIC Ratnagiri	1.16	1.00	0.70	4.25	0.00		
	SIC Sangli	0.46	0.78	0.56	0.98	0.23	0.57	1
	TIC Thane	1.00	0.00	0.00	1.00	0.00		

Indicator XII: Assessment recover ratio (NI) Highly deficit plan group:

CADA Beed: The average value of this indicator for projects under this circle has slightly decreased from 0.74 to 0.23. Kada is the only project to have attained required ratio of 1.00, Kurnoor has ratio of 0.19 and rest of the projects has ratio zero as there is no NI use in the projects.

CADA Solapur: It is increased from 62% to 64% compared to last year

PIC Pune: Average assessment ratio (NI) of six medium projects is 0.70. It increases from last year ratio of 0.20 due to increase in recovery of water charges of Non Irrigation use.

Deficit plan group:

AIC Akola & BIPC Buldhana: Recovery against assessment during the year 2008-09 on group of projects under AIC Akola Deficit was 97%, & it was up to the state target in BIPC Buldhana.

CADA Aurangabad: The average value of this indicator for projects under this circle has decreased from 0.88 to 0.68. Sukhana, Khelna, & Lahuki have attained the state norms i.e.1.00, where as in Galhati, Girija & Jui has no NI use which affect overall performance of the circle to fall down.

CADA Beed: The average value of this indicator for projects under this circle has increased from 0.37 to 0.42, Tawarja, Whati, Wan & Rui have attained the state norms. Many of the projects have no NI use resulting nil value of indicator.

CADA Jalgaon: The overall ratio is on lower side (73%).Improvement is necessary in case of Kanoli project.

CADA Nashik: The target is achieved in Haranbari & Kelzar projects. However improvement is required in Ghatshil Pargaon project.

NIC Nanded: The average value of this indicator for projects under this circle has increased from 0.86 to 1.00.

Normal Plan group:

YIC Yeotmal & AIC Akola: Assessment Recovery ratio on projects under these circles is 0.32 & 0.69 respectively.

CADA Aurangabad: The average value of this indicator for projects under this circle has decreased over its last year's value from 1.00 to 0.89. Ambadi has attained state norms, where as in Dheku it is zero.

CADA Jalgaon: The ratio is improved from 0.68 (2007-08) to 0.70 (2008-09).

CADA Nashik: The ratio has been improved from 0.38 (2007-08) to 0.78 (2008-09).

CIPC Chandrapur: 100% recovery has been achieved.

NIC Nanded: The average value of this indicator of the projects for this circle has retained its last year's value 1.00. Nagzari & Loni project has attained the state norms, where as in Dongargaon there is no NI use.

PIC Pune: In Wadiwale Project 100 % recovery has been achieved as that of last year.

Surplus Plan Group:

CADA Nagpur: 96 % recovery has been achieved as compared to last year's performance (100%)


CIPC Chandrapur: 20% recovery has been achieved as that of last year (67%).

Abundant Plan Group:

CIPC Chandrapur: 100% recovery has been achieved.

KIC Ratnagiri: In Natuwadi Project 70% recovery has been achieved this year.

SIC Sangli: The ratio is decreased from 78% to 56%.



Plan group	Circle	FY Avg	LY 2007-08	TY 2008-09	Past Max	Past	Avg	Stat
Linda La Da Cali		0.400				Min	Per	eTar
Highly Deficit	CADA Beed	6403	5045	6889	7974	0	5500	0007
	CADA Solapur	8406	11631	5432	11631	0	5509	6667
	PIC Pune	10107	12105	4208	18293	0		
Deficit	AIC Akola	4531	4040	4189	5854	3296		
	BIPC Buldhana	6037	8089	7834	8089	3589		
	CADA Abad	8485	7610	7354	10130	7582		000 7
	CADA Beed	5948	6452	5335	8694	3751	6000	6667
	CADA Jalgaon	5336	4774	4954	7292	4074		
	CADA Nashik	5504	5385	5321	10000	0		
	NIC Nanded	7407	6750	7015	8837	5116		
Normal	AIC Akola	306223	3169	0	1737052	0		
	BIPC Buldhana	5547	5798	2342	7316	0		
	CADA Jalgaon	7864	7362	7607	10367	6667		
	CADA Nagpur	5326	7436	0	7436	2968	6250	6667
	CADA Nashik	5500	5115	4768	7429	4497		
	CIPC	5260	6652	6034	6748	2403		
	Chandrapur							
	NIC Nanded	6042	7680	6377	7680	5271		
	PIC Pune	6910	6821	6464	10534	5600		
	YIC Yavatmal	10709	12169	13725	14713	0		
Surplus	CADA Nagpur	3297	4093	2990	4093	2690		6667
Abundant	CADA Pune	8520	6094	7263	19180	3125		
	CIPC	10039	7786	7237	12259	7786		
	Chandrapur							
	KIC Ratnagiri	22703	25000	25000	25000	1817 2	6517	6667
	NKIPC Thane	36261	45284	39470	45284	2968 8		
	SIC Sangli	5180	3001	5050	19476	3001		
	TIC Thane	20992	18092	19478	24866	1809 2		

Observations of Minor Projects

Indicator I: Annual Irrigation Water Supply per Unit Irrigated Area. Highly deficit Plan Group:

CADA Beed: The water use per unit irrigated area has increased from 5045cum/ha (2007-08) to 6889 cum/ha (2008-09), the ratio is above the State norms. Kinhi has value of 7840 cum/ha which is maximum and Bagalwadi has minimum value of 6369 cum/ha.

CADA Solapur: The average performance of this year is 5432 cum/ha, which is less than state norms. The water use is decreased by 55% compared to last year.

PIC Pune: Average Annual Irrigation Water Supply of Chinchodi Patil MI Tank is 4208 cum/ha. Shows improvement in performance as compared to last year and state norms.

Deficit Plan group:

AIC Akola: Annual irrigation water use on all grouped projects under AIC Akola was 4189 cum/Ha. Individually for vyaghra it was close to the state norm.

BIPC Buldhana: Water use on all projects under the circle taken together was less than last year. However Water use on Vidrupa, sawkhed bhoi & viswamitri was more but less on Masrul & Brahmanwada.

CADA Aurangabad: The performance has improved over last year by 3%. The average value of this indicator for the year decreased from 7610 cum/ha to 7354 cum/ha, though it is above State norms. Tandulwadi is the only project in this plan group.

CADA Beed: The performance has improved over last year. The water use has decreased from 6452 cum/ha to 5335 cum/ha. compared to last year. The average value of this indicator for this circle has decreased by 17% over last year; the indicator is well below the State norms. Bhutekarwadi project has maximum water use i.e. 5949cum/ha, Dhanori has 5804 cum/ha and Hiwarsinga has least value of 1594 cum/ha. Project authorities are advised to be more watchful in measurements of water utilized either by canal flow or Reservoir lift.

CADA Jalgaon: Though the water use is increased from 4774cum/ha to 4954cum/ha as compared to last year, it is below the state norms.

CADA Nashik: The water use is less than state norms since last three years. **NIC Nanded**: The average value of this indicator has increased from 6750

cum/ha to 7015 cum/ha. compared to last year.

Normal Plan group:

AIC Akola: As no irrigation was on Singdoh due to non availability of water.

BIPC Buldhana: Water use on Adol project is 2342 cum/ha.

CADA Jalgaon: The water use is increased from 7362cum/ha to 7607cum/ha as compared to last year and it is above state norms.

CADA Nashik: The water use is less than the state norms (72%).

CIPC Chandrapur: The average value of this indicator for the year is 6034 cum/ha.

NIC Nanded: There is improvement in performance. The average value of this indicator for this year has decreased from 7680 cum/ha to 6377 cum/ha, Nichpur has the maximum water use of 6689 cum/ha.

PIC Pune: Average annual irrigation water supply of two Minor Projects comes to 6464 cum/ha. this year. It is slightly below than last year value of 6821 cum/ha.

YIC Yeotmal: Water use on Manjra project is 13725 cum/ha.

Surplus Plan Group:

CADA Nagpur: Annual water use on projects under CADA Nagpur is 2990 cum/ha which is less than state norm due to low water intensive crops grown in the command, compared to last year, it is decreased.

Abundant Plan Group:

CADA Pune: In Thoseghar MI project annual irrigation water supply comes to 7263 cum/ha. It increases from last year performance.

CIPC Chandrapur: Annual water use on Lagam project is 7237 cum/ha. As compared to last year is decreased and less than the state target.

KIC Ratnagiri: In Shirval M.I. Project annual irrigation water supply comes to 25000 cum/ha. which is above the state target.

NKIPC Thane: In Dhasai M.I. Project of this circle annual irrigation water supply comes to 39470 cum/ha. which is better than last year but six time above the state target.

SIC Sangli: Annual water use on minor project under this circle is 5050 cum/ha which is less than state norms and increased than last year to some extent.

TIC Thane: The average water use is 19478 cum/ha. Which is nearly double than the state norms. and more than the last year use to some extent.

			dicator I a (-	-			
450 -	Annual	Area Irrig	ated per un	it of Water	Supplied	d (ha/Mm3	3)	
			Γ		п			
400 -						П		
350 -				Π			Π	1
300 -								
Č 250 -		—						
2 50 - 200		──┤─┲╟		─────────────────				
ہے 150 -								
100 -								
50 -								
0 -	ur Na Ine	ਤ ਨੂੰ ਤੁ	i i i i i i i i i i i i i i i i i i i	i s i i	per per	ह इ	iii g	ane gli:
	CADA Beed CADA Solapur PIC Pune AIC Akola BIPC Buldhana	CADA Abad CADA Beed CADA Jalgaon	CADA Nashik NIC Nanded AIC Akola	CADA Jalgaon CADA Nagpur CADA Nagpur CADA Nashik	Chandrapur NIC Nanded PIC Pune	YIC Yavatmal CADA Nagpur	Chandrapur KIC Ratnagiri	VKIPC Thane SIC Sangli TIC Thane
	CAD, DA S AIC	CAD/	ADA		PI Cha		Cha Cha Cha	
	BIF	C C C			CIPC Chandrapur NIC Nanded PIC Pune	5 3	CIPC Chandrapur KIC Ratnagiri	2
	Highly Deficit	Deficit		Norm		Surplus	Abund	ant
	FY A	vg 💶 LY 2	2007-08 TY	2008-09	Past Max 💼	🗖 Past Min 🗕		
Plan	Circle	FY	LY	ТҮ	Past	Past	Avg	State
group	Circle	Avg	2007-08	2008-09	Max	Min	Per	Tar
Highly								
Deficit	CADA Beed	156	198	145	198	125		
	CADA Solapur	119	86	184	119	86	189	150
	PIC Pune	99	83	238	99	55		
Deficit	AIC Akola	221	248	239	303	171		
	BIPC Buldhana	166	124	128	279	124		
	CADA Abad	118	131	136	132	99		
	CADA Beed	168	155	187	267	115	175	150
	CADA Jalgaon	187	209	202	245	137		
	CADA Nashik	182	186	188	186	100		
	NIC Nanded	135	148	143	195	113		
Normal	AIC Akola	3	316	NA 407	316	1		
	BIPC Buldhana	180	172	427	180	137		
	CADA Jalgaon	127	136	131	150	96	101	150
	CADA Nagpur CADA Nashik	188 182	134 196	NA 210	337 222	134 135	164	150
	CIPC	192	150	166	416	148		
	Chandrapur	150	150	100	410	140		
	NIC Nanded	166	130	157	190	130		
	PIC Pune	145	147	155	179	95		
	YIC Yavatmal	93	82	73	93	68		
Surplus	CADA Nagpur	303	244	334	372	244	334	150
Abundant	CADA Pune	117	164	138	320	52		
	CIPC	100	128	138	128	82		
	Chandrapur							4 = 0
	KIC Ratnagiri	44	40	40	55	40	158	150
	NKIPC Thane	28	22	25	34	22		
	SIC Sangli	193	333	198	333	51		
1	TIC Thane	48	55	51	55	40		

NA: Not available

Indicator I a: Annual Area irrigated per unit of water supplied (ha//Mm3). Highly deficit Plan Group:

CADA Beed: The overall area irrigated per unit of water supply (145 ha/Mm3) in the projects under this circle is nearly achieved state target.

CADA Solapur: Overall area irrigated per unit of water supplied is 184 ha/M3 in this year. Compared with last year it is increased by 114% & it is 23% more than the state target

PIC Pune: Overall area irrigated per unit of water supplied is 238 ha/Mm3 in this year. Compared with last year it is increased by 187% & it is 59 % more than the state target

Deficit Plan group:

AIC Akola: The area irrigated per unit of water supplied for minor project during this year is observed higher than State norm.

BIPC Buldhana: The area irrigated per unit of water supplied under BIPC Buldhana of minor project during this year is 128 Mm3 it fairly near to state norm of 150 ha/Mm3

CADA Aurangabad: The overall area irrigated per unit of water supply (136 ha/Mm3) in the projects under this circle is nearly achieved state target.

CADA Beed: The overall area irrigated per unit of water supply (187 ha/Mm3) in the projects under this circle is over takes state target, this may due to area irrigated on reservoir lift.

CADA Jalgaon: Due to less no o rotations the area irrigated per unit of water supplied is on higher side i.e. 202 ha/Mm3.

CADA Nashik: There is slight improvement as compared to last year (186 ha/Mm3) performance for this indicator (188 ha/Mm3) this is higher than the state norm due to this no of rotations.

NIC Nanded: The overall area irrigated per unit of water supply (143 ha/Mm3) in the projects under this circle is nearly achieved state target.

Normal Plan group:

AIC Akola: Singdoh Minor project is a due to non availability of water for irrigation

BIPC Buldhana: The area irrigated per unit of water supplied under BIPC Buldhana of minor projects is excessively high 427 ha./Mm3 due to less availability of water for irrigation.

CADA Jalgaon: The area irrigated per unit of water supplied is 131 ha/Mm3 which is less than state norm.

CADA Nashik: The overall area irrigated per unit of water supplied is improved from 196 ha/Mm3 to 210 ha/Mm3.

CIPC Chandrapur: Average166 ha/Mm3 area was irrigated per unit of water supplied for the projects under this circle.

NIC Nanded: The overall area irrigated per unit of water supply (157 ha/Mm3) in the projects under this circle is achieved state target and improved compared to last year.

PIC Pune: Over all area irrigated per unit of water supplied is 155 ha/Mm3) in this year. Compared with last year it is increased by 6%& it is 8% less than the state target

YIC Yeotmal: The area irrigated per unit of water supplied under YIC Yavatmal of Mozari minor project is only 73% less than state norm.

Surplus Plan Group:

CADA Nagpur: Average 334 ha/Mm3 area was irrigated per unit of water supplied for the projects under this circle. The value is on higher side due to Kharif utilization.

Abundant Plan Group:

CADA Pune: Over all area irrigated per unit of water supplied is 138 ha/Mm3 in this year. Compared with last year it is decreased by 16% & it is 8% less than.


CIPC Chandrapur: Average138 ha/Mm3 area was irrigated per unit of water supplied for the projects under this circle.

KIC Ratanagiri: Over all area irrigated per unit of water supplied is 40 ha/Mm3 in this year. Compared with last year it is same as last year & it is 74% less than the state target.

NKIPC Thane: Overall area irrigated per unit of water supplied is 25 ha/Mcum compared with last year, it is increased by 14% it is 84 % less than the state target

SIC Sangli: Over all area irrigated per unit of water supplied is 198 ha/Mm3 in this year. Compared with last year it is decreased by 41% & it is 32% more than the state target

TIC Thane: Over all area irrigated per unit of water supplied is 151 ha/Mm3 in this year. Compared with last year it is decreased by 8% & it is 66% less than the state target



Plan group	Circle	FY Avg	LY 2007- 08	TY 2008- 09	Past Max	Past Min	Avg Per	State Tar
Highly Deficit	CADA Beed	0.34	0.36	0.46	0.88	0		
	CADA Solapur	0.89	1.41	1.46	1.69	0.00	•	1.0
	PIC Pune	0.36	0.49	0.44	0.75	0.00		
Deficit	AIC Akola	0.65	0.63	0.92	1.30	0.36		
	BIPC Buldhana	0.57	0.48	0.27	1.03	0.29		
	CADA Abad	0.44	0.43	0.24	0.68	0.31	1.2	1.0
	CADA Beed	0.34	0.43	0.44	0.65	0.19		
	CADA Jalgaon	1.18	1.28	1.39	2.61	0.76		
	CADA Nashik	0.66	1.17	0.92	1.17	0.00		
	NIC Nanded	0.41	0.40	0.24	0.48	0.37		
Normal	AIC Akola	0.27	0.31	0.00	0.70	0.00		
	BIPC Buldhana	0.83	1.77	0.78	1.77	0.00		
	CADA Jalgaon	1.00	1.51	1.50	1.51	0.68		
	CADA Nagpur	0.49	0.46	0.00	0.70	0.36	0.7	1.0
	CADA Nashik	1.01	1.36	1.31	1.36	0.36		
	CIPC	0.94	0.50	0.77	1.00	0.50		
	Chandrapur							
	NIC Nanded	0.47	1.74	0.54	1.74	0.16		
	PIC Pune	1.57	1.12	1.20	14.54	0.99		
-	YIC Yavatmal	0.46	0.13	0.08	18.13	0.00		
Surplus	CADA Nagpur	0.84	0.86	1.34	0.97	0.74		1.0
Abundant	CADA Pune	0.41	0.24	0.35	1.00	0.19		
	CIPC	0.93	1.15	0.81	1.15	0.70		
	Chandrapur							
	KIC Ratnagiri	0.44	0.35	0.38	0.47	0.35		
	NKIPC Thane	0.22	0.22	0.21	0.28	0.14	0.8	1.0
	SIC Sangli	0.51	0.78	0.43	1.86	0.10		
	TIC Thane	0.64	0.64	0.70	0.98	0.50		

Indicator II: Potential Utilised and created Highly deficit Plan Group:

CADA Beed: The performance of this indicator has improved over the last year by 27%. The average ratio of this indicator has increased from 0.36 to 0.46 for this year 2008-09. But it is still below State norms. Tintraj has the maximum value of 0.58

CADA Solapur: The ratio for this indicator is 1.46 it is more than last year and as well as state norms.

PIC Pune: The potential utilization of Chichondi Patil M.I. Tank is 0.44 which is less than state norms.

Deficit Plan group:

AIC Akola: The ratio for potential utilized & created for projects was 0.92

BIPC Buldhana The ratio for potential utilized & created for project under this circle was 0.27 low than last year.

CADA Aurangabad: The performance of this indicator has decreased over last year by 44%. The average ratio of this indicator for this year has decreased from 0.43 to 0.24. Project authorities should take efforts to attain State norms.

CADA Beed: The average ratio of the indicator for this year 2008-09 has increased slightly from 0.43 to 0.44 and is below State norms. Dhanori has maximum potential utilized i.e. 1.49.

CADA Jalgaon: The ratio is one for last three years, which is up to the State target.

CADA Nashik: The performance is lowered as compared to last year (92%).

NIC Nanded: It has decreased over last year by 40%. The average ratio of this indicator has decreased from 0.40 to 0.24 and is below State norms. Wasur project has maximum ratio i.e. 0.52

Normal plan group:

BIPC Buldhana: Actual potential utilisation compared to created potential on Adol project under BIPC Buldhana was 78%.

CADA Jalgaon: The ratio is with the state norms.

CADA Nashik: The ratio is one for last three years which is up to the State target.

CIPC Chandrapur: The ratio of actual potential utilization compared to created for projects under CIPC is 0.77.

NIC Nanded: There is a decrease in the performance over last year by 68%. The average ratio of this indicator has decreased from 1.74 to 0.54 which is below State norms.

PIC Pune: Average utilised potential of Two Minor Projects comes to 1.00 this year. It is same as last year.

YIC Yeotmal: Actual potential utilisation compared to created potential on projects under YIC Yeotmal is 8%.

Surplus Plan Group:

CADA Nagpur: Potential utilisation is more (1.34) than the state target.

Abundant Plan Group:

CADA Pune: In Thoseghar M.I, project potential utilization ratio comes to 0.35. It increases from last year value of 0.24.


CIPC Chandrapur: Potential utilisation is 81% on an average on projects under this circle.

KIC Ratnagiri: In Shirval MI Project annual utilised potential ratio comes to 0.38 which is below state target.

NKIPC Thane: Average potential utilization of Two M.I. Projects of this circle comes to 0.21 which is below than last year and the state target.

SIC Sangli: The ratio for this indicator is 0.43 it is more than last year less than the state norm.

TIC Thane: The ratio is 0.70 which is more than last year & less than the state norm.



			LY					_
	e	FY	2007-	ΤY	Past		Avg	State
Plan group	Circle	Avg	08	2008-09	Max	Past Min	Per	Target
Highly		0.405	0.404	40400	40540		•	40000
Deficit	CADA Beed	9495	8401	10166	13518	0	0	16000
	CADA Solapur	21366	22296	22018	25446	0		
	PIC Pune	20082	25391	55693	25391	0		
Deficit		79922	4 4 4 0 0 0	00040	271023	404004	00470	04000
Deficit	AIC Akola	0	144382	28616	9	101094	20472	21000
	BIPC Buldhana	34157	45568	40967	48695	27155		
	CADA Abad	33888	53659	35398	55310	6667		
	CADA Beed	21357	9769	18857	37216	9769		
	CADA Jalgaon	17935	26017	11792	26017	10220		
	CADA Nashik	12896	10855	13761	17111	0		
	NIC Nanded	20392	13097	14409	24140	13097		
Normal	AIC Akola	26447	45333	0	45333	0	13251	21000
	BIPC Buldhana	32168	42105	19000	42105	0		
	CADA Jalgaon	9819	6368	4705	17715	0		
	CADA Nagpur	8996	11169	0	15167	0		
	CADA Nashik	18528	14723	15991	32586	13358		
	CIPC							
	Chandrapur	23059	17586	17948	24417	7390		
	NIC Nanded	17089	11680	16110	21756	11680		
	PIC Pune	26286	27526	26092	50141	13117		
	YIC Yavatmal	7795	2831	19412	100000	0		
Surplus	CADA Nagpur	17479	18406	9251	22728	13891	9251	27000
Abundant	CADA Pune	9529	15906	14137	16875	3770	20396	36000
	CIPC							
	Chandrapur	19403	17299	24498	24700	14458		
		13169						
	KIC Ratnagiri	0	151029	149040	151029	102312		
	NKIPC Thane	98726	148038	49575	153113	57604		
	SIC Sangli	26425	21343	60976	51844	17525		
	TIC Thane	36130	29814	22554	59317	22849		

Indicator III: Output Per Unit Irrigated Area (Rs./ha) Highly deficit Plan Group:

CADA Beed: The average performance of this circle has improved slightly over past year. The average value of this indicator has increased from Rs.8401/ha to Rs 10166 /ha which is still below State norms of Rs 16000/ha. Bagalwadi project has maximum output of Rs12375/ha.

CADA Solapur: Output is Rs. 22018/ha.It is less than the last year & more than the state norm.

PIC Pune: In Chichondi Patil M.I. Tank output comes to Rs.55693/ha. The performance is better as compared to state target & last year.

Deficit Plan Group:

AIC Akola: Output per unit irrigated area on projects under this circle was high (Rs.28616/ha).

BIPC Buldhana: Out put per unit irrigated area was high. It was Rs. 40967/ha.

CADA Aurangabad: The average value of this indicator though decreased from Rs. 53659/ha to Rs.35398/ha compared to last year it is still more than state norms.

CADA Beed: There is an increase of 180% over last year. The average value of this indicator has increased from Rs. 9769/ha to Rs.18857./ha. Bhutekarwadi has the average of Rs 30408/ha. The average value of the circle under this Plan group is 11% below State norms i.e. Rs. 21,000 /ha.

CADA Jalgaon: The overall out put is lowered from Rs26017/ha to Rs11792/ha as compared to last year and it is below state norms.

CADA Nashik: The out put is increased from Rs10855/ha to Rs13761/ha as compared to last year and which is 66% of the State target.

NIC Nanded: The average performance of this circle though increased from Rs. 13097/ha to Rs. 14409/ha. compared to last year, It is still below state norms.

Normal Plan Group:

BIPC Buldhana: Out put per unit irrigated area was Rs. 19000/ha on Adol project close compared to state target.

CADA Jalgaon: The out put is 22% to the state norms only.

CADA Nashik: The out put is 76% of the state norms.

CIPC Chandrapur: Out put on projects under the circle were low (Rs. 17948 /ha) than state target & better than last years performance (Rs.17586 /ha). **NIC Nanded**: There is improvement in performance over last year. But still it is below State norms. The average value of indicator has increased from Rs 11680/ha to Rs.16110 /ha for this year 2008-09. Amthana has maximum output of Rs27692/ha.

PIC Pune: Average output in two Minor Projects of this circle comes to Rs. 26092/ha. This is below than last year but above state target.

YIC Yeotmal: Output per unit irrigated area on Manjra project under this circle was Rs 19412/ha.

Surplus Plan Group:

CADA Nagpur: Out put on projects under the circle were lowered (Rs.9251/ha) in comparison with state target as well as last year out put (Rs.18406 /ha).

Abundant Plan Group:


CADA Pune: Annual output in Thoseghar M.I. Project comes to Rs. 14137/ha this year, decrease from Rs. 15906/ha of last year.

CIPC Chandrapur: Out put on projects under the circle is Rs. 24498 /ha in comparison with state target It is to much less & improved compared with last year performance.

KIC Ratnagiri: In Shirval M.I. Project agricultural output comes to Rs. 1,49,040/ha which is decreased from last year.

NKIPC Thane: Average Agricultural output of Two Minor Projects is Rs. 49575/ha which decreased from Rs. 148038/ha of last year.

SIC Sangli: Out put Rs. 60976/- It is more than last year & state norm **TIC Thane:** Out put Rs. 22554/- It is less than last year & state norm.



L				TV				
		FY	LY 2007-	TY 2008-	Past	Past	Avg	State
Plan group	Circle	Avg	08	09	Max	Min	Per	Target
Highly Deficit	CADA Beed	1.82	1.67	1.48	2.09	0		
riigiliy Denoit	CADA Solapur	4.41	3.25	6.41	7.06	0.00	3.95	2.4
	PIC Pune	2.90	3.55	13.24	3.55	0.00	0.00	
Deficit	AIC Akola	165.50	29.18	4.79	520.33	23.72		
2 0.101	BIPC Buldhana	6.22	6.88	5.23	13.57	4.73		
	CADA Abad	4.61	7.05	4.81	9.06	1.14		
	CADA Beed	3.77	1.56	3.59	6.60	1.56	3.9	3.15
	CADA Jalgaon	4.95	9.93	4.00	9.93	2.22		
	CADA Nashik	2.56	2.32	2.59	3.27	0.00		
	NIC Nanded	3.04	2.13	2.60	4.20	2.13		
Normal	AIC Akola	0.06	7.56	0.00	7.56	0.00		
	BIPC Buldhana	7.26	9.10	8.11	9.10	0.00		
	CADA Jalgaon	1.41	1.29	0.92	2.66	0.00		
	CADA Nagpur	1.81	1.75	0.00	5.11	0.00		
	CADA Nashik	5.73	5.38	5.73	8.00	4.27	2.7	3.15
	CIPC	4.45	3.19	3.58	4.61	2.63		
	Chandrapur							
	NIC Nanded	3.33	2.09	3.33	4.09	2.09		
	PIC Pune	4.22	4.27	4.21	8.64	2.08		
	YIC Yavatmal	2.32	0.23	1.41	6.80	0.00		
Surplus	CADA Nagpur	5.29	4.18	3.12	7.68	4.12	3.1	4.05
Abundant	CADA Pune	1.88	2.61	1.95	5.40	0.82		
	CIPC	2.07	3.15	3.38	3.15	1.48		
	Chandrapur				0.00			
	KIC Ratnagiri	5.80	6.04	5.96	6.23	5.55		- 40
	NKIPC Thane	2.80	3.85	1.26	3.85	1.94	3.3	5.40
	SIC Sangli	4.26	6.39	6.19	6.39	0.92		
	TIC Thane	1.72	1.65	1.16	3.08	0.92		

Indicator IV: Output per Unit Irrigation Water Supply Rs./cum Highly Deficit Plan Group:

CADA Beed: The average value of this indicator has decreased from Rs.1.67/cum (2007-08) to 1.48 for 2008-09. Bagalwadi has the maximum ratio i.e. Rs. 1.94/cum.

CADA Solapur: Output per unit water supply comes to Rs.6.41/cum

PIC Pune: In Chichondi Patil MI Tank the output per unit water supply comes to Rs. 13.24/cum. It is above the state norms.

Deficit Plan Group:

AIC Akola: Output per unit water supply observed on projects under this circle was high i.e. Rs.4.79/cum.

BIPC Buldhana: Output per unit water supply observed on project was Rs 5.23/ cum which was very high to state target.

CADA Aurangabad: The performance has decreased from Rs 7.05/cum to Rs.4.81/cum compared to last year, there is a decline of 32% though it is above state norms.

CADA Beed: It has improved over last year performance and gone above state norms, the average ratio of 2008-09 is increased from 1.56 to 3.59, Bhutekarwadi project has the maximum output i.e. Rs 5.24 /cum.

CADA Jalgaon: The out put per cum is more than state norms.

CADA Nashik: The out put per cum is 82% of the state norms.

NIC Nanded: The performance has increased over last year by 22% though it is below state norms. The average value of indicator has increased from 2.13 to 2.60. Panshewadi has the maximum output i.e. Rs 4.70/ha.

Normal Plan Group:

BIPC Buldhana: Output under this circle was high due to low water use per unit irrigated area i.e. 8.11.

CADA Jalgaon: The out put is well below (29%) the state norms

CADA Nashik: The out put per cum is 1.8 times the state norms.

CIPC Chandrapur: The performance for this indicator is Rs. 3.58/cum compared to last year performance (Rs.3.19/cum); It is increased to some extent.

NIC Nanded: There is improvement over last year's performance 2.09 to 3.33 in this year achieving state norms. Nichpur has the maximum output i.e. Rs 4.12/cum

PIC Pune: Average output per unit water supply in two Minor Projects comes to Rs. 4.21/cum increased from Rs. 4.00/cum of last year.

YIC Yeotmal: Output per unit irrigation water supply was observed very less on projects under this circle (1.41).

Surplus Plan Group:

CADA Nagpur: Output per unit water supply observed on projects under this circle in group was Rs 3.12/cum as compared to last year performance (Rs. 4.18/cum) It is decreased to some extent.

Abundant Plan Group:

CADA Pune: In Thoseghar M.I. Project the output per unit irrigated water decreased from Rs.2.61/cum of last year to Rs. 1.95/cum this year.


CIPC Chandrapur: Output on projects under the circle was (Rs. 3.38/cum). As compared to last year performance (Rs.3.15/cum), it is increased to some extent.

KIC Ratnagiri: In Shirval Project the output decreases from Rs. 6.00/cum of last year to Rs. 5.96/cum this year and it is above state target.

NKIPC Thane: Average agricultural output of two MI Projects decreases from Rs. 3.85/cum of last year to Rs. 1.26/Cum this year. It is below the state target.

SIC Sangli: Output per unit water supply is reduced from Rs. 6.39/cum (2007-08) to Rs. 6.19/cum in this year.

TIC Thane: Output per unit water supply is reduced from Rs. 1.65/cum (2007-08) to Rs. 1.16/cum in this year.



Plan group	Circle	FY Avg	LY 2007- 08	TY 2008- 09	Past Max	Past Min	Avg Per	State Target
Highly Deficit	CADA Beed	0.09	0.05	0.07	0.21	0.00		
	CADA Solapur	0.06	0.04	0.48	0.24	0.00		1.0
	PIC Pune	0.12	0.42	0.18	0.42	0.00		
Deficit	AIC Akola	0.44	0.11	0.02	0.54	0.11		
	BIPC Buldhana	0.23	0.23	0.00	0.42	0.13		
	CADA Abad	0.09	0.04	0.00	0.15	0.02	0.7	1.0
	CADA Beed	0.30	0.38	0.66	0.51	0.08		
	CADA Jalgaon	0.22	0.23	0.11	0.34	0.19		
	CADA Nashik	0.05	0.11	0.03	0.11	0.00		
	NIC Nanded	0.12	0.08	0.03	0.32	0.08		
Normal	AIC Akola	0.16	0.55	0.28	1.00	0.00	0.3	1.0
	BIPC Buldhana	0.97	1.8	1.44	1.8	0.6		
	CADA Jalgaon	0.27	0.23	0.43	0.44	0.15		
	CADA Nagpur	0.45	1.55	0.14	1.55	0.13		
	CADA Nashik	0.07	0.07	0.08	0.08	0.07	1.4	1.0
	CIPC Chandrapur	0.26	0.18	0.06	0.31	0.11		
	NIC Nanded	0.15	0.12	0.03	0.23	0.07		
	PIC Pune	0.64	0.76	0.12	0.86	0.42		
	YIC Yavatmal	1.00	0.11	0.00	18.00	0.11		
Surplus	CADA Nagpur	0.25	0.30	0.15	0.43	0.16		1.00
Abundant	CADA Pune	0.03	0.01	0.08	0.35	0.01		
	CIPC Chandrapur	0.27	0.35	0.13	0.35	0.14		
	KIC Ratnagiri	0.16	0.19	0.77	0.22	0.07		
	NKIPC Thane	0.10	0.09	0.12	0.25	0.06	0.8	1.0
	SIC Sangli	0.23	0.62	0.49	0.62	0.00		
	TIC Thane	0.23	0.11	0.14	0.37	0.11		

Indicator V: Cost Recovery Ratio

Highly Deficit Plan Group:

CADA Beed: The performance of this indicator has increased from 0.05 to 0.07in this year 2008-09.

CADA Solapur: The performance of this indicator has increased from 0.04 to 0.48 in this year 2008-09.

PIC Pune: The ratio for Chichondi Patil MI Tank comes to 0.18 this year. It is below the state norms.

Deficit Plan Group:

AIC Akola: Ratio was lower on projects under this circle (0.02).

CADA Aurangabad: Average performance has declined from 0.04 to 0.00.

CADA Beed: The performance has increased from 0.38 to 0.66 though it is 34% below State norms.

CADA Jalgaon: The ratio is only 0.11, which is far below the state norms.

CADA Nashik: The ratio is only 0.03, which is far below the state norms

NIC Nanded: There is drastic decline over past performance. The average value has decreased from 0.08 to 0.03 in this year which is far below the state norm.

Normal Plan Group:

AIC Akola, BIPC Buldhana: The ratio was found (0.28) exceptionally low on koradi projects of AIC Akola but above state target value on projects under BIPC Buldhana it was above 1.

CADA Jalgaon: The ratio is 0.43 which is far below the state norm.

CADA Nashik: The ratio is 0.08 since last two years which is below the state norms.

CIPC Chandrapur: Average cost recovery ratio of MI Projects under this circle has decreased from 0.18 of last year to 0.06 this year.

NIC Nanded: There is decline by 75% over past performance. The average value of this indicator has decreased from 0.12 to 0.03 in this year which is far below the state norm.

PIC Pune: Average cost recovery ratio of two MI Projects decreases from 0.76 of last year to 0.12 of this year.

Surplus Plan Group:

CADA Nagpur: Cost recovery ratio is low (0.15) as compared to last year performance (0.30).

Abundant Plan Group:

CADA Pune: In Thoseghar Project the cost recovery ratio comes to 0.08 this year.


CIPC Chandrapur: Cost recovery ratio was low (0.13) compared to state norm and decreased than its last year value (0.35).

KIC Ratnagiri: In Shirval Project the cost recovery ratio increased from 0.19 last year to 0.77 this year. It is below state target.

NKIPC Thane: Average cost recovery ratio of two M.I. Project comes to 0.12 this year is very much low as compared to state target.

SIC Sangli: The performance of this indicator has decreased from 0.62 to 0.49 in this year 2008-09.

TIC Thane: The performance of this indicator has increased from 0.11 to 0.14 in this year 2008-09.



Dian group	Circle	FY	LY 2007- 08	TY 2008- 09	Past Max	Past Min	Avg Per	State
Plan group	CADA Beed	Avg 1762	3031	2236	3031		Per	Target
Highly Deficit	CADA Beed CADA Solapur	2969	303 I 4659	2236 664	4659	0	664	1150
	PIC Pune	2303	756	2079	5958	0	004	1150
Deficit	AIC Akola	4458	3647	20194	11088	1285		
Donon	BIPC Buldhana	921	1261	2149	1469	320		
	CADA Abad	1221	1298	127	1675	852		
	CADA Beed	1377	2133	1981	2133	887	816	1150
	CADA Jalgaon	1247	1608	1505	1608	679		
	CADA Nashik	3162	2442	2991	4787	0		
	NIC Nanded	2486	4143	12630	4143	1114		
Normal	AIC Akola	3132	1307	0	4938	0		
	BIPC Buldhana	288	110	309	1512	0		
	CADA Jalgaon	1841	1050	804	4310	1005		
	CADA Nagpur	752	367	0	1092	367		
	CADA Nashik	535	704	450	933	286	926	1150
	CIPC Chandrapur	774	3318	3449	4238	567		
	NIC Nanded	1847	1987	2482	3104	998		
	PIC Pune	516	244	844	654	244		
	YIC Yavatmal	72729	476	0	1462956	0		
Surplus	CADA Nagpur	1036	1015	976	1686	726	976	1150
Abundant	CADA Pune	8859	9359	3032	9359	1250		
	CIPC Chandrapur	766	607	1869	1166	260		
	KIC Ratnagiri	2346	3686	3680	3686	1161		1150
	NKIPC Thane	8462	11835	11426	14210	3485		
	SIC Sangli	2481	896	2715	15571	896		
	TIC Thane	5118	9824	12902	9824	3182		

Indicator VI: O & M Cost per Unit Area (Rs./ha) Highly Deficit Plan Group:

CADA Beed: The O & M cost per unit area for this year has decreased from Rs 3031/ha to Rs. 2236 /ha though it is above State norms of Rs.1150 /ha. Kinhi project has the maximum of Rs.6099/ha. where as in Incharna project it has minimum of Rs.1339/ha.

CADA Solapur: The average value of the indicator has decreased from Rs. 4659/ha to Rs 664/ha.

PIC Pune: The O & M cost per unit irrigated area for Chichondi Patil M.I. Tank is Rs.2079/ha it is above the state target and more than last year performance.

Deficit Plan group:

AIC Akola: The O & M cost per unit area irrigated on projects under AIC Akola was 20194/Ha.

BIPC Buldhana The O & M cost per unit area irrigated on projects under BIPC Buldhana was Rs. 2149/Ha.

CADA Aurangabad: The average value of the indicator has decreased from Rs. 1298/ha to Rs. 127/ha. which is below the state norms. Tandulwadi is the only representing project in this Plan group.

CADA Beed: The average value of the indicator has decreased for the year 2008-09 from Rs. 2133/ha to Rs. 1981/ha. It has decreased over last year by 7%. But it is still above the state norms. Hiwarsinga project has the maximum of Rs.10609 /ha.

CADA Jalgaon: The O & M cost per unit area is increased by 30% to state norms.

CADA Nashik: The O & M cost per unit area is 2.6 times more than the state norms.

NIC Nanded: There is increase in the average value of the indicator by 35%. The average value for the year 2008-09 has increased from Rs 4143/ha to Rs.12630/ha. The value is above 10 times the State norms. This due to increase in O & M cost in Wasur, Koshtewadi & Panshewadi projects compared to last year.

Normal Plan Group:

BIPC Buldhana: The O & M cost per unit area irrigated on projects under BIPC Buldhana was Rs.309/Ha

CADA Jalgaon: The O & M cost per unit area is lowered from Rs1050/ha to Rs804/ha, which is below the state norms.

CADA Nashik: The O & M cost per unit area is well below the state norms from last two years.

CIPC Chandrapur: The ratio is Rs 3449 /ha on projects under the circle as compared to last y ears (Rs.3318 /ha), It is increased to some extent.

NIC Nanded: The average value of O & M cost has increased from Rs1987/ha (2007-08) to Rs.2482/ha (2008-09) which is above the State norms. Nichpur has the maximum value for this indicator i.e. Rs 4049/ha.

PIC Pune: Average O & M cost per unit irrigated area of Rahu MI Project is decreased to Rs. 214/ha, from Rs. 244/ha, of last year and in Tambve MI Project increased to Rs. 3178/ha.from Rs. 734/ha, of last year.

Surplus Plan Group:

CADA Nagpur: The value is Rs.976 /ha on projects under the circle as compared to last year Rs. 1015 /ha. It is decreased to some extent.

Abundant Plan Group:

CADA Pune: In Thoseghar MI Project the O & M Cost ratio decreases from Rs.9359/ha to Rs. 3032/ha. Still the performance is very poor as compared to state norms and last year.


CIPC Chandrapur: The ratio was well within state norm on projects (Rs.1869/ha) & in comparison with last years performance (Rs.607/ha) under the circle, It is increased marginally.

KIC Ratnagiri: In Shirval Project the O & M Cost per unit area comes to Rs. 3680/ha this year. The performance is poor as compared to state target.

NKIPC Thane: Average O & M Cost of two MI Projects decreases from Rs. 11835/ha of last year to Rs. 11426/ha this year. Still the performance is poor as compared to state norms.

SIC Sangli: The average value of the indicator has increased from Rs. 896/ha to Rs 2715 per ha.

TIC Thane: The average value of the indicator has increased from Rs. 9824/ha to Rs 12902 per ha.



Plan		FY	LY	TY	Past	Past	Avg	State
group	Circle	Avg	2007-08	2008-09	Max	Min	Per	Target
Highly								
Deficit	CADA Beed	0.36	0.82	0.32	0.82	0		
	CADA Solapur	0.52	0.60	0.19	32.13	0.00	0.19	0.17
	PIC Pune	0.29	0.10	0.44	0.78	0.00		
Deficit	AIC Akola	0.93	0.81	2.78	2.04	0.29		
	BIPC Buldhana	0.16	0.18	44.80	0.32	0.07		
	CADA Abad	0.16	0.17	0.02	0.21	0.10		
	CADA Beed	0.23	0.30	0.38	0.48	0.14	0.25	0.17
	CADA Jalgaon	0.31	0.53	0.49	0.53	0.14		
	CADA Nashik	0.56	0.52	0.47	0.75	0.00		
	NIC Nanded	0.37	0.67	2.21	0.67	0.13		
Normal	AIC Akola	0.34	0.22	0.00	0.46	0.00		
	BIPC Buldhana	0.06	0.02	0.11	0.33	0.02		
	CADA Jalgaon	0.26	0.21	0.16	0.45	0.15		
	CADA Nagpur	0.15	0.06	0.00	0.32	0.06	0.10	0.17
	CADA Nashik	0.16	0.26	0.16	0.26	0.10		
	CIPC	0.15	0.65	0.69	0.65	0.11		
	Chandrapur							
	NIC Nanded	0.36	0.33	0.51	0.60	0.19		
	PIC Pune	0.08	0.04	0.14	0.11	0.04		
	YIC Yavatmal	21.66	0.04	0.00	99.44	0.00		
Surplus	CADA Nagpur	0.31	0.23	0.33	0.54	0.23	0.23	0.17
Abundant	CADA Pune	1.74	1.54	0.42	1.74	0.07		
	CIPC	0.08	0.12	0.26	0.12	0.03		
	Chandrapur							
	KIC Ratnagiri	0.10	0.15	0.15	0.18	0.05	0.24	0.17
	NKIPC Thane	0.24	0.31	0.29	0.33	0.12		
	SIC Sangli	0.39	0.27	0.27	0.80	0.27		
	TIC Thane	0.24	0.53	0.57	0.53	0.14		

Indicator VII: O & M Cost Per Unit of Water Supply (Rs/cum) Highly Deficit Plan Group:

CADA Beed: The average performance of this indicator has decreased from Rs.0.82/cum to Rs. 0.32/cum compared to last year.

CADA Solapur: The average performance of this indicator has decreased from Rs.0.60/cum to Rs.0.19/cum.

PIC Pune: In Chichondi Patil MI Tank the O. & M. cost per unit water supply is Rs. 0.44/ha, which is above the state norms.

Deficit Plan group:

AIC Akola & BIPC Buldhana: Due to moderate O & M expenditure and economic water use, the ratio has very high value compared to state norm on projects under AIC Akola. It was exceptionally high with state norm on projects under BIPC Buldhana.

CADA Aurangabad: The average value of the indicator has decreased from Rs 0.17/cum to Rs.0.02/cum.The performance has improved over last year by 82% and has achieved the State norms. Tandulwadi is the only representing project under this Plan group.

CADA Beed: The average value of the indicator has increased from Rs 0.30/cum to Rs.0.38/cum. Hiwarsinga has the maximum value of Rs 6.65/cum. Bhutekarwadi has the least value of Rs 0.17/cum.

CADA Jalgaon: The O & M cost per unit of water supplied is nearly 3 times more than the state norms. The cost is increasing for last four years.

CADA Nashik: The O & M cost per unit of water supplied is 2.75 times more than state norms. The cost is increasing for last four years.

NIC Nanded: The average value of the indicator has increased from Rs 0.67/cum to Rs. 2.21/cum this year. Wasur has the maximum value of Rs9.2/cum. Purjal has the least value of Rs. 0.08/cum.

Normal Plan Group:

BIPC Buldhana: On Adol project under BIPC Buldhana the indicator value is Rs. 0.11 /cum which is below the state norm of Rs 0.17/cum.

CADA Jalgaon: The O & M cost per unit of water supplied is nearer to the state norms.

CADA Nashik: The O & M cost per unit of water supplied is nearer to the state norms.

CIPC Chandrapur: O & M Cost per unit water supplied is Rs. 0.69 /cum as compared to Rs. 0.65 /cum during last year.

NIC Nanded: The performance indicator has increased from Rs 0.33/cum to Rs. 0.51/cum. In Nichpur project has the maximum value i.e. 0.80.

PIC Pune: Average O & M Cost per unit of water supply of Two MI Project increases to Rs. 0.14/cum this year from Rs. 0.04/cum last year but it is below the state target.

Surplus Plan Group:

CADA Nagpur: O&M cost per unit area irrigated on projects under the circle has more value (Rs 0.33/ha) It is more than the state target.

Abundant Plan Group:

CADA Pune : In Thoseghar MI Project the O & M Cost per unit water supply decreased to Rs. 0.42/ cum this year from Rs. 1.25/cum of last year. But it is above the state target. Field Officers are required to do needful action for reducing expenditure on maintenance.


CIPC Chandrapur: O & M Cost per unit water supplied is Rs. 0.26 /cum as compared to Rs. 0.12 /cum during last year.

KIC Ratnagiri: In Shirval MI Project the O & M Cost per unit water supply comes to Rs. 0.15/cum this year. This is within the state norms.

NKIPC Thane : Average O & M Cost per unit water supply of two Minor Projects decreases from Rs. 0.31/cum to Rs. 0.29 this year.

SIC Sangli: The average performance of this indicator has same value as per last year i.e. Rs 0.27/cum.

TIC Thane: The average performance of this indicator has increased slightly from Rs.0.53/cum to Rs. 0.57 per cum.



Plan group	Circle	FY Avg	LY 2007-08	TY 2008-09	Past Max	Past Min	Avg Per	State Target
Highly Deficit	CADA Beed	0.03	0.04	0.02	0.50	0	I	0.19
	CADA Solapur	0.03	0.02	0.09	0.38	0.00		
	PIC Pune	0.03	0.04	0.08	0.42	0.00		
Deficit	AIC Akola	0.40	0.09	0.06	11.08	0.81		
	BIPC Buldhana	0.04	0.04	0.06	1.05	0.24		
	CADA Abad	0.01	0.01	0.00	0.23	0.03		
	CADA Beed	0.07	0.11	0.25	1.14	0.11	0.3	0.19
	CADA Jalgaon	0.07	0.12	0.06	1.21	0.46		
	CADA Nashik	0.03	0.06	0.02	0.57	0.00		
	NIC Nanded	0.05	0.06	0.06	0.59	0.32		
Normal	AIC Akola	0.05	0.12	0.00	1.20	0.00		
	BIPC Buldhana	0.06	0.04	0.15	2.20	0.43		
	CADA Jalgaon	0.07	0.05	0.07	1.96	0.42		
	CADA Nagpur	0.07	0.09	0.00	1.01	0.22		
	CADA Nashik	0.01	0.02	0.01	0.17	0.07	0.0	0.19
	CIPC	0.04	0.12	0.04	1.20	0.33		
	Chandrapur							
	NIC Nanded	0.05	0.04	0.02	0.67	0.40		
	PIC Pune	0.05	0.03	0.02	0.73	0.29		
	YIC Yavatmal	21.62	0.00	0.00	994.34	0.00		
Surplus	CADA Nagpur	0.08	0.07	0.05	1.17	0.57		0.19
Abundant	CADA Pune	0.05	0.06	0.03	1.00	0.21		
	CIPC	0.02	0.04	0.03	0.43	0.04		
	Chandrapur							
	KIC Ratnagiri	0.02	0.03	0.11	0.31	0.04		
	NKIPC Thane	0.02	0.03	0.03	0.29	0.17	0.1	0.19
	SIC Sangli	0.09	0.17	0.13	1.65	0.00		
	TIC Thane	0.05	0.06	0.08	0.76	0.43		

Indicator VIII: Revenue Per Unit of Water Supplied Rs./cum Highly Deficit Plan Group:

CADA Beed: The average value of this indicator for minor project under this circle has decreased from Rs 0.04/cum to Rs.0.02/cum. Tintraj has the maximum value for the indicator Rs0.03/cum. Most of the projects have low value of the indicator.

CADA Solapur: Revenue per unit water supply is increased from Rs. 0.02/cum (2007-08) to Rs.0.09/cum in 2008-09.

PIC Pune: In Chichondi Patil MI Tank the revenue per unit water supply is Rs.0.08/cum which is below the state norms.

Deficit Plan Group:

AIC Akola, BIPC Buldhana: Revenue collected per unit water supplied on all projects under this plan group was less than Rs. 0.10/cum against state norm of Rs. 0.19 /cum. This indicates low revenue recovery.

CADA Aurangabad: The average value of this indicator for minor projects under this circle has decreased from 0.01 to zero. It has again declined over last years performance. Field officers has to take efforts in revenue collection to achieve state target.

CADA Beed: The average value of this indicator for minor project under this circle has increased over last years value from Rs0.11/cum to Rs. 0.25/cum. Hiwarsinga has the maximum value of Rs 5.52/cum.For the rest of the projects the field officers have to take efforts for revenue collection.

CADA Jalgaon: There is 32% recovery in this year (08-09) as compared to state norms.

CADA Nashik: The value is 0.02. This shows that there is only 11% recovery with compared to state target.

NIC Nanded: The average value of this indicator for minor projects under this circle has retained last years value 0.06. It is below 1/3rd ratio state target. Daryapur has the maximum value for the indicator i.e. 0.08

Normal Plan Group:

BIPC Buldhana: The ratio was 0.15 on Adol project of BIPC Buldhana.

CADA Jalgaon: The indicator value is 0.07, which is far below the state norms. This shows that very less (37%) recovery is achieved with compared to state target.

CADA Nashik: The indicator value is 0.01 which is far below the state norms.

CIPC Chandrapur: The average value of this indicator for minor projects under the circle is 0.04. But it is still below state norms and decreased in comparison with last year's performance 0.12.

NIC Nanded: The average value of this indicator for projects under this circle has reduced from 0.04 to 0.02.

PIC Pune: Average revenue per unit water supplied of two MI Projects is decrease to Rs. 0.02/cum this year it is below the state norms.

Surplus Plan Group:

CADA Nagpur: The average value of this indicator for minor projects under the circle is 0.05. But it is still below state norms and nearly same as last year's performance 0.07.

Abundant Plan Group:

CADA Pune: In Thoseghar MI Project the revenue per unit water supply increased from Rs. 0.06/cum to Rs. 0.03/cum this year. It is also below state norms.


CIPC Chandrapur: The average value of this indicator for minor projects under the circle is 0.03. But it is still below state norms and decreased in comparison with last years performance 0.04.

KIC Ratnagiri: In Shirval MI Tank revenue per unit of water supply is Rs. 0.11 /cum which increases from Rs. 0.03/cum of last year. But it is below as compared to state norms.

NKIPC Thane: Average revenue per unit water supplied of Two Minor Projects is same as Rs. 0.03/cum last year. It is also below state norms.

SIC Sangli: Revenue per unit water supply is decreased from Rs. 0.17/cum (2007-08) to 0.13 in 2008-09.

TIC Thane: Revenue per unit water supply is increased from Rs. 0.06/cum (2007-08) to Rs. 0.08/cum in 2008-09.



Plan group	Circle	FY Avg	LY 2007- 08	TY 2008- 09	Past Max	Past Min	Avg Per	State Target
Highly Deficit	CADA Beed	0.38	0.39	0.5	0.459	0		
	CADA Solapur	0.33	0.20	1.00	0.51	0.00	0.83	1.00
	PIC Pune	1.19	0.51	1.00	10.00	0.00		
Deficit	AIC Akola	0.77	0.52	0.02	0.82	0.52		
	BIPC Buldhana	0.30	0.44	0.43	0.60	0.11		
	CADA Abad	0.13	0.00	0.00	0.19	0.00		
	CADA Beed	0.05	0.77	0.83	0.77	0.01	0.9	1.0
	CADA Jalgaon	0.61	0.81	0.79	0.81	0.53		
	CADA Nashik	8.17	0.32	1.00	30.77	0.00		
	NIC Nanded	0.28	0.40	0.13	0.75	0.14		
Normal	AIC Akola	0.77	1.04	0.00	1.04	0.00		
	BIPC Buldhana	0.56	0.40	0.05	1.00	0.15		
	CADA Jalgaon	0.69	0.79	0.93	0.79	0.00		
	CADA Nagpur	0.54	0.02	0.00	0.83	0.00		
	CADA Nashik	0.84	0.97	0.77	0.97	0.60	0.6	1.0
	CIPC Chandrapur	0.26	0.58	0.41	0.67	0.21		
	NIC Nanded	0.27	0.30	0.01	0.70	0.14		
	PIC Pune	0.68	0.87	0.87	1.09	0.30		
	YIC Yavatmal	1.84	0.00	0.00	1.90	0.00		
Surplus	CADA Nagpur	0.57	0.44	0.49	0.78	0.39	0.5	1.0
Abundant	CADA Pune	0.84	1.00	0.70	1.00	0.00		
	CIPC Chandrapur	0.39	0.23	1.00	0.69	0.15		
	KIC Ratnagiri	0.14	0.12	0.55	0.30	0.04		
	NKIPC Thane	0.63	0.69	0.78	0.84	0.49	0.8	1.0
	SIC Sangli	0.95	1.00	1.00	1.00	0.00		
	TIC Thane	0.90	0.88	0.89	3.03	0.45		

Indicator XII (I): Assessment Recovery Ratio (Irrigation) Highly Deficit Plan Group:

CADA Beed: The average value of the indicator under this circle has increased from 0.39 to 0.50 Tintraj project has the lowest recovery ratio that is 0.12 & Incharna has the highest assessment recovery ratio that is 0.91.

CADA Solapur: Ratio is increased from 0.20 (2007-08) to 1.00 (2008-09).

PIC Pune: In Chichondi Patil MI Tank the assessment recovery ratio comes to 1.00.

Deficit Plan Group:

AIC Akola & BIPC Buldhana: Recovery of irrigation revenue against assessment on projects under AIC Akola was 0.02 very low to the state target and than last year revenue recovery. But it was 0.43 with projects under BIPC Buldhana.

CADA Aurangabad: The average value of the indicator under this circle has retained last years value nil recovery. Tandulwadi is the only project under this plan group & which has no recovery.

CADA Beed: The average value of the indicator under this circle has increased from 0.77 to 0.83. Hiwarsinga has the highest recovery ratio that is 2.0. Dhanori has no recovery.

CADA Jalgaon: The ratio is 0.79 which is nearer to state norms.

CADA Nashik: The ratio is 1.00 which is as per the state norms.

NIC Nanded: The average value of the indicator under this circle has decreased from 0.40 to 0.13. Kosthewadi has the maximum recovery of 1.00. Daryapur has no recovery.

Normal Plan Group:

BIPC Buldhana: Recovery of irrigation revenue against assessment on Adol project was .0.05.

CADA Jalgaon: The ratio is 0.93, which is nearer to state norms.

CADA Nashik: The ratio is lowered from 0.97(2007-08) to 0.77(2008-09).

CIPC Chandrapur: Assessment recovery ratio is 0.41 compared with last year it decreased by 17%, below the state norm value.

NIC Nanded: Ratio is reduced from 0.30 (2007-08) to 0 .01(2008-09).

PIC Pune: Average assessment recovery ratio of M.I. Projects retains last year's value (0.87).

Surplus Plan Group:

CADA Nagpur: Revenue recovery under this circle is less during this year (0.49) but more as compared to last years performance (0.44).

Abundant Plan Group:

CADA Pune: In Thoseghar MI tank ratio decreases from 1.00 of last year to 0.70 this year.

CIPC Chandrapur: Revenue recovery on projects under CIPC Chandrapur is 100%. It is as per state target, & increased marginally than the last year value.

KIC Ratnagiri: In Shirval Project the ratio increases to 0.55 this year from 0.12 of last year. But it is below the state norms.

NKIPC Thane: Average assessment recovery ratio of two MI Projects increased this year to 0.78 from 0.69 last year. But it is below state norms.

SIC Sangli: The average value of the indicator under this circle has retained last years value (1.00)

TIC Thane: The average value of the indicator under this circle has retained nearly last years value.

Chapter-V

Action Taken Report

Benchmarking process involves number of steps, right from Indicators selection to monitoring of results obtained through action taken on last years performance deficiencies. Where the Benchmarking of irrigation projects has been a routine process of performance evaluation, preparation of a comprehensive, problem specific action plan for every individual irrigation project based on the outcome of last year performance & its effective implementation plays an important role in securing the desired improvement.

Since last seven years, Water Resources Department is using Benchmarking as an effective tool to evaluate the performances of irrigation projects. Project wise, Indicator wise results along with probable causes for low performances compared to past achievement as well as state targets were made available to field officers with the intention and directives to prepare and implement a project wise consolidated complete action plan. Field officers were stressed to submit the out come of such action plans with its details. Project authorities are no doubt taking the cognizance of the low performances and are taking suitable actions to seek the desired improvement in Irrigation Management. But the information gathered so far indicates that instead of preparing a detail, integrated action plan, actions are taken in the form of a single activity.

Not a single action plan is received from Project authorities for the year 2008-09; hence it is not incorporated in this report.

Chapter VI Benchmarking of Water Users Association's - A Case Study

Till the end of June 2008, a potential to the tune of 4.486Mha has been created in the state. At present, the Irrigation Management of created irrigation potential is managed at Water Resources Department level with 0.403 Mha managed by the794 Water Users Associations working on Major / Medium and 306 on Minor projects. These WUA's are registered under co-operative act.

Water Resources Department, GOM has categorically taken the decision of handing over the total potential created on all projects to the Water Users Associations. Accordingly, an act namely MMISF Act 2005 has been passed in the State Assembly.

At present, Maharashtra Water sector Improvement Programme (MWSIP) is under implementation through which a potential to the tune of 0.67 Mha on 286 projects shall be handed over to1539 WUAs in the stipulated period. The MMISF act 2005 is made applicable to the projects under MWSIP. The cost of the project is Rupees 1700 crores and it is aided by the World Bank. Above mentioned act is made applicable to all projects under MWSIP.

For evaluating the irrigation performance of irrigation projects and bringing about necessary improvement in Irrigation Water Management, the state is using Benchmarking as an effective management tool for last five years.

Considering huge public capital investment in construction of number of projects along with large amount of funds investment involved in rehabilitation of irrigation system before its handing over to WUAS, evaluation of the performance of each individual WUA each year by Benchmarking was felt necessary and was under consideration for last two years. Benchmarking of WUAs will help to determine and bring necessary improvement in the over all functioning of each WUA. Also it will help the WR Department to ascertain whether the objectives of handing over the Irrigation Management to WUAs are attained or not.

6.1 Objectives of Benchmarking of WUAs

- 1. To determine the participation of beneficiaries in working of WUA'S.
- 2. To ascertain whether the WUA is getting the water as per sanctioned water quota and management funds/share of revenue collected as per the agreement and guidelines or not.
- 3 To check the increase in area irrigated and Out Put after the irrigation management is handed over to WUA
- 4 To determine per ha water use (excluding well/ river lift) in the jurisdiction of WUA
- 5 To check the conjunctive use of wells in the command of WUA.
- 6 To determine the financial status / self-sustainability of WUA.
- 7 To check whether water is judiciously/ equitably supplied to beneficiaries at Head, Middle and Tail reaches of the canal system under the jurisdiction of WUA
- 8 To fix the area of problems so as to take suitable action to bring necessary changes in the working of WUA and improve the performance of a distribution system, ultimately of the project.
- 9 To create a sense of responsibility /accountability among the office bearers of WUA and discipline among members of the association.

6.2 **Proforma for data submission for Benchmarking of WUA:**

For calling the data/information for benchmarking of WUA, Proforma 1 and 3 are designed in regional language (Marathi). These Proforma in English are shown on subsequent pages of this report.

For accurate evaluation of performance of WUA, 9 indicators are designed and shown in Proforma 2 in subsequent pages of this report.

6.3 Selection of WUA for benchmarking study:

Looking to the large number of WUA's formed so far, to initialize the process as a case study, it was decided to call the data of two WUAs established on major project from each revenue division. Secondly, preference was given to WUAs which are in working for a longer range of period.

Accordingly, data for 12 WUAs on 7 Major projects from 5 Irrigation circles has been analyzed broadly in this typical study.

Plan group wise classification of these WUAs shows that, 1, 4, 6 and 1 WUA in number, belongs to Highly Deficit, Deficit, Normal and Abundant plan group respectively.

Out of 12 WUAs only two WUAs on Mula project are functioning under MMISF Act 2005. Rest of 10 WUAs are functioning under co-operative Act.

6.4 Methodology adopted for Benchmarking:

Considering the WUA selected are in limited numbers, Benchmarking is proposed to carry out by -

I) comparing the performances of individual WUA with state target

ii) Comparing the performances of two WUA's on the same project,

iii) Comparing the performances of two WUA's from two different projects but from same plan group and

iv) Incase of some indicators, Benchmarking is carried out by comparing the performances of WUA's from two different Plan groups also.

At present, the performance of individual WUA is compared with the state target only.

6.5 Targets:

Targets for indicator 1 to 3, 6, 7 & 9 are shown in Proforma 2 and are self explanatory.

Target for indicator IV (Annual water use per unit area irrigated) is decided by reducing the target for BM of irrigation projects (7692 cum/ha) by 30% for transit losses in canal as the water supplied to WUA'S is measured at off taking of the concerned Distributory /Minor. Thus target becomes 5384 cum/ha.

Target for indicator V (Annual expenditure per ha for irrigation management) for a WUA is evaluated as follows:

Total command area of a WUA: 200 ha (Presumption) Salary of Staff and other mandatory expenditure for IWM per annum

S.N.	Item	Amount
1	Salary of One Canal inspector	Rs 36000
2	Salary of One Labour	Rs 18000
3	Office Building Rent	Rs 6000
4	Maintenance of distribution system	Rs 4000
5	Telephone/ electricity bill	Rs 12000
6	Report publication etc	Rs 3000
7	Stationary	Rs 1000
	Total	Rs 80000

Annual expenditure per unit area irrigated = 80000

200

= Rs 400 / ha

6.6 Indicator wise analysis

As mentioned here before, data of 2008-09 year for Benchmarking of WUA was received from some selected WUA'S in prescribed Proforma and indicator values were obtained as shown in table 1.

Indicator wise, WUA wise findings along with charts are given in Chart I to IX Indicator I: Percentage of WUA'S member to total beneficiaries in command

of WUA

All the WUA,s except Datta & Yogeshwar (CADA Nashik -100%) have membership ranging between 52 to 85 %. It is opined that, to increase farmers participation in irrigation water management & to increase the efficiency of WUA'S, 100% membership should be developed on each WUA.

Indicator II: Percentage of Water supplied to the sanctioned Water quota

In Pandurang (CADA Solapur), Bhagawati (CADA Beed), Datta (CADA Nashik) & Nanaksingh (SIC Sangli) WUAs, water is supplied as per standard water quota. However in rest of the WUAs, the percentage of water supplied ranges from 13 to 86%.

Indicator III: Ratio of potential utilization to Maximum utilization prior to formation of WUA.

In all the WUAs expect Krishna (NIC Nanded) the ratio is more than 1.

Indicator IV: Annual Irrigation water use per unit area Irrigated (Cum/ha)

1. In Shukleshwar (CADA Beed), Datta (CADA Nashik) & Godavari (NIC Nanded), water use per unit irrigated area is nearer to the state norm.

Indicator V: Annual expenditure per Ha by WUA for irrigation management (Rs /ha)

Annual expenditure per Ha for irrigation management in Bhagwati (CADA Beed), Krishna (NIC Nanded), &Jai Ambica (CADA Nashik) WUA's exceeds state norms. These WUA's should take proper measures to maintain the economic sustainability. In case of Krishna WUA, as per field authorities, the excess expenditure is due to additional new activities like awards etc.

Indicator VI: Cost recovery ratio.

All WUAs expect St. Muktabai & Jai Ambaica (CADA Nashik) have achieved the state target.

Indicator VII: Ratio of Water revenue remitted to Govt. to Actual water revenue recovered

No WUA except Shukleshwar (CADA Beed) & Yogeshwar (CADA Nashik) had paid the recovered water charges to the Govt. The remittance of revenue in rest of the WUAs ranges from 13% to 89%.

Indicator VIII: Annual Output per ha of area irrigated (Rs/ha)

1. Out put per ha on all WUA's except Godavari (NIC Nanded) WUA on Purna project appears to be satisfactory as compared to the fixed norm.

2. In general, out put per ha observed on WUA's in normal plan group was more than that observed on WUA's in deficit plan group.

Indicator IX: Equity performance

From the available data it reveals that, there is no equitable distribution amongst the beneficiaries in the command by respective WUA's except Krishna & Godawari on Purna project and Saptashrangi on Ozerkhed project.

6.7 Action Ahead

- 1. At present looking to large numbers of WUAs, Benchmarking of selected WUAs on Major project is possible at State level. After handing over of total irrigation management of projects to WUA, Benchmarking of apex (Canal, Dystributory) WUAs would be feasible at State level.
- 2. In case of Medium and Minor projects which are totally handed over to WUAs for irrigation management, Benchmarking of WUAs on Medium and Minor projects could be entrusted to concerned Sub divisions and Divisions respectively. In case of Major projects, Benchmarking of WUAs on Canal can be carried out at circle level.
- 3. To bring about necessary improvement in functioning of WUAs, monitoring of Benchmarking of Major, Medium and Minor project's WUAs at concerned Division, Circle and Chief Engineer level will be desirable.

enchmarking of Water User Association (Proforma 1)	
Prescribed format for Information to be submitted for Benchma	Irrigation Year :

VUA		Total		14						
ceived to V M)	(M)	Hot Total	weather	13	VUA	r actual	Iring the		Tail	27
quota rec	TCM) (TCM) Kharif Rabbi Hot weathe 11 12 13 Number of WUA members as per actual area irrigated during the		members as per actual area irrigated during the year		Middle	26				
Actual		Kharif		11	nΝ	meml	member area irrig		Head	25
s per		Total		10	UA	otal	nel		Tail	24
f WUA a	agreement (1 UM)	Hot	weather	9 10	Number of WUA	members in total	length of channel		Middle	23
Quota o	eement	Rabbi		8	Nun	men	leng		Head	22
Sanction (agr	Kharif Rabbi Hot Total Kharif Rabbi		7	Annual	income	during	irrigation	irrigation year (Rs.) Head Middle Tail Head Middle year (Rs.)	21
Number of	w UA members			9	Water cess	paid to	Govt.	during	irrigation year (Rs.)	20
Number of	beneficiaries in w UA command of members WUA			5	Water cess	recovery	during	irrigation year	(Rs)	19
Name of Water	User Association			4	Crop area Total area Expenditure on	irrigation	management	during	irrigation year (Rs)	18
Basin No.				3	Total area	irrigated in	irrigation	year (ha)		17
Name of	CITCLE			2	Crop area	measured	during	irrigation year (ha)	year (ha)	16
Name of Project Name of Basin No. Name of Water Number of Number of Sanction Quota of WUA as per Actual quota received to WUA				1	Annual crop	area measured measured irrigated in irrigation	in command of during irrigation	WUA before	establishment year (ha) (ha)	15

Indicator No.	Indicator	Target / Achievement	Purpose of Indicator
Indicator No. I	Percentage of WUA members to total beneficiaries in Command of WUA (Column 6 /Column 5)* 100	100%	To check the participation of beneficiaries in the Irrigation Management of WUA
Indicator No. II	Percentage of water supplied to sanction quota (Column 14 /Column 10)* 100	100%	To check the actual water quota received as compared to the sanction water quota during the irrigation year.
Indicator No. III	Ratio of actual area irrigated to the area irrigated before functioning of the WUA (Column 16 /Column 15)	More than 1	To check whether area irrigated is increased or decreased after the formation of WUA.
Indicator No. IV	Annual irrigation water use per unit area irrigated (Cum/ha) (Column 14 x 1000/Column 17)	Less than 5382 Cum	To check the economic, efficient use of water in irrigation management.
Indicator No. V	Annual expenditure per ha for irrigation management (Rs/ha) (Column 18 /Column 16)	Rs. 400/ha	To check whether the expenditure for irrigation management is economical or not.
Indicator No. VI	Ratio of annual expenditure to recovered water charges (Column 19 /Column 18)	More than 1	To check and decide the self sustainability of WUA.
Indicator No. VII	Ratio of water revenue remitted to Govt. to actual water revenue recovered (Column 20 /Column 19)	More than 1	To check the actual remittance of water revenue to Govt. from the collected water charges.
Indicator No. VIII	Annual Output per ha of area irrigated (Rs/ha) (Column 21 /Column 16)	As per State target for project BM	To check actual increase in income of beneficiaries due to freedom of crops and participation of farmers in
Indicator	Equity Performance		irrigation management. To check equitable
No. IX	Head (Column 25 /Column 22)	One	distribution of water in head, middle & tail reaches of WUA. Reaches are
	Middle	One	defined by equally dividing the total beneficiaries in
	(Column 26 /Column 23) Tail	One	three reaches namely head, middle and tail.
	(Column 27 /Column 24)		

	Circle wise Ancillary information of WUA in Highly Deficit & Abundant Plan group (Proforma 3)				
Sr. No.	Item /Circle	CADA Solapur	SIC Sangli		
	Project	Bhima (Ujani)	Warna		
	Name of WUA	Pandurang	Nanaksingh		
1	Jurisdiction of WUA	Dy No.35 On Ujani LBC	Dy No.1,2,3		
2	ICA of WUA	117 ha	111 ha		
3	Is WUA included in MWSIP?	No	No		
4	Date of handing over of IWM (command area) to the WUA	12-12-1994	6-8-2004		
5	No of wells in command area of WUA				
	a) Before handing over	50	0		
	b) Total as on today	60	0		
6	Subsidy received during the irrigation year	Rs60232/-	0		
7	Year for which subsidy is not received	2004-05 to 2007-08	2004-05, 2005- 06, 2006-07		
8	Dose the well water was used as an additional source for irrigation during the irrigation year	Yes	No		
9	Area under perennial crops during the irrigation year	150 ha	26.60 ha		
10	No. of staff employed for irrigation management by WUA	2	3		
11	Does water supply was on volumetric basis or not	Volumetric basis	Volumetric basis		
12	Assessment of water charges were on volumetric basis or as per crop area measurement	On volumetric basis	On volumetric basis		
13	Percentage of actual live storage to the design storage in the reservoir during the irrigation year	100%	100%		
14	Reasons for less achievements compared to the set target during the irrigation year	 The people getting benefit of irrigation from river are not becoming the members of WUAs. There is conjunctive use of wells & canal. 	 Deterioted disnet system. Fill Irrigation potential is not created. Association is in preliminary stage 		

Sr. No.	Item /Circle	CADA I	Beed	
	Project	Majalg	aon	
	Name of WUA	Bhagwati	Shukleshwar	
1	Jurisdiction of WUA	Minor No.1 to 7/ Tilsmukh branch/ MRBC	Minor No.8/ GM Branch Canal / MRBC	
2	ICA of WUA	555 ha	725 ha	
3	Is WUA included in MWSIP?	No	No	
4	Date of handing over of IWM (command area) to the WUA	25-03-1998	9-10-1998	
5	No of wells in command area of WUA			
	a) Before handing over	2	68	
	b) Total as on today	61 (33 wells, 28 Bore wells)	93	
6	Subsidy received during the irrigation year	0	0	
7	Year for which subsidy is not received	2008-09	2007-08 & 2008-09	
8	Dose the well water was used as an additional source for irrigation during the irrigation year	Yes	Yes	
9	Area under perennial crops during the irrigation year	298 ha	134 ha	
10	No. of staff employed for irrigation management by WUA	2	2	
11	Does water supply was on volumetric basis or not	Volumetric basis	Volumetric basis	
12	Assessment of water charges were on volumetric basis or as per crop area measurement	On volumetric basis	On volumetric basis	
13	Percentage of actual live storage to the design storage in the reservoir during the irrigation year	100%	84%	
14	Reasons for less achievements compared to the set target during the irrigation year	 s 1) Less response from WUA members 2) Due to more number of wells in command ,there was low response to canal irrigation 3) Trend of cultivators towards cash crops 		

Circle wise Ancillary information of WUA in Deficit Plan group (Proforma 3)

Sr. No.	Item /Circle	NIC Nanded			
	Project	Purn	a		
	Name of WUA	Krishna	Godawari		
1	Jurisdiction of WUA	Malegaon Minor /Dour Minor / camp colony DO No.5 to 9	Kamtha Minor 1,2,3/ Do No.10 to 15		
2	ICA of WUA	1036 ha	619 ha		
3	Is WUA included in MWSIP?	No	No		
4	Date of handing over of IWM (command area) to the WUA	3.7.1991	3.7.1991		
5	No of wells in command area of WUA				
	a) Before handing over	92	78		
	b) Total as on today	141	102		
6	Subsidy received during the irrigation year	Rs 235778/-	Rs 31548/-		
7	Year for which subsidy is not received	Nil	Nil		
8	Dose the well water was used as an additional source for irrigation during the irrigation year	Yes	Yes		
9	Area under perennial crops during the irrigation year	65.5 ha	41 ha		
10	No. of staff employed for irrigation management by WUA	8	6		
11	Does water supply was on volumetric basis or not	Volumetric basis	Volumetric basis		
12	Assessment of water charges were on volumetric basis or as per crop area measurement	On volumetric basis	On volumetric basis		
13	Percentage of actual live storage to the design storage in the reservoir during the irrigation year	100%	100%		
14	Reasons for less achievements compared to the set target during the irrigation year	Information not available			

Sr. No.	Item /Circle		CADA Nashik				
	Project	Ozerkhed	Ozerkhed	Pa	lkhed		
	Name of WUA	Parashari	Saptashrangi	Sant Muktabai	Jai Ambika		
1	Jurisdiction of WUA	Godagaon Dy on Ozerkhed canal	Ambepimpalgaon Dy on Ozerkhed canal	Dy.14 Palkhed Left Bank Canal	Dy.10 & 11 Palkhed Left Bank Canal		
2	ICA of WUA	520 ha	583 ha	462 ha	534 ha		
3	Is WUA included in MWSIP?	No	No	No	No		
4	Date of handing over of IWM (command area) to the WUA	01/01/1993	29/07/1995	10/2006	01/ 11/2002		
5	No of wells in command area of WUA						
	a) Before handing over	98	107	379	390		
	b) Total as on today	125	192	391	415		
6	Subsidy received during the irrigation year	Rs. 27744/-	Rs56000/-	Yes Rs. 5140/-	Yes Rs 7306/-		
7	Year for which subsidy is not received	2004 -05	2004-05	2008-09	2008-09		
8	Dose the well water was used as an additional source for irrigation during the irrigation year	Yes	Yes	Yes	Yes		
9	Area under perennial crops during the irrigation year	115 Ha.	112ha	350 ha	111 ha		
10	No. of staff employed for irrigation management by WUA	2	1	1	1		
11	Does water supply was on volumetric basis or not	Volumetric basis	Volumetric basis	Volumetric basis	Volumetric basis		
12	Assessment of water charges were on volumetric basis or as per crop area measurement	On volumetric basis	On volumetric basis	On volumetric basis	On volumetric basis		
13	Percentage of actual live storage to the design storage in the reservoir during the irrigation year	100%	100%	100%	100%		
14	Reasons for less achievements compared to the set target during the irrigation year	More rain fall in command area resulting increase in irrigation on wells	More rain fall in command area resulting increase in irrigation on wells	More rain fall in command area in Rabbi season	More rain fall in command area in Rabbi season		

Circle wise Ancillary information of WUA in normal plan group (Proforma 3)

Sr. No.	Item /Circle	CADA Nashik			
	Project	Mu	la		
	Name of WUA	Datta	Yogeshwar		
1	Jurisdiction of WUA	Dy No 7 of Mula Right Bank Canal.	Dy No 3, Minor No 2 of Mula Right Bank Canal.		
2	ICA of WUA	361 Ha	200.70 Ha		
3	Is WUA included in MWSIP?	Yes	Yes		
4	Date of handing over of IWM (command area) to the WUA	30-06-1989	24-10-1997		
5	No of wells in command area of WUA				
	a) Before handing over	162	88		
	b) Total as on today	109	109		
6	Subsidy received during the irrigation year	Rs78900/-	Rs13400/-		
7	Year for which subsidy is not received	2001-02to2007-08	2006-07&2007-08		
8	Dose the well water was used as an additional source for irrigation during the irrigation year	Yes	Yes		
9	Area under perennial crops during the irrigation year	155Ha	40 Ha		
10	No. of staff employed for irrigation management by WUA	3	2		
11	Does water supply was on volumetric basis or not	Volumetric basis	Volumetric basis		
12	Assessment of water charges were on volumetric basis or as per crop area measurement	Volumetric basis	Volumetric basis		
13	Percentage of actual live storage to the design storage in the reservoir during the irrigation year	100%	100%		
14	Reasons for less achievements compared to the set target during the irrigation year	-	1		

	IND I- Percentage of WOA members to total beneficiaries					
Highly Deficit	CADA Solapur	Bhima	Pandurang	61		
	CADA Beed	Majalgaon	Shukleshwar	59		
Deficit	CADA Deeu	Majaiyaon	Bhagwati	70		
Dencit	NIC Nanded	Purna	Krishna	77		
	INIC Nanded	Fuma	Godavari	65		
	CADA Nashik	Ozerkhed	Parashari	64		
		Ozerkneu	Saptashrangi	53		
		Palkhed	St.Muktabai	54		
Normal			Jai Ambika	85		
			Datta	100		
		Mula	Yogeshwar			
				100		
Abundant	SIC Sangli	Warna	Nanaksingh	53		

IND I- Percentage of WUA members to total beneficiaries

IND II- Percentage of Water supplied to sanctioned water quota

	V 11	T		
Highly Deficit	CADA Solapur	Bhima	Pandurang	100
	CADA Beed	Majalgaon	Shukleshwar	53
Deficit		Iviajalyauti	Bhagwati	100
	NIC Nanded	Purna	Krishna	17
		Pulla	Godavari	61
	CADA Nashik	Ozerkhed	Parashari	22
		Ozerkneu	Saptashrangi	59
Normal		Palkhed	St.Muktabai	53
Inormai		Faikileu	Jai Ambika	13
		Mula	Datta	158
		iviula	Yogeshwa	86
Abundant	SIC Sangli	Warna	Nanaksingh	100

Indicator III: Ratio of Potential Utilisation to maximum Utilisation prior to formation of WUA

Plan group	Circle	Project	W U A	Value
Highly Deficit	CADA Solapur	Bhima	Pandurang	2.56
	CADA Beed	Majalgaon	Shukleshwar	1.22
Deficit		Majaigaon	Bhagwati	2.37
Dencit	NIC Nanded	Purna	Krishna	0.63
	NIC Nallueu	i una	Godavari	1.12
		Ozerkhed	Parashari	2.20
		Ozerkiled	Saptashrangi	4.60
Normal	CADA Nashik	Palkhed	St.Muktabai	2.32
Normai		T aikited	Jai Ambika	1.95
		Mula	Datta	1.20
		ividia	Yogeshwa	1.43
Abundant	SIC Sangli	Warna	Nanaksingh	1.81


Indicator IV: And	nual Irrigation wat	er use per unit a	rea Irrigated (Cu	m/ha)
Plan group	Circle	Project	W U A	Value
Highly Deficit	CADA Solapur	Bhima	Pandurang	3012
	CADA Beed	Majalgaan	Shukleshwar	7254
Deficit	CADA Deeu	Majalgaon	Bhagwati	10911
Dencit	NIC Nanded	Purna	Krishna	2888
	INIC Manueu	Fullia	Godavari	5396
		Ozerkhed	Parashari	1176
		Ozerkneu	Saptashrangi	1951
Normal	CADA Nashik	Palkhed	St.Muktabai	3750
normai	CADA Nashik	Paikned	Jai Ambika	3452
		Mula	Datta	5366
		Mula	Yogeshwa	3282
Abundant	SIC Sangli	Warna	Nanaksingh	11000
	-			
Indicator V: Ann	nual expenditure for	or IWM per unit a	rea irrigated (Rs	/ha)
Plan group	Circle	Project	W U A	Value
Highly Deficit	CADA Solapur	Bhima	Pandurang	157
	CADA Beed	Majalaaan	Shukleshwar	160
Deficit	CADA Deeu	Majalgaon	Bhagwati	1190
	NIC Needed	Durran	Krishna	1528
	NIC Nanded	Purna	Godavari	477
			Parashari	28
		Ozerkhed	Saptashrangi	180
Normal		Delliked	St.Muktabai	174
Normal	CADA Nashik	Palkhed	Jai Ambika	959
		N4 1-	Datta	303
		Mula	Yogeshwa	351
Abundant	SIC Sangli	Warna	Nanaksingh	388
Indicator VI: Co	st recovery Ratio		U	1
Plan group	Circle	Project	WUA	Value
Highly Deficit	CADA Solapur	Bhima	Pandurang	2.64
			Shukleshwar	2.94
	CADA Beed	Majalgaon	Bhagwati	2.37
Deficit		_	Krishna	1.49
	NIC Nanded	Purna	Godavari	1.81
			Parashari	10.13
		Ozerkhed	Saptashrangi	2.1
	0.00.00	D II · · ·	St.Muktabai	0.17
Normal	CADA Nashik	Palkhed	Jai Ambika	0.14
			Datta	2.66
		Mula	Yogeshwa	1.89
Abundant	SIC Sangli	Warna	Nanaksingh	2.15


-


Indicator VII: Ra	atio of Recovery re	emittance to To	otal recovery	
Plan group	Circle	Project	WUA	Value
Highly Deficit	CADA Solapur	Bhima	Pandurang	0.49
	CADA Beed	Majalgaon	Shukleshwar	1.00
Deficit	CADA Deeu	Majaiyaon	Bhagwati	0.85
Dencit	NIC Nanded	Purna	Krishna	0.85
	NIC Nanueu	Funa	Godavari	0.62
		Ozerkhed	Parashari	0.46
		Ozerkileu	Saptashrangi	0.70
Normal	CADA Nashik	Palkhed	St.Muktabai	0.78
Normai	CADA Nashik		Jai Ambika	0.80
		Mula	Datta	0 .89
		India	Yogeshwa	0.95
Abundant	SIC Sangli	Warna	Nanaksingh	0.13
Indicator VIII: A	nnual Out put per	unit area irriga		
Plan group	Circle	Project	W U A	Value
Highly Deficit	CADA Solapur	Bhima	Pandurang	95001
	CADA Beed	Majalgaon	Shukleshwar	28845
Deficit		Majaigaon	Bhagwati	90699
Denen	NIC Nanded	Purna	Krishna	21990
		i unia	Godavari	12358
		Ozerkhed	Parashari	480000
		Ozerkiled	Saptashrangi	383965
Normal	CADA Nashik	Palkhed	St.Muktabai	385000
Norman			Jai Ambika	395
		Mula	Datta	56230
		India	Yogeshwa	40839
Abundant	SIC Sangli	Warna	Nanaksingh	40854

Plan Group	Circle	Project	WUA	Reach	Value
				н	0.58
Highly Deficit	CADA Solapur	Bhima	Pandurang	М	0.74
				Т	0.44
				Н	0.76
			Shukleshwar	М	0.62
	CADA Beed	Majalgaon		Т	0.22
				Н	0.63
			Bhagawati	М	0.70
Deficit				Т	0.83
2 011011				Н	1.00
			Krishna	М	1.00
	NIC Nanded	Purna		Т	1.00
				Н	1.00
			Godavari	М	1.00
				Т	1.00
				Н	0.75
			Parashari	М	0.42
		Ozerkhed		Т	0.92
				Н	0.96
			Saptashrangi	М	0.95
				Т	0.97
				Н	0.21
			St. Muktabai	М	0.30
Normal	CADA Nashik	Palkhed		Т	0.56
				Н	0.49
			Jai Ambika	М	0.19
				Т	0.21
				н	0.19
			_	М	0.23
		Mula	Datta	Т	0.19
				Н	0.35
				М	0.48
			Yogeshwa	Т	0.33
				н	0.80
Abundant	SIC Sangli	Warna	Nanaksingh	М	0.44
				Т	0.14


Indicator IX: Equity performance











Indicator III: Ratio of Potential Utilisation to maximum Utilisation prior to formation of WUA Value














Chapter - 7

Project wise Review of Major and Medium Projects

The Benchmarking Reports published for year 2003-04 to 2007-08 consist of the graphical representation of each indicator with circle as a unit. Project wise data for each indicator was not appearing any where in the said reports.

As per directives of Secretary (CAD) it is decided to incorporate project wise data for last 5 years for all the Major and Medium projects in the Benchmarking report of year 2008-09.

The project wise data incorporated is as below

- I) Name of project.
- II) Designed live storage in Mm³
- III) Irrigable Command Area in Ha.
- IV) Irrigation year
- V) Year status
- VI) Live storage available as on 15th October
- VII) Water used for irrigation in Mm³
- VIII) Irrigated Area in Ha.
- IX) Recovery for irrigation in Rs Lakh
- X) Recovery for Non irrigation in Rs lakh
- XI) Total Recovery for Irrigation & Non irrigation in Rs lakh
- XII) Annual Water Supply for irrigation in ha/Mm³

Data for last five years of the above parameters for all Major and Medium projects of is tabulated here to have a project wise performance at a glance.

	Annual Water supply	ha/Mm ³ .	13*	0	0	112	166	174	0	133	104	277	152	159	144	106	0	47	101	126	70	50	58	50	48	56	98
	Total recovery Irrication +	Irrigation in Lakhs	12	159.84	25.62	39.65	134.76	139.65	92.74	29.86	10.75	6.11	1.83	4.47	4.29	86.83	13.31	1.05	10.95	10.33	20.57	77.81	78.59	88.59	95.07	129.66	140.81
	Recovery Non Irrination	Rs. In lakhs	11	132.74	25.62	39.65	131.66	136.16	92.29	15.60	5.10	2.50	0.28	1.49	3.42	53.70	12.16	0.95	9.94	8.60	14.57	54.40	59.04	66.44	59.50	80.44	101.24
(60-800	Recovery Irrigation Re In	lakhs	10	27.10	0.00	0.00	3.10	3.49	0.45	14.26	5.65	3.61	1.55	2.98	0.87	33.13	1.15	0.10	1.01	1.73	6.00	23.41	19.55	22.15	35.57	49.23	39.57
003-04 to 20	Irrigated area in ha		6	0	0	2627	4740	5985	0	3338	1324	688	5357	3946	1513	5621	0	2958	7021	7544	3917	13233	16890	12067	13631	18342	7118
ysis of Major projects in Maharashtra State (2003-04 to 2008-09)	Water used for irrigation		8	0.00	0.00	23.43	28.64	34.42	0.00	25.13	12.74	2.48	35.21	24.89	10.51	52.85	0.00	62.44	69.46	59.98	56.32	262.65	291.65	241.88	281.68	327.04	72.44
n Maharas	Live Storage	15th oct	7	23.48	2.34	56.74	86.35	80.50	15.40	60.38	24.86	5.63	69.32	32.59	19.11	76.99	7.14	91.26	91.26	91.26	75.25	614.80	514.21	582.86	548.14	548.14	288.39
projects i	Year status		9	I st	Ii nd	III rd	I_{V}^{th}	V^{th}	Current	I st	Ii nd	III rd	Iv^{th}	V^{th}	Current	I st	Ii nd	III rd	Iv^{th}	V^{th}	Current	I st	Ii nd	III rd	I_{V}^{th}	V^{th}	Current
is of Major	Irrigation Year		5	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09
Analys	ICA in ha		4	8325						8604						8215						75000					
	Designed live storage نی کیس ³		3	86.35						69.32						91.26						614.80			548.14		
	Project		2	Katepurna						Nalganga						Pus						Upper Wardha					
	Sr. No.		-	~						2						ю						4					

~

Annual Water supply ha/Mm ³ .	13*	142	266	109	110	122	73	155	0	41	85	84	103	108	96	103	78	76	96	205	204	156	140	124	155
Total recovery Irrigation + Non Irrigation in Lakhs	12	13.04	9.71	13.77	34.44	26.69	82.62	4.86	0.71	1.00	5.23	1.48	0.00	1776.65	2119.61	2196.28	2351.96	2442.15	1555.74	28.90	11.71	12.69	13.06	30.98	4.33
Recovery Non Irrigation Rs. In Iakhs	11	0.65	8.09	6.00	34.44	24.07	73.95	1.08	0.71	1.00	2.10	0.00	0.00	1642.15	2010.87	2056.76	2113.05	2216.21	1491.29	10.08	0.00	0.14	0.47	12.21	2.50
Recovery Irrigation Rs. In Iakhs	10	12.39	1.62	7.77	0.00	2.62	8.67	3.78	0.00	0.00	3.13	1.48	0.00	134.50	108.74	139.52	238.91	225.94	64.45	18.82	11.71	12.55	12.59	18.77	1.83
Irrigated area in ha	0	9481	3003	6963	7460	8230	4263	2347	0	2689	6061	5570	279	85134	51243	79049	80097	80344	52566	30738	21980	30691	25966	30037	23460
Water used for irrigation in Mm ³	8	66.97	11.29	64.05	67.87	67.57	58.57	15.11	0.00	66.15	70.91	66.27	2.72	791.00	534.38	765.67	1028.00	1062.03	544.78	150.04	107.75	196.99	186.00	241.62	151.18
Live Storage as on 15th oct	7	NA	30.76	81.96	81.96	81.96	72.30	37.92	7.07	129.69	168.10	108.68	23.87	1303.00	432.22	1249.73	1156.94	1069.31	658.17	269.00	113.85	207.78	186.74	221.53	76.06
Year status	9	I st	Ii nd	III rd	Iv^{th}	V^{th}	Current	I st	Ii nd	III rd	Iv^{th}	V^{th}	Current	I st	Ii nd	III rd	Iv^{th}	v^{th}	Current	I st	Ii nd	III rd	Iv^{th}	v^{th}	Current
Irrigation Year	5	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09
ICA in ha	4	15100						20515						101200						23740					
Designed live storage in Mm ³	3	81.96						169.92						1374						268					
Project	2	Wan (Buldhana)						Arunavati						Pench						Bagh					
No. No.	-	5						9						7						8					

Annual Water supply ha/Mm ³ .	13*	114	110	97	75	97	98	202	309	188	138	154	139	217	219	204	168	224	188	91	135	61	54	55	56
Total recovery Irrigation + Non Irrigation in Lakhs	12	28.99	16.56	49.83	39.66	47.73	5.32	8.67	6.70	10.24	8.20	6.15	17.36	14.66	15.62	13.64	24.08	7.45	14.75	12.68	7.22	8.04	9.57	10.58	5.86
Recovery Non Irrigation Rs. In Iakhs	11	5.36	0.00	21.60	1.63	2.43	0.00	0.00	2.10	2.17	2.61	3.10	2.38	0.00	0.00	1.28	0.00	1.63	0.21	0.00	0.00	5.15	2.91	0.29	0.21
Recovery Irrigation Rs. In Iakhs	10	23.63	16.56	28.23	38.03	45.30	5.32	8.67	4.60	8.07	5.59	3.05	14.98	14.66	15.62	12.36	24.08	5.82	14.54	12.68	7.22	2.89	6.66	10.29	5.65
Irrigated area in ha	6	25240	17823	28488	26325	28249	17530	9919	11745	11967	10702	10684	9198	11356	10736	11060	11392	10794	10913	6108	2339	4424	4331	4716	2256
Water used for irrigation in Mm ³	8	220.60	162.12	294.75	348.91	292.56	178.73	49.12	38.00	63.70	77.63	69.28	65.96	52.35	49.00	54.15	67.70	48.29	58.06	67.06	17.36	72.58	79.88	85.27	40.21
Live Storage as on 15th oct	7	234.00	121.79	287.80	271.96	302.98	51.75	46.37	33.61	42.63	36.70	56.38	12.66	55.94	55.94	34.32	52.66	46.10	3.04	81.84	41.42	98.90	88.45	127.35	57.44
Year status	9	I st	Ii nd	III rd	Iv^{th}	V^{th}	Current	I st	Ii nd	III rd	Iv^{th}	V^{th}	Current	I st	Ii nd	III rd	Iv^{th}	v^{th}	Current	I st	Ii nd	III rd	Iv^{th}	v^{th}	Current
Irrigation Year	5	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09
ICA in ha	4	17500						9919						7826						13360					
Designed live storage in Mm ³	З	318.86						56.38						55.94			68.3			127.42					
Project	2	ltiahdoh						Asola Mendha						Dina						Bor					
No. No.	٢	6						10						11						12					

Sr.	Project	Designed ICA in h	ICA in ha	Irrigation Year	Year	Live	Live Water used Irrigated Recovery Recovery	Irrigated	Recovery	Recovery	Total	Annual
No.		live storage		Year	status	Storage	Storage for irrigation area in ha Irrigation	area in ha	Irrigation	Non	recovery	Water
		in Mm ³				as on	in Mm ³		Rs. In	Irrigation Irr	Irrigation +	supply
						15th oct			lakhs	Rs. In	Non	ha/Mm ³ .
										lakhs	Irrigation in	
											Lakhs	
-	2	3	4	5	9	7	8	6	10	11	12	13*

Annual Water supply ha/Mm ³ .	13*	75	80	111	59	59	104	0	76	70	70	68	72	69	139	120	86	69	82	118	119	253	231	167	163	172	
Total recovery Irrigation + Non Irrigation in Lakhs	12	0.00	177.66	193.73	232.45	123.83	75.63		158.55	204.15	222.63	252.03	309.51	302.90	1268.70	1426.74	1889.99	1654.07	1943.58	2278.33	90.84	130.03	177.66	140.02	181.01	193.49	
Recovery Non Irrigation Rs. In Iakhs	11	0.00	166.85	186.23	222.08	120.25	71.78		145.27	169.22	173.97	213.48	255.68	258.34	1253.37	1414.25	1875.83	1646.78	1934.47	2270.47	81.17	124.94	171.68	133.24	173.19	189.68	
Recovery Irrigation Rs. In Iakhs	10	0.00	10.81	7.50	10.37	3.58	3.85		13.28	34.93	48.66	38.55	53.83	44.56	15.33	12.49	14.16	7.29	9.11	7.86	9.67	5.09	5.98	6.78	7.82	3.81	
Irrigated area in ha	6	5927	6934	7829	6855	6000	7185		4434	20016	19892	21766	27306	23063	9017	8861	6126	6874	6950	6668	3289	2851	4285	3065	2788	2452	
Water used for irrigation in Mm ³	8	78.84	87.09	70.43	115.44	101.02	69.42		58.25	284.81	285.17	321.02	378.07	335.64	64.93	73.68	71.15	99.21	84.75	56.67	27.67	11.29	18.59	18.36	17.06	14.22	
Live Storage as on 15th oct	7	189.18	159.77	187.87	189.18	187.82	126.84		217.53	523.55	523.55	523.55	519.65	484.58	255.00	255.00	255.00	255.00	255.00	255.00	76.85	76.85	76.85	76.85	76.85	76.85	
Year status	9	I st	Ii nd	III rd	Iv^{th}	V^{th}	Current		I st	Ii nd	III rd	Iv^{th}	V^{th}	Current	I st	li nd	III rd	Iv^{th}	v^{th}	Current	I st	li nd	III rd	Iv^{th}	v^{th}	Current	
Irrigation Year	5	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09		2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	
ICA in ha	4	19500							69350						37838						14042						
Designed live storage in Mm ³	3	189.18							525.06						255						76.85						
Project	2	Lower Wunna							Girna						Hatnur						Chanakapur						
S No.	-	13							14						15						16						

Annual Water supply ha/Mm ³ .	13*	47	42	47	33	36	49	108	94	64	95	83	77	143	71	87	86	83	74	84	85	201	207	144	143	
Total recovery Irrigation + Non Irrigation in Lakhs	12	3.44	33.36	1.05	0.68	1.42	7.12	20.28	209.87	55.86	357.80	268.34	188.78	188.02	123.43	265.21	344.06	268.08	376.40	1812.02	2641.60	2338.52	3414.18	3882.56	3414.18	
Recovery Non Irrigation Rs. In Iakhs	11	0.00	29.10	0.79	0.08	0.62	1.16	5.75	140.60	31.59	213.85	174.03	131.72	105.98	97.14	157.82	173.10	155.95	247.45	1772.33	2628.67	2320.67	3389.00	3838.91	3389.00	
Recovery Irrigation Rs. In Iakhs	10	3.44	4.26	0.26	0.60	0.80	5.96	14.53	69.27	24.27	143.95	94.31	57.06	82.04	26.29	107.39	170.96	112.13	128.95	39.69	12.93	17.85	25.18	43.65	25.18	
Irrigated area in ha	6	2455	1630	2339	1391	1965	2125	34732	32053	24428	26348	28554	26744	37329	40276	48185	43001	52735	40942	2710	2110	11293	10553	7196	7174	
Water used for irrigation in Mm ³	8	52.34	38.75	49.51	41.60	54.18	43.48	322.13	339.92	380.44	276.50	344.02	349.15	261.80	571.27	556.71	497.22	638.35	549.79	32.32	24.75	56.18	51.00	50.08	50.20	
Live Storage as on 15th oct	7	52.91	52.91	52.91	52.91	52.91	52.91	304.10	304.10	303.73	304.10	304.09	304.10	266.27	608.82	608.82	608.82	608.82	608.82	158.48	158.48	158.48	159.42	157.12	158.54	
Year status	9	I st	Ii nd	IIIrd	Iv^{th}	v^{th}	Current	I st	Ii nd	III rd	Iv^{th}	v^{th}	Current	I st	li nd	III rd	Iv^{th}	v^{th}	Current	I st	li nd	III rd	Iv^{th}	v^{th}	Current	
Irrigation Year	5	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	
ICA in ha	4	10117						23077						82920						15960						
Designed live storage in Mm ³	3	52.91						304.10						608.82						159.42						
Project	2	Kadva						Bhandardara						Mula						Gangapur						
Sr. No.	-	17						18						19						20						

Annual Water supply ha/Mm ³ .	13*	113	65	84	92	96	107	212	122	150	112	80	61	66	103	94	97	113	98	88	104	141	103	106	126	
Total recovery Irrigation + Non Irrigation in Lakhs	12	13.34	22.07	20.93	24.55	40.38	26.73	490.75	335.85	294.60	283.71	385.96	572.35	11.16	14.06	10.33	14.84	29.96	32.92	605.31	1112.62	801.15	1087.13	1618.25	1438.13	
Recovery Non Irrigation Rs. In Iakhs	11	8.59	5.91	7.18	7.77	25.14	11.89	464.10	293.94	266.57	249.60	353.70	530.88	3.98	7.40	0.53	2.66	9.10	7.15	476.54	657.18	540.91	672.79	816.06	984.61	
Recovery Irrigation Rs. In Iakhs	10	4.75	16.16	13.75	16.78	15.24	14.84	26.65	41.91	28.03	34.11	32.26	41.47	7.18	6.66	9.80	12.18	20.86	25.77	128.77	455.44	260.24	414.34	802.19	453.52	
Irrigated area in ha	6	3182	2292	3348	3064	4264	4436	15851	11521	16951	11043	13468	11046	2264	3206	4079	4100	4504	4444	32901	134516	171475	201402	206523	208735	
Water used for irrigation in Mm ³	8	28.26	35.12	39.95	33.16	44.47	41.50	74.91	94.10	112.76	98.77	167.69	179.95	34.49	30.98	43.54	42.30	39.88	45.46	374.98	1287.52	1216.50	1960.54	1956.68	1650.33	
Live Storage as on 15th oct	7	NA	60.30	60.31	60.31	60.11	60.32	NA	21.23	6.05	6.05	21.24	21.23	NA	72.20	70.84	70.84	70.86	70.86	432.52	1642.98	1688.11	1688.10	1675.14	1688.41	
Year status	9	I st	Ii nd	III rd	Iv^{th}	v^{th}	Current	I st	Ii nd	III rd	Iv^{th}	v^{th}	Current	I st	li nd	III rd	Iv^{th}	v^{th}	Current	I st	Ii nd	III rd	Iv^{th}	v^{th}	Current	
Irrigation Year	5	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	
ICA in ha	4	10400						43154						6750						205277						
Designed live storage in Mm ³	3	60.32						21.24						72.2						1517.2	1688.41					
Project	2	Ozerkhed						Palkhed						Waghad						Bhima						
Sr. No.	٢	21						22						23						24						

Annual Water supply ha/Mm³.	13*	163	195	125	124	95	84	175	188	122	131	118	105	189	162	84	63	86	60	102	98	97	94	137	124	
Total recovery Irrigation + Non Irrigation in Lakhs	12	193.62	201.30	24.40	83.60	193.83	225.46	58.53	120.91	175.84	187.73	296.13	271.47	392.98	177.59	210.27	264.03	372.69	235.50	801.87	770.73	698.93	479.64	622.68	848.40	
Recovery Non Irrigation Rs. In Iakhs	11	39.71	20.47	8.90	17.49	43.20	83.42	53.07	76.93	106.28	147.34	224.98	225.32	237.78	152.18	174.83	151.01	270.57	158.54	587.90	503.60	496.02	359.21	501.45	720.00	
Recovery Irrigation Rs. In Iakhs	10	153.91	180.83	15.50	66.11	150.63	142.04	5.46	43.98	69.56	40.39	71.15	46.15	155.20	25.41	35.44	113.02	102.12	76.96	213.97	267.13	202.91	120.43	121.23	128.40	
Irrigated area in ha	9	61683	104790	50622	47444	69938	50866	18891	22821	17335	18932	16645	17769	49396	50996	30136	26048	38826	33954	26274	27352	30327	42495	42245	42245	
Water used for irrigation in Mm ³	8	377.97	537.08	404.30	382.41	735.05	602.74	108.10	121.19	141.64	144.42	141.34	169.02	261.68	313.88	357.36	411.72	449.79	569.89	257.05	280.11	311.50	452.16	307.73	340.54	
Live Storage as on 15th oct	7	615.16	729.97	850.56	863.20	702.50	759.11	68.22	154.80	154.80	154.80	154.80	154.80	443.02	601.18	602.73	602.11	598.41	602.73	219.97	219.97	219.97	218.30	214.67	217.64	
Year status	9	I st	Ij nd	III rd	Iv^{th}	v^{th}	Current	I st	Ii nd	III rd	Iv^{th}	v^{th}	Current	I st	li nd	III rd	Iv^{th}	v^{th}	Current	I st	Ii nd	III rd	Iv^{th}	v^{th}	Current	
Irrigation Year	5	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	
ICA in ha	4	119166						20500						69269						26560						
Designed live storage in Mm ³	3	864.39						154.8						602.73						219.97						
Project	2	Kukadi						Ghod						Krishna						Radhanagari						
No. No.	-	25						26						27						28						

Annual Water supply ha/Mm ³ .	13*	75	75	114	117	56	68	95	100	155	94	148	131	97	106	133	101	113	78	108	111	108	112	66	110	
Total recovery Irrigation + Non Irrigation in Lakhs	12	18.64	23.02	21.63	14.84	14.87	22.15	281.90	288.38	274.41	174.91	268.36	358.83	266.73	318.65	460.31	363.29	584.87	644.84	538.92	430.23	473.17	529.45	765.62	717.90	
Recovery Non Irrigation Rs. In Iakhs	11	0.00	0.00	7.48	2.54	5.75	5.70	134.64	130.93	78.93	80.70	170.02	192.80	221.92	228.15	336.40	322.00	534.00	619.76	367.63	187.50	311.04	363.55	437.00	351.95	
Recovery Irrigation Rs. In Iakhs	10	18.64	23.02	14.15	12.30	9.12	16.45	147.26	157.45	195.48	94.21	98.34	166.03	44.81	90.50	123.91	41.29	50.87	25.08	171.29	242.73	162.13	165.90	328.62	365.95	
Irrigated area in ha	6	2560	2620	4032	5028	3395	2563	29151	25498	40433	32971	40529	38840	14338	14217	28199	26698	26293	25748	111738	135616	127815	137872	122016	145858	
Water used for irrigation in Mm ³	8	34.35	34.98	35.37	43.04	60.89	37.79	306.65	256.10	260.92	351.10	273.55	296.15	147.40	134.07	211.57	264.97	233.70	328.97	1034.84	1220.76	1184.00	1235.17	1235.27	1331.25	
Live Storage as on 15th oct	7	91.92	91.92	91.92	91.92	91.92	91.92	779.35	779.35	773.40	778.03	746.52	779.35	675.03	675.03	672.67	674.49	678.09	679.11	726.09	931.93	918.43	931.94	931.93	932.01	
Year status	9	I st	Ii nd	IIIrd	Iv^{th}	V^{th}	Current	I st	Ii nd	III rd	Iv^{th}	v^{th}	Current	I st	li nd	III rd	Iv^{th}	v^{th}	Current	I st	Ii nd	III rd	Iv^{th}	v^{th}	Current	
Irrigation Year	5	2003-04	2004-05	2002-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	
ICA in ha	4	4720						137254						73340						102576						
Designed live storage in Mm ³	3	91.92						779.35						679.11						932.01						
Project	2	Tulashi						Warna						Dudhganga						Neera (Complex)						
No. No.	-	29						30						31						32						

Annual Water supply ha/Mm³.	13*	47	154	46	88	107	125	122	164	201	145	166	54	35	32	36	42	39	33	45	45	46	56	38	42	
Total recovery Irrigation + Non Irrigation in Lakhs	12	1744.47	1516.31	2563.63	2333.76	3219.47	3227.64	1844.27	2053.14	2302.75	3033.16	4490.17	4472.47	00.00	2608.20	14.09	24.00	17.30	3276.11	2970.51	2329.22	1274.41	1976.14	2411.72	8219.59	
Recovery Non Irrigation Rs. In Iakhs	11	1650.02	1401.39	2376.24	2116.68	3013.00	3009.00	1835.70	2045.80	2294.61	3022.17	4479.76	4460.33	0.00	2594.00	0.94	12.00	2.00	3263.41	2966.69	2319.97	1270.07	1968.55	2405.65	8214.07	
Recovery Irrigation Rs. In Iakhs	10	94.45	114.92	187.39	217.08	206.47	218.64	8.57	7.34	8.14	10.99	10.41	12.14	0.00	14.20	13.15	12.00	15.30	12.70	3.82	9.25	4.34	7.59	6.07	5.52	
Irrigated area in ha	6	16213	48832	27405	30477	38773	45245	3083	4441	4410	1562	1812	1982	4085	4170	4212	4585	4100	3400	811	1191	1537	2839	2566	2667	
Water used for irrigation in Mm ³	8	345.27	317.33	591.62	347.06	362.62	361.47	25.31	27.02	21.99	10.78	10.89	36.96	115.40	128.73	116.10	110.02	105.84	103.51	18.18	26.38	33.14	50.40	67.98	62.84	
Live Storage as on 15th oct	7	646.74	717.49	778.48	781.73	775.62	793.47	232.54	230.57	235.68	241.11	230.11	241.11	427.71	443.67	322.07	398.50	405.21	423.19	711.86	711.86	838.63	810.83	787.26	782.34	
Year status	9	I st	Ij nd	III rd	Iv^{th}	V^{th}	Current	I st	Ii nd	III rd	Iv^{th}	v^{th}	Current	I st	Ii nd	III rd	Iv^{th}	v^{th}	Current	I st	Ii nd	III rd	Iv^{th}	v^{th}	Current	
Irrigation Year	5	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	
ICA in ha	4	62146						5304						12731						47860						
Designed live storage in Mm ³	3	793.47						241.11						528.19						942.1						
Project	2	Khadakwasla						Pawana						Kal						Bhatsa						
Sr. No.	-	33						34						35						36						

Annual Water supply ha/Mm³.	13*	33	41	23	51	57	39	77	60	90	93	107	67	188	163	55	62	78	66	0	0	95	100	122	105	
Total recovery Irrigation + Non Irrigation in Lakhs	12	920.13	878.23	1002.00	1145.00	1662.23	1754.53	1645.31	2075.05	1619.03	3136.37	3714.26	5223.90	697.48	78.43	245.62	392.75	135.29	111.74	23.72	102.89	189.35	132.57	138.86	119.21	
Recovery Non Irrigation Rs. In Iakhs	11	916.94	873.00	1000.00	1141.00	1658.96	1748.55	1425.42	1995.98	1421.44	2915.73	3515.20	4892.11	697.48	73.58	208.64	284.52	86.08	25.39	23.72	102.89	95.36	51.29	86.39	96.00	
Recovery Irrigation Rs. In Iakhs	10	3.19	5.23	2.00	4.00	3.27	5.98	219.89	79.07	197.59	220.64	199.06	331.79	0.00	4.85	36.98	108.23	49.21	86.35	0.00	0.00	93.99	81.28	52.47	23.21	
Irrigated area in ha	6	2333	2478	2000	4300	3580	3683	10595	55604	100826	113086	126048	104339	494	4089	10828	13349	14979	15465	0	0	9252	13008	12738	12553	
Water used for irrigation in Mm ³	8	70.48	59.82	86.66	85.00	62.85	93.57	137.22	923.52	1115.79	1210.14	1183.10	1548.90	2.63	25.13	195.71	216.48	192.10	235.49	0.00	0.00	97.41	129.99	104.55	119.90	
Live Storage as on 15th oct	7	176.48	176.48	158.69	216.31	175.43	172.12	400.07	2129.14	1927.72	2170.94	2170.94	2170.94	114.50	0.00	312.00	312.00	260.40	312.00	0.00	0.00	173.32	173.32	173.32	173.32	
Year status	9	I st	li nd	IIIrd	Iv^{th}	V^{th}	Current	I st	Ii nd	IIIrd	Iv^{th}	v^{th}	Current	I st	Ii nd	III rd	Iv^{th}	v^{th}	Current	I st	Ii nd	III rd	Iv^{th}	v^{th}	Current	
Irrigation Year	5	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	
ICA in ha	4	8988						183322						54737						18223						
Designed live storage in Mm ³	3	286.31						2171						312						173.32						
Project	2	Surya						Jayakwadi						Majalgaon						Manjra						
Sr. No.	-	37						38						39						40						

Annual Water supply ha/Mm³.	13*	0	0	161	140	151	139	193	197	159	125	125	128	134	163	77	123	116	109	110	130	88	54	64	92	
Total recovery Irrigation + Non Irrigation in Lakhs	12	0.47	0.00	10.30	7.15	3.18	18.21	28.33	116.26	135.01	175.88	217.79	11.11	22.22	22.55	23.48	30.07	24.21	2.61	251.08	94.92	82.57	62.93	32.41	82.65	
Recovery Non Irrigation Rs. In Iakhs	11	0.47	0.00	3.41	0.65	1.15	0.96	26.68	91.54	109.44	159.51	196.63	0.00	1.83	2.32	2.48	1.90	8.63	0.00	127.32	73.11	3.90	2.00	0.97	61.45	
Recovery Irrigation Rs. In Iakhs	10	0.00	0.00	6.89	6.50	2.03	17.25	1.65	24.72	25.57	16.37	21.16	11.11	20.39	20.23	21.00	28.17	15.58	2.61	123.76	21.81	78.67	60.93	31.44	21.20	
Irrigated area in ha	9	0	0	2023	3926	4616	5154	9876	11638	10435	12031	11025	12046	11166	10950	9045	15304	12495	918	38757	4033	36975	36451	23777	20276	
Water used for irrigation in Mm ³	8	0.00	0.00	12.59	28.11	30.53	37.04	51.27	59.09	65.78	96.20	87.96	94.00	83.13	67.14	116.87	124.56	107.84	8.42	353.30	31.10	419.50	670.33	373.42	219.68	
Live Storage as on 15th oct	7	0.00	0.00	37.52	91.22	76.15	91.22	81.37	80.79	80.79	39.49	28.67	80.02	111.03	95.15	138.21	137.08	134.29	39.22	471.59	51.51	499.31	890.22	437.70	265.32	
Year status	9	I st	li nd	III rd	Iv^{th}	v^{th}	Current	I st	Ii nd	III rd	Iv^{th}	v^{th}	Current	I st	Ii nd	IIIrd	Iv^{th}	v^{th}	Current	I st	Ii nd	III rd	Iv^{th}	v^{th}	Current	
Irrigation Year	5	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	
ICA in ha	4	11610						28340						23310						57988						
Designed live storage in Mm ³	3	113.95						80.79						138.21						890.22						
Project	2	Lower Terna						Vishnupuri						Manar						Purna						
Sr. No.	-	41						42						43						44						

[103	255	83	62	51	77	1
Annual	Water	supply	ha/Mm ³ .			13*	v			-			
Total	recovery	Irrigation +	Non	Irrigation in	Lakhs	12	174.73	92.06	30.36	2.14	3.62	46.10	
Recovery	Non	Irrigation	Rs. In	lakhs		11	30.19	61.06	22.17	1.07	2.34	3.45	
Recovery	Irrigation	Rs. In	lakhs			10	144.54	31.00	8.19	1.07	1.28	42.65	
Irrigated	area in ha					6	33913	10932	22052	22843	21188	23131	
Water used	for irrigation area in ha	in Mm ³				8	330.00	42.93	267.29	369.05	419.20	302.17	
Live	Storage	as on	15th oct			7	555.40	137.10	964.09	963.14	871.48	411.27	
Year	status					9	I st	li nd	IIIrd	Iv^{th}	V^{th}	Current	
Irrigation	Year					2	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	
ICA in ha						4	125495						
Designed ICA in ha	live storage	in Mm ³				3	964.09						
Project						2	Upper Penganga						NOTE :
ເ	No					٦	45]

1 Change in col.No.3 of designed live storage in respective years if any is due to revision in designed live storage capicity 2 In col. No.8 of water used for irrigation is more than col.No. 7 of live storage as on 15th Oct. of respictive year is due to water utilisation in kharif of east

Vidharbha Region.

3 Col.No.9 of irrigated area is more than Col.No.4 of ICA is due to increase of area in kharif seasion in east Vidharbha region. 4 Zero value in col. 13 due to non availability of water for irrigation.

	Annual	Water	supply	ha/Mm ³ .		13	187	0	88	160	108	220		90	0	76	138	190	145	355	0	113	167	200	0	100	0	0	181	225	159	
	Total	recovery	Irrigation +	Non	irrigation in Lakhs	12	13.18	11.06	2.07	4.03	9.26	4.95		7.87	3.12	5.50	5.44	5.98	2.82	0.53	0.00	0.54	4.56	7.27	1.31	82.17	45.16	5.98	5.04	53.00	72.69	
	Recovery	Non-	Irrigation	Rs. In	lakhs	11	10.60	10.98	2.07	2.84	5.19	3.74		2.10	3.12	5.50	1.17	1.87	1.09	0.25	00.00	0.54	2.44	2.81	1.05	77.82	45.07	5.98	5.04	53.00	72.69	
2008-09)	Recovery	Irrigation	Rs. In	lakhs		10	2.58	0.08	00.00	1.19	4.07	1.21		5.77	0.00	00.00	4.27	4.11	1.73	0.28	00.0	00.00	2.12	4.46	0.26	4.35	0.09	00.0	00.0	00.00	00.00	
Analysis of Medium projects in Maharashtra State (2003-04 to 2008-09)	Irrigated	area in ha				6	343	0	733	3150	3606	840		918	0	1279	3293	2818	1401	71	0	791	1533	2066	0	1236	0	0	1795	1428	1188	
htra State	Water		irrigation	in Mm ³		ω	1.83	00.00	8.35	19.68	33.29	3.82		10.16	0.00	16.87	23.84	14.85	9.69	0.20	00.00	7.02	9.16	10.32	00.00	12.32	00.0	00.0	9.91	6.35	7.47	
n Maharas	Live	Storage	as on	15th oct		7	12.06	2.61	15.49	41.46	41.46	8.65		18.66	3.37	21.33	28.85	20.03	14.48	1.23	0.10	11.68	11.68	11.68	0.24	30.08	6.48	4.69	33.93	22.36	20.10	
i projects i	Year	status				9	lst	pu ^{II}	IIIrd	Iv^{th}	$\Lambda_{ m tp}$	Current	-	I st	li nd	IIIrd	Iv^{th}	$\Lambda_{ m tp}$	Current	l st	pu ^{II}	IIIrd	Iv^{th}	$\Lambda^{ m th}$	Current	I st	pu [!] I	IIIrd	Iv^{th}	Λ^{th}	Current	
of Medium	Irrigation	Year				5	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09		2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	
nalysis	ICA in	ha				4	4633							5836						2241						4249						
∢	Designed	live	storage	in Mm ³		3	41.46							28.85						11.68						33.93						
	Project					2	Morna							Nirguna						Uma						Gyanganga						
	Sr.	No				~	-							2						3						4						

Annual Water supply ha/Mm ³ .		13	172	0	0	171	166	127	140	0	0	145	168	214	220	270	223	249	222	228	160	84	77	181	162	166
Total recovery Irrigation + Non	irrigation in Lakhs	12	5.05	0.29	0.51	0.00	2.62	3.81	6.07	3.87	0.83	0.92	1.02	5.40	14.30	3.79	7.91	6.29	0.54	4.97	32.49	25.89	25.90	45.34	59.43	20.45
Recovery Non- Irrigation Rs. In	lakhs	11	2.19	0.26	0.50	0.00	2.62	3.81	4.33	3.65	0.81	0.92	1.02	5.40	13.45	3.79	3.91	0.00	0.54	4.95	26.90	23.82	18.92	38.32	52.61	13.44
Recovery Irrigation Rs. In Iakhs		10	2.86	0.03	0.01	0.00	00.0	0.00	1.74	0.22	0.02	0.00	00.0	0.00	0.85	0.00	4.00	6.29	00.0	0.02	5.59	2.07	6.98	7.02	6.82	7.01
Irrigated area in ha		6	835	0	0	922	808	521	340	0	0	1673	1382	564	11	384	2700	4224	3051	98	2343	463	962	2796	2847	2495
Water used for irrigation in Mm ³		8	4.85	0.00	0.00	5.39	4.87	4.09	2.42	0.00	0.00	11.55		2.64	0.05	1.42	12.09	16.95	13.75	0.43	14.67	5.51	12.53	15.49	17.59	14.99
Live Storage as on 15th oct		7	7.51	2.14	0.70	7.51	7.23	7.51	7.35	4.50	0.70	15.04	12.96	7.85	0.79	3.19	15.89	20.70	18.47	1.90	NA	17.90	46.04	46.04	43.88	32.93
Year status		9	I st	li nd	III	Iv^{th}	$\Lambda^{ m th}$	Current] st	li nd	III	I_V^{th}	V^{th}	Current	I st	li nd	III	I_V^{th}	$\Lambda_{ m tp}$	Current	I st	pu ^{II}	III	I_V^{th}	V^{th}	Current
Irrigation Year		5	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09
ICA in ha		4	1932						4415						4061						7466					
Designed live storage in Mm ³		3	7.51						22.04						20.7						46.04					
Project		2	Paldhag						Mas						Koradi						Shahanoor					
Sr. No.		-	5						9						7						8					

Annual Water	supply	ha/Mm ³ .			13		06	0	70	107	129	94	140	0	171	24	173	444	180	205	172	182	216	0	200	0	0	152	158	267	
Total	Irrigation +	Non	irrigation	IN Lakhs	12		14.95	2.08	0.02	1.72	3.31	7.98	3.15	0.09	0.21	1.22	0.19	0.19	1.55	0.00	6.10	7.19	9.68	1.02	7.69	2.76	5.99	7.10	10.68	12.11	
Recovery Non-	Irrigation	Rs. In	lakhs		11		11.04	1.38	0.00	1.68	3.18	6.92	0.17	0.09	0.09	0.09	0.09	0.09	00.00	00.0	00.00	00.0	0.87	1.02	5.94	2.76	5.98	4.69	8.25	11.09	
Recovery	Rs. In	lakhs		0	10		3.91	0.70	0.02	0.04	0.13	1.06	2.98	0.00	0.12	1.13	0.10	0.10	1.55	00.0	6.10	7.19	8.81	00.0	1.75	00.0	0.01	2.41	2.43	1.02	
Irrigated area in ha	5			(6		1248	0	831	1482	1726	1450	736	0	902	130	987	182	521	41	1798	2507	2813	0	965	0	0	1338	1249	753	
Water used for	irrigation	in Mm ³		(8		13.93	0.00	11.86	13.87		15.50	5.24	0.00	5.28	5.49	5.71	0.41	2.90	0.20	10.46	13.81	13.05	0.00	4.83	0.00	0.00	8.79	7.92	2.82	
Live	as on	15th oct		1	7		NA	12.89	27.18	27.18	27.18	27.18	NA	2.11	6.53	6.61	6.61	1.69	NA	0.20	16.92	16.92	16.92	0.00	NA	3.13	11.97	11.97	11.97	9.29	
Year				(9	-	181	li nd	III rd	Iv^{th}	Λ_{tp}	Current	I st	li nd	III rd	Iv^{th}	Λ_{tp}	Current	I st	li nd	III rd	Iv^{th}	V^{th}	Current	l st	pull	IIIrd	Iv^{th}	Λ^{th}	Current	
Irrigation Year	5			1	5		2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	
ICA in ha	5				4		3116						2271						2447						2271						
Designed	storage	in Mm ³		(ε		27.18						6.61						16.92						11.97						
Project				(2		Saikheda						Borgaon						Sonal						Ekburji						
Sr.				,	-		б						10						11						12						

Annual Water supply ha/Mm ³ .	13	103	0	191	86	113	133		169	158	1550	91	96	117	206	36	125	82	675	110	174	0	43	86	104	243	
Total recovery Irrigation + Non irrigation	12	13.97	2.87	15.12	4.26	6.51	16.05		11.72	7.54	5.23	0.12	10.58	7.18	1.65	0.86	0.20	0.35	0.00	0.00	13.45	4.63	0.00	7.81	12.62	0.00	
Recovery Non- Irrigation Rs. In Iakhs	11	4.89	2.87	7.62	3.50	5.59	13.02		0.00	3.04	4.68	0.00	0.71	1.16	0.00	0.00	0.00	0.00	00.0	00.0	12.15	4.63	0.00	7.38	12.14	0.00	
Recovery Irrigation Rs. In Iakhs	10	9.08	00'0	7.50	0.76	0.92	3.03		11.72	4.50	0.55	0.12	9.87	6.02	1.65	0.86	0.20	0.35	00'0	00.0	1.30	0.00	00'0	0.43	0.48	0.00	
Irrigated area in ha	ი	3749	0	7829	4098	4568	4627		1422	757	31	2618	1056	1903	294	43	5	462	27	576	1212	0	1695	4862	4281	745	
Water used for irrigation in Mm ³	8	36.24	00.00	40.98	47.49	40.55	34.72		8.42	4.79	0.02	28.79	11.14	16.28	1.43	1.21	0.04	5.65	0.04	5.23	6.95	0.00	39.35	56.26	41.18	3.07	
Live Storage as on 15th oct	7	NA	00.0	59.63	59.63	59.50	54.30	0000	22.66	7.79	3.85	36.83	13.31	17.50	NA	2.04	0.50	7.90	1.26	6.91	17.73	1.25	67.25	67.25	67.25	3.81	
Year status	9	l st	pu ^{II}	IIIrd	Iv^{th}	V^{th}	Current	ţ	10 I	li nd	III rd	Iv^{th}	$\Lambda^{ m th}$	Current] st	li nd	IIIrd	Iv^{th}	V^{th}	Current] st	li nd	IIIrd	Iv^{th}	V^{th}	Current	
Irrigation Year	5	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09		2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	
ICA in ha	4	6600							7804						1465						7804						
Designed live storage in Mm ³	з	59.63							36.83						7.9						67.25						
Project	2	Lowerpus							Mun						Torna						Adan						
Sr. No.	-	13							14						15						16						

Annual Water	supply ha/Mm³		13	132	0	148	138	111	125	267	000	269	326	276	360	400	523	300	409	304	431	385		183	360	214	192	199	231	
Total recovery	Irrigation + Non	irrigation in Lakhs	12	0.64	0.30	0.67	0.00	1.00	4.66	1 67	4.04	0.56	7.55	5.26	14.88	0.34	4.43	0.22	7.87	3.56	12.80	0.03		8.54	1.10	5.60	3.37	12.34	1.40	
Recovery Non-	Irrigation Rs. In	lakhs	11	0:30	0:30	0.67	0.00	1.00	4.66				0.00	0.81	0.07	0.04	0.00	0.00	0.00	0.01	00.0	00.00		0.00	00.0	00.0	00.0	0.00	00.00	
Recovery Irrigation	Rs. In lakhs		10	0.34	00.0	00.0	00.0	00.0	00.0	167		00.0	7.55	4.45	14.81	0:30	4.43	0.22	7.87	3.55	12.80	0.03		8.54	1.10	5.60	3.37	12.34	1.40	
Irrigated area in ha			6	606	0	577	436	479	526	1108		2879	4295	4303	4345	4023	5044	1333	5409	5064	5064	3749		3752	2433	3552	3196	3533	3009	
Water used for	irrigation in Mm ³		ω	6.90	0.00	3.91	3.15	4.30	4.22	17 50			13.17	15.57	12.07	10.05	9.65	4.44	13.24	16.65	11.74	9.73		20.54	6.76	16.60	16.66	17.72	13.03	
Live Storage	as on 15th oct		7	12.47	2.97	12.47	12.47	12.17	12.34	16 AE		10.74	8.73	5.93	4.04	1.75	10.71	4.44	13.11	9.72	2.24	0.98		19.99	7.22	14.27	11.39	18.38	2.63	
Year status			9	I st	li nd	IIIrd	Iv^{th}	V^{th}	Current	Ist	T T	••••[]	III ^{ra}	Iv th	V^{th}	Current] st	li nd	III rd	Iv^{th}	V^{th}	Current	-] st	li nd	IIIrd	Iv^{th}	V^{th}	Current	
Irrigation Year			ъ	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2002-04		2004-02	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09		2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	
ICA in ha			4	2056						7047	101						4047							3167						
Designed live	storage in Mm ³		с	12.47						16 AE	0 						20.8							21.46						
Project			2	Navargaon						Bodalkaca							Chorakhmara							Chulband						
Sr. No.			-	17						0	2						19							20						

Annual Water supply	ha/Mm ³ .	13	481	373	539	410	582	598	000	000	266	347	306	389	404	202	254	177	208	332	154	382	284	363	274	336	261	
Total recovery Irrigation +	Non irrigation in Lakhs	12	7.21	0.00	11.23	5.73	15.52	1.25	1 15		0.12	2.48	1.29	3.60	0.01	0.80	0.12	0.78	1.20	2.31	0.15	2.08	2.40	2.67	1.84	2.57	0.79	
Recovery Non- Irrigation	Rs. In lakhs	11	0.00	0.00	0.00	0.00	00.0	00.0		0.00	0.00	0.00	0.00	00.0	00.0	0.00	0.00	00.0	0.00	00.0	00.0	0.00	0.00	0.00	00.0	0.00	0.00	
Recovery Irrigation Rs. In	lakhs	10	7.21	00.0	11.23	5.73	15.52	1.25	1 15	- -	0.12	2.48	1.29	3.60	0.01	0.80	0.12	0.78	1.20	2.31	0.15	2.08	2.40	2.67	1.84	2.57	0.79	
Irrigated area in ha		6	5422	1338	5647	5239	5285	5045	1010	0 0	234	1161	1099	1004	792	1065	800	1029	1008	1251	1045	994	959	985	943	980	945	
	in Mm ³	ω	11.27	3.59	10.48	12.76	9.09	8.44	00 0	0.03	0.88	3.35	3.59	2.58	1.96	5.28	3.15	5.82	4.85	3.77	6.78	2.60	3.38	2.71	3.44	2.92	3.62	
Live Storage as on	15th oct	7	15.38	4.48	11.91	15.95	6.93	1.23	73 0	0.0	1.38	2.15	0.64	1.17	0.16	7.05	3.36	4.90	4.30	6.89	4.04	3.57	3.57	1.96	1.42	2.78	0.65	
Year status		9] st	li nd	IIIrd	Iv^{th}	V^{th}	Current	Ist	- pu	, II	III rd	Iv^{th}	V^{th}	Current] st	li nd	IIIrd	Iv^{th}	V^{th}	Current] st	li nd	IIIrd	I_{V}^{th}	V^{th}	Current	
Irrigation Year		ъ	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09		t0-0007	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	
ICA in ha		4	6109						1004	1034						1700						870						
Designed live storage	in Mm ³	с	15.95						70 C	10.0						7.05						3.57						
Project		2	Khairbanda						Constraint	Janganpu						Managadh						Rengepar						
Sr. No.		-	21						ç	77						23						24						

Annual Water	supply ha/Mm ³		13	686	339	711	130	448	527		156	272	704	329	380	684	155	215	229	224	245	498	156	186	303	271	253	272	
Total recovery	Irrigation + Non	irrigation in Lakhs	12	7.76	0.12	6.96	82.00	9.23	2.91		1.31	0.00	0.58	0.88	0.95	0.20	0.99	0.01	1.18	1.11	1.28	0.35	2.01	0.01	2.16	2.72	1.89	0.89	
Recovery Non-	Irrigation Rs. In	lakhs	11	00.0	00.0	00.0	41.00	00.0	00.0		0.00	0.00	0.00	0.05	00.0	00.0	0.00	00.0	00.0	00.0	00.00	00.0	0.00	00.0	00.0	00.0	0.00	00.00	
Recovery Irrigation	Rs. In Iakhs		10	7.76	0.12	6.96	41.00	9.23	2.91		1.31	0.00	0.58	0.83	0.95	0.20	0.99	0.01	1.18	1.11	1.28	0.35	2.01	0.01	2.16	2.72	1.89	0.89	
Irrigated area in ha			6	5767	2727	5998	130	6390	6448		1100	662	1284	1192	1185	1149	793	750	769	768	808	767	981	662	996	994	1042	875	
Water used for	irrigation in Mm ³		ω	8.41	8.04	8.43	1.00	14.28	12.23	1	1.07	2.43	1.83	3.62	3.12	1.68	5.10	3.49	3.36	3.43	3.30	1.54	6.30	3.57	3.19	3.67	4.12	3.22	
Live Storage	as on 15th oct		7	16.22	8.14	13.93	11.71	6.86	0.09		4.04	2.57	2.62	1.62	1.22	0.13	3.66	3.49	1.79	1.00	1.78	0.00	5.73	3.57	3.70	3.04	2.58	0.00	
Year status			9	I st	li nd	III	Iv^{th}	V^{th}	Current	ā	<u>,</u>	li nd	IIIrd	Iv^{th}	Λ^{th}	Current] st	li nd	IIIrd	Iv^{th}	V^{th}	Current] st	li nd	IIIrd	Iv^{th}	V^{th}	Current	
Irrigation Year			5	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	10,0000	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	
ICA in ha			4	6271							1/98						1315						933						
Designed live	storage in Mm ³		с	28.87						0	4.53						3.66						5.73						
Project			2	Chandpur						-	Bagneda						Betekar Bothali						Sorna						
Sr. No.			-	25						0	26						27						28						

Annual Water supply ha/Mm ³ .		13	119	306	115	89	92	89	Ċ	68	300	94	96	97	148	103	486	102	118	95	79	167	273	163	129	80	126	
Total recovery Irrigation + Non	irrigation in Lakhs	12	1.84	0.68	0.32	1.90	2.98	0.23		1.08	0.83	0.55	1.06	1.85	0.07	0.17	0.38	0.38	1.07	0.99	0.05	0.92	0.03	0.43	1.14	0.58	0.19	
Recovery Non- Irrigation Rs. In	lakhs	11	0.00	0.02	0.03	0.33		0.21		0.08	0.07	0.08	0.10	0.10	0.05	0.03	0.34	0.36	0.47		0.00	0.00	0.00	0.00	0.00	0.00	0.00	
Recovery Irrigation Rs. In Iakhs		10	1.84	0.66	0.29	1.57	2.65	0.02		1.00	0.76	0.47	0.96	1.75	0.02	0.14	0.04	0.02	0.60	0.99	0.05	0.92	0.03	0.43	1.14	0.58	0.19	
Irrigated area in ha		6	745	524	571	547	574	20		337	361	274	349	325	101	159	136	214	235	324	522	396	505	368	395	393	450	
Water used for irrigation in Mm ³		8	6.25	1.71	4.98	6.12	6.23	0.79		4.95	1.21	2.92	3.62	3.37	0.68	1.54	0.28	2.09	1.99	3.40	6.57	2.37	1.85	2.26	3.07	4.89	3.56	
Live Storage as on 15th oct		7	8.26	3.87	8.26	8.26	7.64	0.73		4.95	1.94	4.95	4.95	4.46	0.93	2.20	0.98	3.93	2.45	3.52	0.63	5.14	2.85	5.14	3.50	4.51	4.76	
Year status		9	I st	li nd	III rd	Iv^{th}	V^{th}	Current	1¢	ا ^{یر}	li nd	III rd	Iv^{th}	Λ^{th}	Current	I st	pu ^{II}	IIIrd	Iv^{th}	$v^{ m th}$	Current] st	li nd	IIIrd	Iv^{th}	$v^{ m th}$	Current	
Irrigation Year		5	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09		2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	
ICA in ha		4	3181							1315						780						12						
Designed live storage in Mm ³		3	8.26							4.95						3.93						5.14						
Project		2	Chandrabhaga						=	Mordham						Kesarnala						Umri						
Sr. No.		-	29						0	30						31						32						

Annual Water supply	ha/Mmč.	13	111	513	93	136	118	154	180	00-	240	24	31	36	79	98	407	169	202	68	244	82	143	98	109	128	128	
Total recovery Irrigation +	irrigation in Lakhs	12	12.47	47.68	10.61	12.64	16.39	5.62	V _ U		c0.1c	0.27	0.58	1.18	0.05	185.71	228.60	211.28	228.33	250.81		2.33	1.95	1.73	3.11	2.60	0.02	
Recovery Non- Irrigation	lakhs	11	10.97	46.52	9.98	9.81	15.77	4.92		1.00	00.1C	0.00	0.00	0.00	00.0	185.67	228.56	211.26	228.28	250.11	259.35	0.69	00.0	00.0	00.0	00.0	00.0	
Recovery Irrigation Rs. In	lakns	10	1.50	1.16	0.63	2.83	0.62	0.70	0 74	100	0.0	0.27	0.58	1.18	0.05	0.04	0.04	0.02	0.05	0.70	0.07	1.64	1.95	1.73	3.11	2.60	0.02	
Irrigated area in ha		6	1460	1418	1232	2814	2587	2148	1580	000	000	325	522	517	522	234	61	22	72	240	44	1244	1030	1436	1683	1675	1781	
	in Mm	ω	13.12	2.77	13.31	20.75		13.96	8 76		20.0	13.76	16.99	14.42	6.57	2.40	0.15	0.13	0.36	3.53		15.12	7.22	14.72	15.42	13.05	13.86	
Live Storage as on		7	24.45	9.16	31.32	27.74	27.26	17.65	10 61		01.01	22.14	21.72	20.86	8.68	NA	10.41	11.06	6.17	21.30	12.39	18.15	14.27	19.71	20.48	20.49	18.00	
Year status		9	I st	li nd	IIIrd	Iv^{th}	V^{th}	Current	Ist	r:nd	II	n, III	Iv th	V^{th}	Current	I st	li nd	IIIrd	Iv^{th}	V^{th}	Current] st	li nd	IIIrd	Iv^{th}	Λ^{th}	Current	
Irrigation Year		5	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04		CU-4002	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	
ICA in ha		4	5940						2640	20104						1214						3371						
Designed live storage	in Mm	3	31.32						72 81	0.04						21.64						20.49						
Project		2	Kolar						Khakranala							Wunna						Kanholibara						
Sr. No.		-	33						34	5						35						36						

Annual Water supply ha/Mm ³ .	13	209	288	179	192	188	0		143	178	114	137	110	167	192	296	121	200	170	285		138	200	198	143	202	242	
Total recovery Irrigation + Non irrigation in Lakhs	12	6.36	4.92	6.35	5.61	6.49	00.0		8.23	7.18	5.20	9.75	11.89	10.78	12.70	10.02	3.65	11.67	5.19	0.81		4.42	4.74	4.38	4.37	1.81	1.95	
Recovery Non- Irrigation Rs. In Iakhs	11	2.38	2.32	2.71	3.50	4.49	0.00	1	7.7.T	3.01	2.11	2.41	5.89	10.74	0.00	0.69	2.12	1.75	1.81	0.18		0.00	0.39	0.55	0.48	0.18	0.02	
Recovery Irrigation Rs. In Iakhs	10	3.98	2.60	3.64	2.11	2.00	0.00	1	1.01	4.17	3.09	7.34	6.00	0.04	12.70	9.33	1.53	9.92	3.38	0.63		4.42	4.35	3.83	3.89	1.63	1.93	
Irrigated area in ha	6	1677	1690	1437	1422	1427	0		3473	2691	2490	2890	2760	311	3846	5729	762	5912	5868	5844		1688	2843	2840	2850	2795	2876	
Water used for irrigation in Mm ³	ω	8.02	5.86	8.03	7.42	7.60	00.0			15.08	21.92	21.11	25.02	1.86	20.07	19.36	6.29	29.60	34.48	20.49		12.19	14.20	14.35	19.95	13.83	11.88	
Live Storage as on 15th oct	7	13.14	13.14	12.01	11.16	11.66	3.33		CU.81	14.38	15.38	25.90	25.90	4.08	33.25	23.22	28.92	19.26	26.54	2.77		8.18	8.18	5.79	8.48	9.36	0.97	
Year status	9	I st	li nd	III rd	Iv^{th}	V^{th}	Current	TST.	<u>,</u>	li nd	III rd	Iv^{th}	$\Lambda^{ m th}$	Current] st	li nd	III rd	Iv^{th}	V^{th}	Current	-] st	li nd	IIIrd	Iv^{th}	V^{th}	Current	
Irrigation Year	5	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09		2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09		2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	
ICA in ha	4	862							54//						3846							1888						
Designed live storage in Mm ³	с	13.14						0	25.9						43.16							10.23						
Project	2	Pandhrabodi							Makardnokda						Ghorazari							Naleshwar						
Sr. No.	-	37						00	38						39							40						

Annual Water supply ha/Mm ³ .	13	185	146	129	226	183	241		130	130	112	111	56	73	307	139	162	157	144	227		272	0	162	128	162	177	
Total recovery Irrigation + Non irrigation in Lakhs	12	2.79	1.38	2.06	2.07	1.21	0.42		3.42	2.97	3.03	3.14	4.15	2.60	2.16	1.00	1.66	3.09	1.40	1.44		161.67	163.15	177.30	181.29	207.19	192.02	
Recovery Non- Irrigation Rs. In Iakhs	11	00.0	0.35	0.53	0.27	0.42	0.13		0.00	0.48	1.41	0.85	2.26	0.07	0.00	0.19	0.45	0.65	0.39	0.63		158.68	163.15	174.80	176.08		189.31	
Recovery Irrigation Rs. In Iakhs	10	2.79	1.03	1.53	1.80	0.79	0.29		3.42	2.49	1.62	2.29	1.89	2.53	2.16	0.81	1.21	2.44	1.01	0.81		2.99	0.00	2.50	5.21	2.38	2.71	
Irrigated area in ha	6	1367	1102	1369	1340	1336	1178		2120	1724	1924	1825	916	873	2000	442	1119	1055	877	949		3900	0	2017	2051	2571	1768	
Water used for irrigation in Mm ³	8	7.37	7.57	10.57	5.93		4.89		16.36	13.23	17.22	16.44	16.41	11.94	6.52	3.17	6.90	6.70	6.07	4.18		14.32	0.00	12.45	16.05	15.83	9.98	
Live Storage as on 15th oct	7	10.69	10.69	8.95	9.52	9.52	1.12		19.87	18.43	17.73	18.24	18.28	8.80	2.35	4.80	7.24	7.35	7.35	7.35		21.20	5.20	21.20	24.48	21.20	16.24	
Year status	9	I st	li nd	IIIrd	Iv^{th}	V^{th}	Current	-] st	li nd	IIIrd	Iv^{th}	V^{th}	Current] st	li nd	III rd	Iv^{th}	V^{th}	Current	ţ] sr	li nd	III rd	Iv^{th}	V^{th}	Current	
Irrigation Year	5	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09		2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09		2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	
ICA in ha	4	2056							1500						2024							2962						
Designed live storage in Mm ³	3	10.69							19.87						7.35							24.48						
Project	2	Chandai							Chargaon						Labhansarad							Amal Nala						
No. No.	-	41							42						43							4						1

Annual	supply	ha/Mm ³ .			13	193	142	74	57	52	51	102	134	92	92	84	106	286	491	57	73	75	65		159	130	112	115	112	98	
Total	Irrigation +	Non	irrigation	IN Lakhs	12	1.10	0.46	0.31	0.40	1.86	1.38	2.82	0.91	0.86	3.26	4.49	5.01	1.25	0.31	0.03	0.31	0.69	0.58	1	1.12	3.88	4.83	10.43	8.02	13.43	
Recovery	Irrigation	Rs. In	lakhs		11	0.00	00.0	00.0	00.0	0.13	0.11	0.00	0.00	0.00	06.0	1.78	2.05	0.07	00.0	00.0	0.00	0.07	0.07	L	0.45	0.32	0.80	9.48	3.55	7.88	
Recovery	Rs. In	lakhs			10	1.10	0.46	0.31	0.40	1.73	1.27	2.82	0.91	0.86	2.36	2.71	2.96	1.18	0.31	0.03	0.31	0.62	0.51	1 1	1.21	3.56	4.03	0.95	4.47	5.55	
Irrigated					ი	724	245	480	525	514	500	2588	1550	2343	2080	2054	1759	730	216	201	206	215	220		1/61	4786	1860	4105	3941	3502	
Water Isod for	irrigation	in Mm ³			ω	3.75	1.72	6.52	9.21	9.85	9.82	25.41	11.54	25.34	22.63	24.32	16.55	2.55	0.44	3.52	2.81	2.87	3.38			36.92	16.66	35.60	35.10	35.66	
Live	as on	15th oct		I	7	6.20	3.81	10.10	9.80	10.39	9.82	NA	19.39	34.17	34.58	34.72	23.38	2.96	0.83	474	4.44	474	4.39		11.68	40.27	20.02	40.27	40.27	40.27	
Year	010100				9] st	pu ^{II}	IIIrd	I_V^{th}	V^{th}	Current	I st	li nd	III rd	I_V^{th}	Λ^{th}	Current	I st	li nd	IIIrd	Iv^{th}	Λ^{th}	Current	151	1.	Ii nd	III rd	Iv^{th}	V^{th}	Current	
Irrigation				1	5	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	10,000	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	
ICA in	2				4	1822						8948						631						1001	4864						
Designed	storage	in Mm ³		,	n	10.39						34.72						4.44							40.27						
Project					2	Panchadhara						Pothra						Dongargaon (Chandrapur)							Manyad						
Sr.					.	45						46						47						9	48						

Annual Water supply ha/Mm ³ .		13	124	6211	1122	117	105	111		96	257	102	89	85	94	121	114	113	38	28	26		137	142	103	95	170	108	
Total recovery Irrigation + Non	irrigation in Lakhs	12	6.04	15.60	7.99	17.77	16.35	29.29		0.49	0.49	0.26	1.74	1.60	1.56	15.90	14.95	25.76	10.32	8.53	14.62		2.61	2.43	4.64	0.41	0.87	0.81	
Recovery Non- Irrigation Rs. In	lakns	11	4.03	15.29	7.68	17.70	8.91	24.03		0.00	0.00	0.21	1.60	0.45	1.07	5.75	6.40	9.60	6.15	4.62	10.87		0.00	0.00	00.0	0.00	0.00	0.00	
Recovery Irrigation Rs. In Iakhs		10	2.01	0.31	0.31	0.07	7.44	5.26		0.49	0.49	0.05	0.14	1.15	0.49	10.15	8.55	16.16	4.17	3.91	3.75		2.61	2.43	4.64	0.41	0.87	0.81	
Irrigated area in ha	,	თ	1127	2795	1515	1905	2161	1662		192	18	134	406	415	192	2030	2371	2604	872	945	926		412	547	310	275	400	355	
Water used for irrigation in Mm ³		ω	9.07	0.45	1.35	16.35	20.63	15.00		2.00	0.07	1.32	4.56	4.87	2.05	16.72	20.84	23.04	22.65				3.00	3.86	3.02	2.91	2.35	3.30	
Live Storage as on 15th oct		7	25.15	2.11	11.35	25.15	25.15	25.15	1	6.54	1.76	2.77	6.54	6.54	3.14	39.85	39.58	39.66	39.85	39.85	39.85		6.02	6.02	3.95	6.02	6.02	6.02	
Year status		9] st	li nd	III	Iv^{th}	V^{th}	Current	±-	10	li nd	IIIrd	Iv^{th}	V^{th}	Current] st	li nd	IIIrd	Iv^{th}	V^{th}	Current	-] st	li nd	IIIrd	Iv^{th}	V^{th}	Current	
Irrigation Year		5	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09		2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09		2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	
ICA in ha		4	4553							1205						5128							1115						
Designed live storage in Mm ³		ო	25.15							6.54						39.85							6.02						
Project		2	Bori							Bhokarbari						Suki							Abhora						
Sr. No.		~	49							50						51							52						

Annual Water supply ha/Mm ³ .	13	147	392	183	132	0	116		114	141	146	131	179	128	407	645	0	323	569	0		206	189	135	76	107	146	
Total recovery Irrigation + Non irrigation in Lakhs	12	0.56	0.07	0.42	1.41	0.77	3.40		1.13	1.31	1.54	2.35		5.06	1.87	1.80	1.78	3.17	2.76	1.52		1.98	1.90	14.35	8.25	1.62	3.49	
Recovery Non- Irrigation Rs. In Iakhs		0.00	00.0	0.34	0.89	0.77	3.40		0.00	0.00	1.54	2.26	5.42	4.86	1.06	1.12	1.78	3.15	2.69	1.52		0.00	1.00	13.50	6.92	0.41	2.46	
Recovery Irrigation Rs. In Iakhs	10	0.56	0.07	0.08	0.52	0.00	00.0		1.13	1.31	00.0	0.09	0.52	0.20	0.81	0.68	0.00	0.02	0.07	00.0		1.98	0.90	0.85	1.33	1.21	1.03	
Irrigated area in ha	0	94	47	22	79	0	158		594	731	262	679	262	844	305	284	0	113	74	0		650	345	602	415	890	1331	
Water used for irrigation in Mm ³	ω	0.64	0.12	0.12	0.60	0.00	1.36		5.22	5.19	1.80	5.19	1.46	6.59	0.75	0.44	0.00	0.35	0.13	00.0		3.16	1.83	4.45	5.48	8.32	9.13	
Live Storage as on 15th oct	7	2.76	2.76	2.18	2.76	00.0	2.76		9.60	9.60	6.11	9.60	3.78	9.60	4.64	4.64	00.0	4.63	3.10	0.98		NA	3.75	6.59	8.45	8.45	8.45	
Year status	9	I st	1. Jud	IIIrd	Iv^{th}	V^{th}	Current	-] st	li nd	IIIrd	I_V^{th}	$v^{ m th}$	Current	I st	li nd	IIIrd	Iv^{th}	$\sqrt{\mathrm{th}}$	Current	-] st	li nd	III rd	Iv^{th}	$v^{ m th}$	Current	
Irrigation Year	5	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09		2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09		2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	
ICA in ha	4	605							2231						1060							1363						
Designed live storage in Mm ³	ю	2.76							9.6						4.64							8.45						
Project	2	Agnawati							Hiwara						Tondapur							Kanoli						
Sr. No.	-	53							54						55							56						

Annual Water supply ha/Mm ³ .	13	131	153	131	191	292	188		118	125	164	168	131	125	236	141	177	196	137	7331		94	110	109	67	95	67	
Total recovery Irrigation + Non irrination	in Lakhs 12	1.85	3.64	4.10	3.49	2.24	1.30		2.01	2.86	6.47	3.66	2.38	3.36	7.07	9.95	18.77	34.14	24.55	6.54		11.71	12.50	48.56	14.07	11.01	11.00	
Recovery Non- Irrigation Rs. In Lakhs	11	0.00	00.0	0.00	0.00	0.00	0.00	0	0.00	0.70	4.37	1.20	00.0	1.81	0.00	1.00	7.99	25.28	15.27	0.91		0.00	0.00	39.02	0.00	0.00	0.00	
Recovery Irrigation Rs. In Iakhs	10	1.85	3.64	4.10	3.49	2.24	1.30	i i	2.01	2.16	2.10	2.46	2.38	1.55	7.07	8.95	10.78	8.86	9.28	5.63		11.71	12.50	9.54	14.07	11.01	11.00	
Irrigated area in ha	σ	1462	1431	1667	2619	3767	2368		804	855	985	1325	1090	921	4579	3748	4032	4507	2994	3538		2272	3358	3695	3286	4360	3106	
Water used for irrigation in Mm ³	œ	11.20	9.34	12.68	13.73	12.90	12.57		6.81	6.86	6.02	7.90	8.34		19.42	26.49	22.82	22.98		25.93		24.22	30.39	33.86	48.78	45.75	46.62	
Live Storage as on 15th oct	7	, NA	14.21	14.21	14.21	14.21	14.21		NA	11.33	11.32	11.32	11.33	11.33	NA	35.63	35.63	35.63	35.63	35.63		NA	21.39	59.20	59.20	59.21	59.21	
Year status	ų]st	pu ^{II}	III rd	Iv^{th}	V^{th}	Current	ţ	ر اور	li nd	III rd	Iv^{th}	V^{th}	Current] st	li nd	IIIrd	Iv^{th}	V^{th}	Current	-	1.21	li nd	III rd	Iv th	V^{th}	Current	
Irrigation Year	2	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09		2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09		2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	
ICA in ha	4	2760							1587						6868							7180						
Designed live storage in Mm ³	c.	14.21							11.33						35.63							59.21						
Project	6	Burai							Malangaon						Panzra							Aner						
S. No.	、	57						í	58						59							60						

Annual Water	supply	ha/Mm ³ .		13	113	153	146	168	166	211		128	160	204	131	169	173	281	166	143	190	176	162	262	230	320	242	252	177	
Total recoverv	Irrigation +	Non	irrigation in Lakhs	12	7.57	7.30	18.10	18.11	12.58	13.96		6.44	4.89	3.90	4.46	3.31	4.80	4.74	2.98	14.89	13.61	31.57		5.65	6.05	16.33	15.10	17.34	17.84	
Recovery Non-	Irrigation	Rs. In	lakhs	11	2.00	2.80	8.25	13.41	9.58	11.09		1.20	2.55	0.66	1.83	0.00	0.00	0.57	0.76	8.87	8.07	27.27		2.55	3.47	12.02	13.06	14.69	13.38	
Recovery Irrigation	Rs. In	lakhs		10	5.57	4.50	9.85	4.70	3.00	2.87		5.24	2.34	3.24	2.63	3.31	4.80	4.17	2.22	6.02	5.54	4.30	3.28	3.10	2.58	4.31	2.04	2.65	4.46	
Irrigated area in ha	5			თ	1011	987	756	1281	1612	3145		1407	1532	2203	1938	2052	2513	3471	2609	2563	3089	2924	2554	2291	2417	1371	1512	1893	1897	
Water used for		in Mm ³		8	8.91	6.45	5.19	7.64	9.72	14.87		10.96	9.57	10.81	14.83	12.16	14.55	12.34	15.74	17.95	16.26	16.63	15.80	8.75	10.51	4.29	6.26	7.50	10.72	
Live Storade	as on	15th oct		7	NA	21.39	10.41	21.39	20.73	18.04		NA	12.89	12.82	12.89	12.89	12.89	33.02	33.02	33.02	33.02	33.02	33.02	16.20	16.20	16.20	16.20	16.09	16.20	
Year status				9	I st	li nd	IIIrd	Iv th	V^{th}	Current	-t-] ₂₁	li nd	IIIrd	Iv^{th}	V^{th}	Current] st	li nd	IIIrd	Iv^{th}	$\Lambda_{ m tp}$	Current] st	li nd	III rd	Iv^{th}	V^{th}	Current	
Irrigation Year				5	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09		2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	
ICA in ha	5			4	4534							3124						9726						3394						
Designed live	storage	in Mm ³		с	21.39							12.89						33.02						16.20						
Project				2	Karwand						:	Rangawali						Haranbari						Kelzar						
Sr. No.				.	61							62						63						64						

Annual Water supply	ha/Mm³.	13	199	109	143	140	181	119	1	115	96	121	109	106	103	333	125	108	105	87	59	121	162	120	66	102	73	
Total recovery Irrigation +	Non irrigation in Lakhs	12	2.00	1.56	11.49	1.37	3.09	3.50		18.67	15.90	15.60	15.00	15.44	1.21	3.36	3.48	3.09	5.67	6.30	0.04	9.99	10.50	13.27	8.59	9.64	0.98	
Recovery Non- Irrigation	Rs. In Iakhs	11	0.21	1.55	8.97	0.00	0.00	00.0		0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.64	2.77	3.71	00.0	0.00	0.00	1.57	1.63	0.02	0.00	
Recovery Irrigation Rs. In	lakhs	10	1.79	0.01	2.52	1.37	3.09	3.50		18.67	15.90	15.60	15.00	15.44	1.21	3.36	3.48	2.45	2.90	2.59	0.04	9.99	10.50	11.70	6.96	9.62	0.98	
Irrigated area in ha		6	610	1112	886	1265	1638	1372	1	2025	1940	2376	2258	2288	2173	2357	1057	1028	829	820	982	2675	3475	3060	2432	2306	1752	
Water used for irrigation	in Mm ³	8	3.07	10.23	6.18	9.05	9.03	11.55		17.62	20.21	19.71	20.64	21.66	21.02	7.07	8.43	9.48	7.90	9.45	16.65	22.02	21.41	25.52	24.47	22.65	23.97	
Live Storage as on	15th oct	7	2.34	11.24	3.99	11.24	11.24	11.24		27.46	27.46	27.46	27.46	27.46	27.46	9.54	10.21	9.93	10.10	10.19	10.11	NA	27.60	27.60	27.60	27.60	27.60	
Year status		9	l st	li nd	IIIrd	Iv^{th}	V^{th}	Current	Þ	10 I	li nd	IIIrd	I_V^{th}	V^{th}	Current] st	li nd	IIIrd	Iv^{th}	V^{th}	Current] st	li nd	IIIrd	Iv^{th}	V^{th}	Current	
Irrigation Year		5	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09		2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	
ICA in ha		4	2400							6296						4500						3914						
Designed live storage	in Mm ³	с	11.24							27.46						10.21						27.60						
Project		2	Nagyasakya						:	Alandi						Bhojapur						Adhala						
Sr. No.		~	65							66						67						68						

Annual Water supply ha/Mm ³ .	13	2	0	215	131	182	170	0	D	77	150	87	78	76	0	477	144	167	203	152	0	349	95	116	160	140	
Total recovery Irrigation + Non irrigation	in Lakhs	0.00	0.00	0.18	0.85		1.05		0.00	0.27	0.80	0.96	1.05	1.91	2.97	2.49	11.56	36.33	6.57	6.06	0.00	1.21	1.20	4.04	7.08	4.16	
Recovery Non- Irrigation Rs. In Lakhs	11	0.00	00.0	0.14	00.00	0.14	0.25		0.00	00.0	0.31	0.45	0.51	1.51	2.45	00.00	10.51	33.82	6.00	5.42	0.00	00.00	0.12	1.54	3.99	3.79	
Recovery Irrigation Rs. In Iakhs	10	0.00	00.0	0.04	0.85	0.55	0.80		0.00	0.27	0.49	0.51	0.54	0.40	0.52	2.49	1.05	2.51	0.57	0.64	0.00	1.21	1.08	2.50	3.09	0.37	
Irrigated area in ha	σ	° °	0	277	832	1117	943	C	D	506	986	602	576	500	0	1427	654	482	63	1018	0	1240	1182	1339	2137	1656	
Water used for irrigation in Mm ³	α	0.00	00.0	1.29	6.34	6.13	5.55			6.59	6.59	6.90	7.38	6.60	0.00	2.99	4.55	2.89	0.31		0.00	3.55	12.48	11.53	13.38	11.81	
Live Storage as on 15th oct	7	00.0	00.0	00.0	8.50	7.48	4.76	00	1.03	8.78	8.78	8.78	8.78	8.78	0.00	26.36	27.49	12.98	0.79	61.15	0.00	5.56	19.11	24.39	17.80	25.21	
Year status	y	l st c	li nd	IIIrd	Iv^{th}	V^{th}	Current	IST	1	li nd	III rd	Iv^{th}	Λ^{th}	Current] st	li nd	IIIrd	Iv^{th}	V^{th}	Current] st	li nd	IIIrd	Iv^{th}	V^{th}	Current	
Irrigation Year	L.	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09		2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	
ICA in ha	4	1660							0077						6944						6192						
Designed live storage in Mm ³	¢	8.50						0 1 0	۵./۵						61.16						25.21						
Project	6	5 Ghatshil Pargaon													Ekrukh						Jawalgaon						
Sr. No.	、	- 69) 1	2						71						 72						

Annual Water	supply ba/Mm ³		13	0	122	102	142	143	131	1	0	990	1100	1111	325	498	0	349	142	151	140	140	109	279	138	141	114	109	
Total recovery	Irrigation + Non	irrigation in Lakhs	12	1.55	3.74	5.58	4.81	4.46	3.72		0.03	0.00	0.08	0.47	1.82	1.87	0.00	0.92	0.30	5.63	13.13	3.68	14.32	26.27	22.07	23.62		32.87	
Recovery Non-	Irrigation Rs. In	lakhs	11	1.50	2.62	4.96	1.48	2.14	2.79		0.00	0.00	0.00	0.00	0.00	0.27	0.00	0.00	0.00	0.68	7.06	3.19	0.00	0.00	2.30	3.81		6.13	
Recovery Irrigation	Rs. In Iakhs		10	0.05	1.12	0.62	3.33	2.32	0.93		0.03	0.00	0.08	0.47	1.82	1.60	0.00	0.92	0.30	4.95	6.07	0.49	14.32	26.27	19.77	19.81	16.92	26.74	
Irrigated area in ha			ი	0	323	1409	2518	3105	1429	,	0	297	33	60	606	1061	0	487	1767	3127	2026	2997	5835	6210	6476	7063	7437	7963	
Water used for	irrigation		8	0.00	2.65	13.79	17.71	21.77	10.93		0.00	0.30	0.03	0.05	1.87	2.13	0.00	1.40	12.42	20.76	14.49	21.47	53.51	22.25	47.03	50.01		73.33	
Live Storage	as on 15th oct		7	00.0	2.44	31.97	31.97	31.97	31.97		0.40	1.88	0.00	0.00	0.00	3.70	0.00	2.00	14.11	29.94	17.40	30.40	76.90	76.90	77.96	77.96	77.96	77.96	
Year status			9] st	li nd	IIIrd	Iv^{th}	V^{th}	Current	10	۰ <u>،</u>	li nd	IIIrd	Iv^{th}	V^{th}	Current] st	li nd	III rd	Iv^{th}	V^{th}	Current] st	li nd	III rd	Iv^{th}	V^{th}	Current	
Irrigation Year			5	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09		2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	
ICA in ha			4	6592							5578						4646						9995						
Designed live	storage in Mm ³		ю	31.97							19.03						30.53						77.96						
Project			2	Hingani (p)						:	Budhihal						Mangi						Kasari						
Sr. No.			-	73							74						75						76						_

Annual Water	supply	ha/Mm ³ .		4.0		55	86	93	101	76		144	96	212	193	181	132	109	85	160	125	81	86	137	64	142	148	161	144	
Total recoverv	Irrigation +	Non	irrigation		15.62	33.67	59.60	19.43	36.22	54.73		23.39	33.55	14.42	21.52	73.72	66.71	22.22	24.77	23.10	11.85	16.96	47.92	8.47	7.37	34.65	24.20	18.25	20.50	
Recovery Non-	Irrigation	Rs. In	lakhs		00.00		15.83	5.25	22.74	15.83		13.14	13.21	13.82	16.52	39.48		00.00	00.00	3.00	7.30	13.00	38.77	00'0	00'0	14.47	4.75		4.50	
Recovery Irrigation	Rs. In	lakhs		10	15.62	21.56	43.77	14.18	13.48	38.90	10 0 7	10.25	20.34	09.0	5.00	34.24	29.07	22.22	24.77	20.10	4.55	3.96	9.15	8.47	7.37	20.18	19.45	17.36	16.00	
Irrigated area in ha				σ	2602	2536	4717	5170	5376	5146	0000	2923	2684	5080	5454	4836	4395	2088	2518	4435	4731	4268	5659	1211	1166	3040	3688	4085	4221	
Water used for	irrigation	in Mm ³		¢	39.95	46.37	55.14	55.80	53.40	67.93		20.31	28.02	23.97	28.24	26.74	33.21	19.17	29.56	27.70	37.79	52.47		8.86	18.23	21.48	24.93		29.25	
Live Storade	as on	15th oct		7	79.86	79.86	79.86	98.49	104.77	104.77		26.15	26.15	26.15	31.88	26.87	33.21	28.54	54.86	60.18	60.58	68.08	76.50	31.17	31.17	37.32	37.31	37.18	43.05	
Year status				ų	_st (lind	IIIrd	Iv^{th}	Λ^{th}	Current	द	~	li nd	IIIrd	Iv^{th}	V^{th}	Current] st	li nd	IIIrd	Iv^{th}	V^{th}	Current	l st	li nd	IIIrd	Iv^{th}	V^{th}	Current	
Irrigation Year				LC.	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	10,0000	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	
ICA in ha				4	10000							445/						9170						6863						
Designed live	storage	in Mm ³		c	104.8							33.21						76.5						43.05						
Project				6	Pataaon	>					-	Jangamhatti						Kumbhi						Chikotra						
Sr. No.				~	77						(/8						79						80						

Annual Water supply ha/Mm ³ .	13	100	163	167	251	215	210		165	90	108	112	129	106	130	115	132	138	155	206		154	290	146	173	143	0	
Total recovery Irrigation + Non irrigation in Lakhs	12	52.22	63.34	24.24	32.49		83.53		3.45	8.94	6.33	5.01	14.12	18.63	64.31	62.52	53.56	2.56	67.21	167.24		0.01	1.50	1.82	2.53	2.92	0.43	
Recovery Non- Irrigation Rs. In Iakhs	11	17.53	16.77	18.93	19.91	40.49	35.19		0.00	0.00	1.50	0.00	4.21	8.70	52.27	54.40	48.16	1.25	59.21	158.27		0.01	0.00	0.52	0.39	0.07	0.43	
Recovery Irrigation Rs. In Iakhs	10	34.69	46.57	5.31	12.58	44.83	48.34	1	3.45	8.94	4.83	5.01	9.91	9.93	12.04	8.12	5.40	1.31	8.00	8.97		0.00	1.50	1.30	2.14	2.85	0.00	
Irrigated area in ha	6	3584	7400	7372	10578	9136	10339		1333	1700	2491	1698	2961	2437	4338	2501	3166	2951	3411	6194		40	1483	740	735	803	0	
Water used for irrigation in Mm ³	ω	35.75	45.49	44.02	42.12	42.50	49.28		8.08	18.98	23.13	15.22	22.98			21.78	24.02	21.33		30.08		0.26	5.12	5.08	4.26	5.62	0.00	
Live Storage as on 15th oct	7	40.66	52.36	52.48	52.48	52.48	52.48		70.56	70.56	69.77	70.56	70.56	70.56	30.39	29.39	30.39	30.39	29.90	30.39		1.83	11.79	11.79	11.79	11.79	3.46	
Year status	9	I st	pu ^{II}	III	Iv^{th}	Λ^{th}	Current	10,	19[Ii nd	III rd	Iv^{th}	$\Lambda^{ m th}$	Current	I st	li nd	IIIrd	Iv^{th}	V^{th}	Current	10	_ اور	Ii nd	III rd	Iv^{th}	$v^{ m th}$	Current	
Irrigation Year	5	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09		2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09		2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	
ICA in ha	4	9160							9908						4468							2636						
Designed live storage in Mm ³	3	52.48							70.56						30.39							11.79						
Project	2	Chitri							Kadavi						Vadiwale							Nher						
N. No.	~	81							82						83							84						

Annual Water supply ha/Mm³.	13	150	169	109	136	187	180		0	286	420	220	148	177	0	144	136	138	116	104		0	562	158	322	156	135	
Total recovery Irrigation + Non irrigation	11 LANIS	0.33	0.40	1.17	0.95	1.75	0.80		0.00	2.92	5.75	1.29	6.32	6.38	0.00	4.69	11.55	12.94	13.00	12.34		0.00	0.47	0.68	2.25	2.78	4.40	
Recovery Non- Irrigation Rs. In Iakhs	11	00.00	0.00	0.00	0.00	0.00	00.0		0.00	0.00	0.00	0.00	00.00	00.0	0.00	0.28	5.55	5.38	3.00	1.19		0.00	0.00	00.0	0.09	0.20	0.26	
Recovery Irrigation Rs. In Iakhs	10	0.33	0.40	1.17	0.95	1.75	0.80		0.00	2.92	5.75	1.29	6.32	6.38	0.00	4.41	6.00	7.56	10.00	11.15		0.00	0.47	0.68	2.16	2.58	4.14	
Irrigated area in ha	6	167	214	259	291	309	427		0	5804	2794	2660	3357	5479	0	2475	1869	2406	1767	1578		0	1113	1246	1123	1326	768	
Water used for irrigation in Mm ³	8	1.11	1.27	2.38	2.14	1.65	2.37		0.00	20.29	6.66	12.08		30.91	0.00	17.18	13.70	17.44	15.23	15.19		0.00	1.98	7.87	3.48		5.70	
Live Storage as on 15th oct	7	3.85	6.42	4.98	6.42	6.42	6.42		5.40	23.56	8.35	14.41	44.33	44.33	1.21	24.46	24.09	24.40	24.46	24.46		0.59	4.94	13.74	13.73	13.74	12.64	
Year status	9	I st	li nd	IIIrd	Iv^{th}	V^{th}	Current	-] st	li nd	III rd	Iv^{th}	Λ^{th}	Current	l st	li nd	IIIrd	Iv^{th}	V^{th}	Current	-	l st	li nd	IIIrd	Iv^{th}	V^{th}	Current	
Irrigation Year	2	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09		2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09		2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	
ICA in ha	4	1093							4049						4049							2318						
Designed live storage in Mm ³	с	6.42							46.22						24.46							13.74						
Project	2	Ranand							Mhaswad						Tisangi							Khairy						
Sr. No.	~	85							86						87							88						

Annual Water supply	ha/Mm [°] .	13	0	120	80	105	81	93	90	00	39	33	36	23	26	19	8	47	8	5	3	0	54	74	96	87	06	
Total recovery Irrigation +	irrigation in Lakhs	12	0.00	3.71	1.12	5.88	8.00	7.77	7	00.1	1.30	0.50	2.00	1.96	1.58	0.66	5.51	0.46	11.04	6.70	5.11	0.00	0.55	37.07	35.69	28.77	14.93	
Recovery Non- Irrigation	lakhs	11	00.0	0:30	0.33	0.61	1.20	1.41		0.00	0.00	0.00	00.0	00.0	00.0	00.0	4.56	0.00	10.46	6.53	4.57	0.00	0.55	27.48	26.53	21.22	6.87	
Recovery Irrigation Rs. In	Iakus	10	00.0	3.41	0.79	5.27	6.80	6.36	00 1	00.1	1.30	0.50	2.00	1.96	1.58	0.66	0.95	0.46	0.58	0.17	0.54	0.00	0.00	9.59	9.16	7.55	8.06	
Irrigated area in ha		6	0	2276	948	3107	3722	4273	100	00 /	789	800	1000	620	680	160	180	14	199	125	72	0	1001	1834	1362	1920	1797	
Water used for irrigation	in Mm [°]	ω	0.00	18.91	11.82	29.53	46.08	45.71	70 07	13.01	20.01	24.60	27.53	26.56	25.77	8.26	23.25	0.30	24.54			0.00	18.64	24.65	14.16	22.11	19.99	
Live Storage as on		7	00.0	37.04	9.46	52.30	52.30	52.30	26.04	00.U4	35.94	33.94	35.94	33.16	34.27	27.23	27.23	26.69	27.23	26.37	26.33	0.00	19.94	32.28	20.26	32.28	32.28	
Year status		9	I st	li nd	III	Iv^{th}	V^{th}	Current	Ist	-1	li ^{na}	III rd	Iv^{th}	$\Lambda^{ m th}$	Current	I st	li nd	III rd	Iv^{th}	V^{th}	Current] st	li nd	III rd	Iv^{th}	V^{th}	Current	
Irrigation Year		5	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09		ZUU3-U4	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	
ICA in ha		4	8445						0007	4000						2050						3644						
Designed live storage	in Mm	с	52.30						20.04	50.34						27.23						32.28						
Project		2	Sina													Natuwadi						Kurnoor						
Sr. No.		~	89						Ş	ß						91						92						

Annual Water supply ha/Mm ³ .	13	0	84	163	247	235	189		0	87	155	164	222	125	178	0	124	133	190	0	0	173	0	72	86	97	
Total recovery Irrigation + Non irrigation in Lakhs	12	0.00	0.00	1.41	0.53	0.53	1.51		7.20	0.00	0.89	3.88	3.88	0.00	0.00	0.00	0.60	0.47	0.47	0.00	0.00	0.00	0.00	0.57	0.18	0.97	
Recovery Non- Irrigation Rs. In Iakhs	11	0.00	0.00	0.00	0.00	0.00	00.0		7.20	0.00	0.58	3.33	3.33	0.00	0.00	0.00	0.00	0.00	0.00	00.0	0.00	0.00	0.00	0.00	0.00	0.00	
Recovery Irrigation Rs. In Iakhs	10	0.00	0.00	1.41	0.53	0.53	1.51		0.00	0.00	0.31	0.55	0.55	00.0	0.00	0.00	0.60	0.47	0.47	00.0	0.00	0.00	0.00	0.57	0.18	0.97	
Irrigated area in ha	6	0	440	451	205	569	535		0	169	390	360	488	110	27	0	404	185	302	0	0	173	0	279	560	215	
Water used for irrigation in Mm ³	8	0.00	5.24	2.77	0.83	2.42	2.83		0.00	1.94	2.52	2.20	2.20	0.88	0.15	0.00	3.25	1.39	1.59	0.00	0.00	1.00	0.00	3.86	6.53	2.22	
Live Storage as on 15th oct	7	0.00	5.24	4.44	0.86	3.17	5.24		0.00	3.72	6.20	4.61	6.20	1.00	0.00	0.00	5.46	1.81	2.42	0.00	0.00	0.00	0.00	12.98	8.60	8.60	
Year status	9	I st	11 nd	III	Iv^{th}	V^{th}	Current	-] st	li nd	III	Iv^{th}	V^{th}	Current] st	li nd	III rd	Iv^{th}	V^{th}	Current] st	li nd	IIIrd	Iv^{th}	v^{th}	Current	
Irrigation Year	5	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09		2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	
ICA in ha	4	830							830						1584						4048						
Designed live storage in Mm ³	3	5.24							6.2						7.96						12.98						
Project	2	Khandala							Turori						Jakapur						Mehakari						
Sr. No.	-	93							94						95						96						

Annual Water supply ha/Mm³.	13	0	0	0	65	100	77		0	103	149	104	91	105	0	63	112	68	51	70	91	108	94	118	84	311	
Total recovery Irrigation + Non irrigation	12	0.00	0.00	0.00	0.04	0.04	1.31		00.00	0.00	0.03	0.37	1.07	2.43	0.00	0.00	0.35	0.25	0.76	1.40	2.79	0.05	0.82	3.28	0.80	0.00	
Recovery Non- Irrigation Rs. In Iakhs	11	00.0	00.0	00.0	00.0	00.0	0.00		0.00	0.00	00.0	0.34	1.06	1.91	0.00	0.00	0.00	00.00	00.00	00.0	0.00	00.00	00.0	2.49	00.00	0.00	
Recovery Irrigation Rs. In Iakhs	10	00.0	00.0	00.0	0.04	0.04	1.31		0.00	0.00	0.03	0.03	0.01	0.52	0.00	0.00	0.35	0.25	0.76	1.40	2.79	0.05	0.82	0.79	0.80	00.00	
Irrigated area in ha	6	0	0	0	138	312	277		0	73	109	176	170	249	0	392	424	328	367	411	1228	55	1152	816	789	934	
Water used for irrigation in Mm ³	8	00.0	0.00	0.00	2.12	3.11	3.60		0.00	0.71	0.73	1.70	1.87	2.38	0.00	6.23	3.77	4.86			13.51	0.51	12.20	6.93		3.00	
Live Storage as on 15th oct	7	00.0	00.0	00.0	5.47	5.21	5.21		0.00	2.11	2.80	8.55	8.55	8.55	0.00	13.84	NA	13.84	10.49	7.90	23.59	3.32	24.76	24.83	14.26	8.37	
Year status	9	l st	Ii nd	III	Iv^{th}	V^{th}	Current	T.	-18I	li nd	III rd	Iv^{th}	$\Lambda^{ m th}$	Current] st	li nd	III rd	Iv^{th}	V^{th}	Current] st	li nd	IIIrd	Iv^{th}	v^{th}	Current	
Irrigation Year	5	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09		2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	
ICA in ha	4	1084							1214						2200						2151						
Designed live storage in Mm ³	с	5.47							8.56						13.84						24.9						
Project	2	Kadi							Kada						Galhati						Karpara						
Sr. No.	~	97							98						99						100						

Annual Water	supply bown ³		13	116	147	114	105	78	107	(D	861	140	120	169	150	0	494	130	173	145	386	0	157	110	174	285	139	
Total recovery	Irrigation + Non	irrigation	12 12	5.53	2.35	2.25	4.33	5.96	11.00		13.00	8.06	6.94	11.49	28.17	31.84	0.00	0.00	0.80	1.80	1.80	0.07	0.00	0.12	1.32	1.28	1.88	2.20	
Recovery Non-	Irrigation Rs In	lakhs	11	2.69	2.02	2.00	2.31	4.27	10.00	00 01	13.00	8.06	6.15	9.00	24.91	28.80	0.00	0.00	0.75	1.80	1.80	00.00	0.00	0.12	00.0	00.00	0.00	00.00	
Recovery Irrigation	Rs. In Iakhs	2	10	2.84	0.33	0.25	2.02	1.69	1.00		0.00	0.00	0.79	2.49	3.26	3.04	0.00	00.0	0.05	00.0	00.0	0.07	0.00	00.0	1.32	1.28	1.88	2.20	
Irrigated area in ha			6	2235	623	1706	1776	1376	737	C	D	285	921	1032	1163	1147	0	498	208	371	530	583	0	36	552	471	379	566	
Water used for	irrigation		8	19.23	4.25	15.00	16.94	17.73	6.90		0.00	0.33	6.58	8.60	6.88	7.64	0.00	1.01	1.59	2.14	3.65	1.51	0.00	0.23	5.00	2.71	1.33	4.08	
Live Storage	as on 15th oct		7	27.13	9.34	27.13	27.13	24.50	8.99		0.81	8.69	19.39	19.63	19.39	19.66	0.00	1.90	7.04	6.47	8.41	8.41	3.74	1.47	9:56	6.06	4.21	11.26	
Year status			9	I st	puli	III rd	Iv^{th}	V^{th}	Current	ISt		li nd	IIIrd	Iv^{th}	V^{th}	Current] st	li nd	IIIrd	Iv^{th}	V^{th}	Current] st	li nd	IIIrd	Iv^{th}	V^{th}	Current	
Irrigation Year			S	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09		2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	
ICA in ha			4	2591							7001						1650						1700						
Designed live	storage in Mm ³		С	27.13						00.01	19.00						8.61						11.26						
Project			2	Masoli						F	lettia						Rui						Raigavan						
Sr. No.			~	101							Z01						103						104						

Annual Water supply ha/Mm ³ .	13	0	78	143	147	235	135		160	141	105	150	198	146	0	0	137	146	181	399	0	0	0	0	221	349	256	
Total recovery Irrigation + Non irrigation in Lakhs	12	0.00	0.00	2.47	7.04	16.75	12.80		1.16	0.19	1.18	0.69	15.88	9.30	0.00	0.00	0.03	0.06	1.45	4.50		0.00	0.00	2.26	0.01	1.04	1.30	
Recovery Non- Irrigation Rs. In Iakhs	11	00.0	00.0	0:30	2.26	9.00	09.6		0.20	0.00	0.88	0.69	13.25	5.30	0.00	0.00	00.0	00.00		3.00		00.0	00.0	2.26	00.0	0.02	00.00	
Recovery Irrigation Rs. In Iakhs	10	00.0	00.0	2.17	4.78	7.75	3.20		0.96	0.19	0.30	00.0	2.63	4.00	0.00	0.00	0.03	0.06	1.45	1.50		00.0	00.0	00.0	0.01	1.02	1.30	
Irrigated area in ha	6	0	18	908	1262	1852	1198		239	31	97	852	1095	1765	0	0	36	412	339	479		0	0	0	631	566	768	
Water used for irrigation in Mm ³	8	0.00	0.23	6.37	8.57	7.87	8.90		1.49	0.22	0.92	5.68	5.54	12.10	0.00	0.00	0.26	2.81	1.87	1.20		0.00	0.00	0.00	2.86	1.62	3.00	
Live Storage as on 15th oct	7	NA	5.60	15.66	18.49	16.28	9.79		NA	0.00	0.00	16.77	11.91	15.60	NA	0.00	1.96	4.31	4.31	4.31		NA	4.56	0.00	10.13	5.85	9.99	
Year status	9	I st	li nd	IIIrd	Iv^{th}	V^{th}	Current	7] _{S1}	li nd	IIIrd	Iv^{th}	Λ^{th}	Current] st	li nd	IIIrd	Iv^{th}	V^{th}	Current] st	li nd	IIIrd	Iv^{th}	V^{th}	Current	
Irrigation Year	5	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09		2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09		2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	
ICA in ha	4	2511							3443						1092							2712						
Designed live storage in Mm ³	3	18.49							21.25						5.21							11.53						
Project	2	Sukhna							Girja						Lahuki							Dheku						
Sr. No.	-	105							106						 107							108						

Annual Water supply ha/Mm ³ .		13	0	0	0	130	472	93		0	0	0	160	2950	188	252	242	104	271	150	0		134	123	123	241	161	238	
Total recovery Irrigation + Non	irrigation in Lakhs	12	0.00	0.00	0.00	3.39	1.09	0.80		00.00	0.00	0.75	5.50	8.36	10.90	4.59	10.71	1.68	7.50	4.32	19.70		1.57	0.75	0.45	3.89	0.35	4.20	
Recovery Non- Irrigation Rs. In	lakhs	11	0.00	0.00	00.00	3.39	1.08	0.10		0.00	0.00	0.75	4.50	7.67	10.20	0.00	6.60	1.50	4.65		19.60		0.00	00.00	00.0	00.0	00.00	2.00	
Recovery Irrigation Rs. In Iakhs		10	0.00	0.00	00.0	00.0	0.01	0.70		0.00	0.00	00.0	1.00	0.69	0.70	4.59	4.11	0.18	2.85	0.72	0.10		1.57	0.75	0.45	3.89	0.35	2.20	
Irrigated area in ha		6	0	0	0	235	85	222		0	0	0	617	118	471	830	841	196	887	54	0		277	185	295	432	249	405	
Water used for irrigation in Mm ³		ω	0.00	0.00	0.00	1.81	0.18	2.40		00.00	0.00	0.00	3.85		2.50	3.30	3.48	1.88	3.27	0.36	0.00		2.06		2.40	1.79	1.55	1.70	
Live Storage as on 15th oct		7	NA	0.00	0.39	2.84	1.14	2.92		NA	0.99	0.00	7.92	0.00	9.42	NA	10.53	4.61	11.07	3.87	3.81		NA	2.16	3.48	3.61	3.69	4.64	
Year status		9] st	li nd	IIIrd	Iv^{th}	V^{th}	Current	1] _{St}	li nd	IIIrd	Iv^{th}	V^{th}	Current] st	li nd	III rd	Iv^{th}	V^{th}	Current	-] st	li nd	IIIrd	Iv^{th}	V^{th}	Current	
Irrigation Year	I	ۍ	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09		2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09		2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	
ICA in ha		4	472							2147						2429							1180						
Designed live storage in Mm ³	(ო	3.23							11.53						11.07							4.64						
Project			Kolhi							Ambadi						Khelna							Gadadgad						
Sr. No.			109							110						111							112						

Annual Water supply ha/Mm ³ .	13	175	0	76	182	101	600		151	0	0	160	200	0	127	156	202	169	144	136	151	172	0	157	191	292	
Total recovery Irrigation + Non irrigation in Lakhs	12	2.58	0.43	3.33	9.69	6.30	27.00		2.02	0.00	0.11	2.03	3.05	3.00	1.31	0.62	1.52	1.97	1.23	3.30	0.92	0.92	0.00	0.69	2.09	0.40	
Recovery Non- Irrigation Rs. In Iakhs	11	0.00	0.43	3.30	7.89	6.22	2.00		0.32	0.00	0.11	0.75	1.46	2.50	0.00	0.00	0.00	0.00	0.76	1.40	0.00	0.00	0.00	0.00	1.72	0.30	
Recovery Irrigation Rs. In Iakhs	10	2.58	00.0	0.03	1.80	0.08	25.00		1.70	0.00	0.00	1.28	1.59	0.50	1.31	0.62	1.52	1.97	0.47	1.90	0.92	0.92	00.0	0.69	0.37	0.10	
Irrigated area in ha	ი	678	0	19	668	84	60		301	0	0	303	497	0	342	222	545	583	122	543	268	237	0	520	428	146	
Water used for irrigation in Mm ³	ω	3.88	0.00	0.25	3.66	0.83	0.10		2.00	0.00	0.00	1.89	2.48	0.00	2.69	1.42	2.70	3.45	0.85	4.00	1.78	1.38	0.00	3.31	2.24	0.50	
Live Storage as on 15th oct	7	NA	1.29	1.20	7.65	2.84	1.08		NA	1.74	0.75	6.03	4.92	2.60	NA	3.87	4.78	6.13	1.77	5.14	NA	3.67	00'0	6.30	1.60	0.00	
Year status	9	I st	pu ^{II}	IIIrd	Iv^{th}	Λ^{th}	Current	-] st	li nd	IIIrd	Iv^{th}	Λ^{th}	Current] st	li nd	IIIrd	Iv^{th}	V^{th}	Current] st	li nd	IIIrd	Iv^{th}	V^{th}	Current	
Irrigation Year	5	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09		2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	
ICA in ha	4	1576							2206						1064						1280						
Designed live storage in Mm ³	с	7.65							6.03						6.13						8.51						
Project	2	Ajantha Andhari							Jui						Jivrekha						Dhamna						
No. No.	-	113							114						115						116						

Annual Water	supply	ha/Mm ³ .		13	139	0	164	149	447	201		164	205	139	115	192	66	162	169	140	210	190	200	0	296	126	145	138	76	
Total recoverv	Irrigation +	Non	irrigation in Lakhs	12	2.39	1.26	2.11	1.58	9.07	8.10		2.13	0.59	0.73	3.42	1.64	2.80	1.39	1.79	4.79	2.95	3.26		0.00	0.00	4.22	8.35	15.92	23.18	
Recovery Non-	Irrigation	Rs. In	lakhs	11	1.44	1.26	1.53	0.00	6.45	6.40		0.00	0.00	0.00	0.00	0.00	1.70	0.00	0.00	00.0	0.00	0.49	0.00	0.00	0.00	1.96	5.49	13.36	19.80	
Recovery Irrigation	Rs. In	lakhs		10	0.95	00.0	0.58	1.58	2.62	1.70	0	2.13	0.59	0.73	3.42	1.64	1.10	1.39	1.79	4.79	2.95	2.77	4.10	0.00	0.00	2.26	2.86	2.56	3.38	
Irrigated area in ha				თ	368	0	466	526	523	703	000	368	117	334	481	402	576	680	701	950	1152	852	970	0	123	1123	1216	1093	674	
Water used for		in Mm ³		8	2.65	00.0	2.83	3.52	1.17	3.50		2.25	0.57	2.40	4.20	2.09	5.80	4.20	4.16	6.81	5.49	4.48	4.85	0.00	0.42	8.89	8.38	7.89	8.87	
Live Storade	as on	15th oct		7	NA	00.0	11.57	12.22	6.40	12.22		NA	1.84	8.47	8.47	5.37	8.30	NA	4.34	10.95	10.95	5.52	8.34	NA	2.28	12.26	17.30	11.55	18.42	
Year status				9	I st	[] Iind	IIIrd	Iv^{th}	V^{th}	Current	ţ	š	li nd	IIIrd	Iv^{th}	V^{th}	Current] st	li nd	IIIrd	Iv^{th}	Λ^{th}	Current] st	li nd	III rd	Iv^{th}	V^{th}	Current	
Irrigation Year				2	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09		2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	
ICA in ha				4	2020							1377						2064						3603						
Designed live	storage	in Mm ³		с	12.22						į	8.47						10.95						20.34						
Project				2	Kalyan						-	Kalyan Girja						Sakol						Tawarja						
Sr. No.				~	117							118						119						120						

Annual Water	supply ha/Mm ³		13	125	173	166	130	148	185	7 7 7	- 0	129	139	95	124	129	136	385	66	83	117	157	140	0	151	28	127	190	
Total recovery	Irrigation + Non	irrigation in Lakhs	12	4.85	2.53	6.33	3.08	2.41	11.21	0 60	0.00	6.13	9.22	9.65	8.34	7.10	0.96	1.35	2.35	3.19	2.31		0.45	0.06	0.71	0.25	0.28	0.95	
Recovery Non-	Irrigation Rs. In	lakhs	11	3.50	00.0	00.0	00.0	00.0	6.00	2 60	0.00	0.00	2.53	2.20	3.00	1.50	0.50	0.00	00.0	0.14			0.00	0.00	0.00	00.00	0.00	00.00	
Recovery Irrigation	Rs. In Iakhs		10	1.35	2.53	6.33	3.08	2.41	5.21	6 1 Q	0.0	6.13	6.69	7.45	5.34	5.60	0.46	1.35	2.35	3.05	2.21	1.93	0.45	0.06	0.71	0.25	0.28	0.95	
Irrigated area in ha			6	470	823	1149	1160	1195	1036	1060	000	1386	1326	1231	1440	1236	616	262	531	459	592	641	14	0	78	80	73	76	
Water used for	irrigation in Mm ³		ω	3.75	4.76	6.91	8.94		5.59	0 66			9.57	12.90	11.60	9.55	4.52	0.68	5.35	5.50	5.06	4.08	0.10	0.00	0.52	2.81	0.58	0.40	
Live Storage	as on 15th oct		7	NA	8.03	15.29	15.29	3.18	11.00	V N		22.46	22.46	22.46	21.91	22.45	NA	0.99	8.27	8.03	8.27	8.27	NA	0.00	4.76	9.64	5.59	3.18	
Year status			9	I st	li nd	IIIrd	Iv^{th}	V^{th}	Current	Ist	۲. pu	II	III rd	Iv th	V^{th}	Current] st	li nd	IIIrd	Iv^{th}	V^{th}	Current] st	li nd	III rd	Iv^{th}	V^{th}	Current	
Irrigation Year			5	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09			2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08		
ICA in ha			4	2348						VCCC	1011						1760						1364						
Designed live	storage in Mm ³		с	15.29						27 AG	01.77						8.27						13.59						
Project			2	Tiru						Charai	GIGUIN						Vati						Masalga						
Sr. No.			~	121						100	771						123						124						

Annual Water supply	ha/Mm³.	13	103	151	84	104	179	196	QE	200 100	1001	201	105	144	139	150	119	110	101	81	0	0	0	85	94	123	
Total recovery Irrigation +	Non irrigation in Lakhs	12	0.59	0.88	2.79	3.41	2.48	1.86	6 10					8.90	22.92	38.65	23.64	18.21	5.68	⁽ N	0.00	0.00	0.00	0.00	0.00	0.56	
Recovery Non- Irrigation	Rs. In Iakhs	11	00.0	00.0	00.0	0.35	00.0	00.0	6 00	2 0.00	2.02	0.00	5.43	5.20	20.07	37.63	19.86	16.30	4.11	24.09	0.00	00.0	00.0	00.0	0.00	00.00	
Recovery Irrigation Rs. In	lakhs	10	0.59	0.88	2.79	3.06	2.48	1.86	070	0.10	00.0	3.52	0.79	3.70	2.85	1.02	3.78	1.91	1.57	1.63	00.0	00.0	00.0	00.0	00.0	0.56	
Irrigated area in ha		6	203	268	399	649	627	448	011		1165	1195	787	1195	456	744	656	682	476	743	0	0	0	23	120	128	
Water used for irrigation	in Mm³	ω	1.97	1.77	4.76	6.26	3.50	2.29	202	6 4 0	10.65	15.10	7.48	8.27	3.29	4.97	5.49	6.22	4.69	9.17	0.00	00.00	00.0	0.27	1.27	1.04	
Live Storage as on	15th oct	7	ΨN	2.96	10.68	10.68	3.98	2.47	NA	30 15	37.60	37.69	37.69	37.69	ΝA	15.86	19.34	19.34	19.34	19.34	NA	2.42	00.0	1.37	1.37	1.37	
Year status		9	I st	ll nd	IIIrd	Iv^{th}	Λ^{th}	Current	Ist	1;nd	TI	$_{\rm Iv^{th}}$	V^{th}	Current	I st	pu [!] I	III	Iv^{th}	$\Lambda_{ m tp}$	Current	I st	pu [!] I	IIIrd	Iv^{th}	V^{th}	Current	
Irrigation Year		5	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-00	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	
ICA in ha		4	1882						2064	1004					5262						972						
Designed live storage	in Mm ³	ę	10.68						37 60	00.10					19.34						3.1						
Project		2	Devarjan						Kundlika	_					Wan (Beed)						Kambli						
Sr. No.		-	125						176	24					127						128						

Annual Water	supply ha/Mm ³		13	0	171	172	1308	114	87	(D	70	257	167	177	172	0	227	163	146	195	327	0	0	0	35	48	145	
Total recovery	Irrigation + Non	irrigation in Lakhs	12	0.05	0.00	0.61	42.00	4.32	3.46		0.00	0.00	0.15	0.70	3.01	1.00	0.00	0.00	0.50	0.72	1.16	0.58	0.00	0.00	0.00	1.03	1.15	0.34	
Recovery Non-	Irrigation Rs. In	lakhs	11	0.05	00.0	0.31	41.00		2.05		0.00	0.00	00.0	00.0	2.10	00.00	0.00	00.00	00.0	00.0	00.00	00.00	0.00	00.00	00.0	1.00	1.06	0.00	
Recovery Irrigation	Rs. In Iakhs		10	00.0	00.0	0:30	1.00	1.08	1.41		0.00	0.00	0.15	0.70	0.91	1.00	0.00	00.0	0.50	0.72	1.16	0.58	0.00	00.0	00.0	0.03	0.09	0.34	
Irrigated area in ha			6	0	65	1316	1308	1584	1079	¢	0	130	1755	1488	1576	1377	0	1151	970	790	870	665	0	0	0	96	151	187	
Water used for	irrigation in Mm ³		ω	0.00	0.38	7.65	1.00	13.95	12.47		0.00	1.87	6.82	8.92	8.91	7.99	0.00	5.06	5.94	5.40	4.45		0.00	0.00	0.00	2.73	3.13	1.29	
Live Storage	as on 15th oct		7	NA	0.00	15.16	17.78	13.66	16.18	< - 4	NA	2.69	13.04	13.04	13.04	13.04	NA	7.24	7.83	7.24	6.96	3.93	0.00	0.00	0.00	6.50	6.57	6.57	
Year status			9	I st	li nd	IIIrd	Iv^{th}	V^{th}	Current	द	<u></u>	li nd	IIIrd	Iv^{th}	V^{th}	Current] st	li nd	IIIrd	Iv^{th}	V^{th}	Current] st	li nd	IIIrd	Iv^{th}	V^{th}	Current	
Irrigation Year			5	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	10,0000	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	
ICA in ha			4	2024							2146						2355						1862						
Designed live	storage in Mm ³		ю	21.58							13.04						13.48						6.57						
Project			2	Chandani							Khasapur						Sakat						Rooty						
Sr. No.			-	129						0	130						131						132						

Annual Water supply ha/Mm ³ .	13	0	117	148	70	158	108	•	0	419	123	145	177	113	0	178	194	163	166	157	0	265	133	145	131	317	
Total recovery Irrigation + Non irrigation	12	00.0	0.00	0.09	0.04	0.04	0.26		0.00	0.40	0.10	0.46	0.47	0.40	0.00	0.00	0.50	0.97	1.30	1.71	0.00	0.00	0.10	0.30	0.88	0.53	
Recovery Non- Irrigation Rs. In Iakhs	11	00.0	0.00	0.00	0.00	0.00	0.00		0.00	0.40	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	00.0	0.00	0.00	0.00	0.00	0.00	0.00	
Recovery Irrigation Rs. In Iakhs	10	00.0	00.0	0.09	0.04	0.04	0.26		0.00	0.00	0.10	0.46	0.47	0.40	0.00	0.00	0.50	0.97	1.30	1.71	0.00	0.00	0.10	0:30	0.88	0.53	
Irrigated area in ha	6	0	158	24	63	155	140		0	285	400	365	430	362	0	187	665	886	1047	689	0	392	489	434	493	439	
Water used for irrigation in Mm ³	8	00.0	1.35	0.16	06.0	0.98	1.30		0.00	0.68	3.25	2.52	2.43	3.22	0.00	1.05	3.43	5.42	6.29	4.39	0.00	1.48	3.69	2.99	3.77	1.39	
Live Storage as on 15th oct	7	0.00	2.15	0.00	3.23	3.23	3.23		0.00	0.00	4.96	4.96	3.99	4.96	0.00	0.00	00.0	7.76	8.37	4.49	0.00	0.00	5.33	5.34	4.54	5.33	
Year status	9	I st	li nd	III rd	Iv^{th}	$\Lambda_{ m tp}$	Current	ţ0*	181	li nd	III rd	Iv^{th}	Λ^{th}	Current	I st	li nd	III rd	Iv^{th}	V^{th}	Current] st	li nd	IIIrd	Iv^{th}	V^{th}	Current	
Irrigation Year	5	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09		2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	
ICA in ha	4	668							906						1471						963						
Designed live storage in Mm ³	с	3.23							4.96						8.78						5.34						
Project	2	Talwar							Banganga						Khandeshwar						Ramganga						
Sr. No.	~	133							134						135						136						

Annual Water	supply	ha/Mm ³ .			13	104	0	98	112	113	136	121	140	89	100	127	102	145	315	132	114	101	96	188	0	172	214	171	149	
Total recoverv	Irrigation +	Non	irrigation	in Lakhs	12	0.14	0.51	0.81	0.71	0.00	1.54	0.20	1.33	0.20	0.01	1.55	7.53	4.09	6.79	2.32	2.49	5.30	8.30	0.23	0.12	1.10	0.49	0.13	0.00	
Recovery Non-	Irrigation	Rs. In	lakhs		11	0.00	0.00	0.09	0.00	00.0	0.00	0.00	0.00	0.00	0.00	00.0	6.69	3.76	6.21	2.00	1.62	3.58	6.69	0.00	0.00	00.0	0.00	0.00	0.00	
Recovery Irrigation	Rs. In	lakhs			10	0.14	0.51	0.72	0.71	00.0	1.54	0.20	1.33	0.20	0.01	1.55	0.84	0.33	0.58	0.32	0.87	1.72	1.61	0.23	0.12	1.10	0.49	0.13	0.00	
Irrigated area in ha					о	685	0	535	609	609	610	689	462	283	482	558	423	552	400	377	413	440	403	620	0	719	703	178	176	
Water used for	irrigation	in Mm ³			8	6.57		5.45	5.43	5.38	4.49	5.71	3.31	3.18	4.80	4.41	4.13	3.80	1.27	2.86	3.62	4.38	4.19	3.29	0.00	4.18	3.29	1.04	1.18	
Live Storade	as on	15th oct			7	ΝA	2.83	8.80	8.47	8.47	8.47	8.38	5.36	8.10	8.21	8.12	8.12	6.54	3.51	6.39	6.56	6.45	6.45	4.51	0.00	4.78	3.05	0.81	1.29	
Year status					9	I st	li nd	IIIrd	Iv^{th}	$\Lambda^{ m th}$	Current	I st	li nd	III	Iv^{th}	Λ^{th}	Current	I st	li nd	III rd	Iv^{th}	Λ^{th}	Current	l st	li nd	IIIrd	Iv^{th}	V^{th}	Current	
Irrigation Year					5	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	
ICA in ha					4	830						1377						960						784						
Designed live	storage	in Mm ³			ი	8.81						8.38						6.56						4.78						
Project					2	Dongargaon (Nanded)						Loni						Nagzari						Mahalingi						
Sr. No.					~	137						138						139						140						

Annual Water supply ha/Mm ³ .	13	96	110	89	113	112	159	151	204	143	218	167	128	84	214	112	111	166	130	159	225	136	182	167	199
Total recovery Irrigation + Non irrigation	IN LAKNS 12	2.43	0.50	3.71	2.71	2.46	0.53	0.21	1.75	0.25	1.27	0.98	7.42	6.00	12.36	4.20	3.92	7.19	11.33	5.76	6.62	2.04	2.33	3.39	5.06
Recovery Non- Irrigation Rs. In Iakhs	11	0.00	00.0	0.00	0.00	0.00	0.00	0.00	0.96	0.00	00.0	0.42	5.66	3.76	12.33	3.25	2.73	5.95	8.38	2.84	6.51	1.68	1.87	2.68	3.47
Recovery Irrigation Rs. In Iakhs	10	2.43	0:50	3.71	2.71	2.46	0.53	0.21	0.79	0.25	1.27	0.56	1.76	2.24	0.03	0.95	1.19	1.24	2.95	2.92	0.11	0.36	0.46	0.71	1.59
Irrigated area in ha	6	658		736	916	807	46	505	284	515	685	529	484	578	521	445	621	557	543	1126	479	725	1259	372	301
Water used for irrigation in Mm ³	80	6.88	6.88	8.28	8.07	7.21	0.29	3.35	1.39	3.60	3.14	3.16	3.77	6.90	2.43	3.96	5.61	3.35	4.17	7.06	2.13	5.35	6.93	2.23	1.51
Live Storage as on 15th oct	7	9.04	9.04	9.03	9.04	9.04	2.86	4.35	2.05	4.35	4.35	2.18	4.29	11.01	6.59	11.01	11.01	7.91	7.78	10.16	3.65	10.41	10.41	5.31	3.65
Year status	9	I st	Ii nd	III rd	Iv^{th}	v^{th}	Current	I st	li nd	IIIrd	Iv^{th}	Λ_{tp}	Current	I st	li nd	III rd	Iv^{th}	V^{th}	Current	I st	li nd	III rd	Iv^{th}	v^{th}	Current
Irrigation Year	5	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09
ICA in ha	4	1478						567						1780						1012					
Designed live storage in Mm ³	ε	9.04						4.35						11.01						10.41					
Project	2	Pethwadaj						Kudala						Karadkhed						Kundrala					NOTE .
Sr. No.	.	141						142						143						144					

NOTE :

1 Change in col.No.3 of designed live storage in respective years if any is due to revision in designed live storage capicity 2 In col. No.8 of water used for irrigation is more than col.No. 7 of live storage as on 15th Oct. of respective year is due to water utilisation in kharif.

3 Col.No.9 of irrigated area is more than Col.No.4 of ICA is due to increase of area in kharif seasion. 4 Zero value in col. 13 due to non availability of water for irrigation.

Chapter 8

BENCHMARKING OF WATER AND LAND MANAGEMENT INSTITUTE (WALMI), AURANGABAD (2008 – 09)

8.0 INTRODUCTION

WALMI, Aurangabad (Maharashtra) is a premier training institute of its kind in India established on 1st October 1980 as an autonomous registered society under Water Resources Department, Government of Maharashtra for imparting the training in IWM.

8.1 Objectives

The main objectives of the institute are:

- To provide in-service training of interdisciplinary nature to staff engaged in Irrigation Water Management and Land Development in Water Resources and Agriculture Departments
- Action and adaptive research pertaining to Irrigation Project Commands.
- Providing consultancy services, production of training materials (in print and electronic media), conducting seminars / workshops and organizing farmers' training programmes

Training is imparted by highly qualified, experienced and well-trained faculty members. WALMI has five faculties:

- Faculty of Engineering
- Faculty of Agriculture
- Faculty of Science (Computer Applications & Hydraulics)
- Faculty of Social Sciences
- Faculty of Integrated Watershed Development & Management

An optimal mix of core faculty and senior field officers on deputation to WALMI constituting the faculty, is one of the vital factors of this institute's strength and performance.

8.2 BENCHMARKING OF WALMI

8.2.1 Performance Indicators

The benchmarking technique is introduced for the performance evaluation of the irrigation systems in the State of Maharashtra. Benchmarking is a continuous process of measuring one's own performance and practices against the best competitors and is a sequential exercise of learning from other's experience. The guidelines are available on the categories of performance indicators for Irrigation Systems. The benchmarking of WALMI, Aurangabad, which is a premier training institute in IWM is carried out by developing the performance indicators based on the activities of the institute. The performance is also compared with the requirement wherever possible. WALMI, being a training institute, has developed its own performance indicators as below:

- 1) Institutional performance
- 2) Qualitative performance
- 3) Financial indicators
- 4) Environmental aspects

8.2.2 Institutional Performance

The institutional performance of the WALMI is assessed based on the following four indicators:

a) Strength of teaching staff

The strength of teaching staff is compared with the potential sanctioned positions and available positions over the period of last five years.

b) Annual training workload (trainee days)

The annual training workload is compared with the planned training workload and achievement for last five years.

c) Annual training workload of long term courses (Participants)

The number of participants actually participated in long term courses (25/21 week's duration) are compared with the potential strength of the long term courses for last five years.

d) Annual Farmers' training workload (Participants)

The number of participants actually participated in different farmer's training programmes are compared with the expected participants.

8.2.3 Qualitative Performance

The overall quality of institute's activities is assessed based on the following indicators:

- a) End of Course evaluation (i) L.T.C. (ii) S.T.C.
- b) Research activities
- c) Revisions & Development of publications
- d) Papers presented & published (state, national & international level)

8.2.4 Financial Indicators

This is assessed based on the actual expenses of the institute:

- a) Cost of training per trainee day
- b) Central Assistance for training programme

8.2.5 Environmental Aspects

Environmental indicators will give information about involvement of participants in the training activities to acquire the knowledge, skills and attitudes for their jobs. It will also indicate the conduciveness of environment in the institute.

a) Referencing WALMI Library b) Visitors in WALMI

8.3 ASSESSMENT OF PERFORMANCE OF WALMI (YEAR 2004 – 2009)

(i) Strength of teaching staff

The strength of teaching staff is almost constant ranging in last five years and is ranging between 25 to 27 as against the sanctioned strength of 47. The existence of sizeable core faculty is one of the vital factors of this institute's strength and performance. (Fig.1)

(ii) Annual training workload (trainee days)

Achievement in last five years is more than the planned training workload. The average planning of the last eight years is about 30000. The actual achieved training workload is ranging in between 30000 - 34537. In almost all the years the achieved is more than the planned. (Fig.2)

(iii) Annual training workload of long term courses (participants)

The number of participants actually attended in LTC for all the years were more than the potential strength (Fig.3). This is because of efforts taken by the Institute and making it mandatory for all the nominated participants.

(iv) Annual Farmers' training workload (participants)

This indicator shows that the number of farmers participated in the courses are much higher than the expected participants (Fig.4). In all the years, the participation of farmers in the training programmes is increasing due to more thrust is given to farmers training programmes by the Institute.

(v) End of course evaluation

In the method of end of course evaluation, the trainee officers are asked to give rating for various questions related to training. The average rating of end course evaluation for long term courses and short term courses (having period more than 4 days) during the year is around four, which indicates that overall quality of training as excellent (Fig.5)

(vi) Research activities

This activity is now taken up as supplemental activities along with the training activities of the Institute. (Fig.6).

(vii) Revisions & Development of publications

This can not be assessed exactly on yearly basis. The fig.7 shows the actual status of this activity.

(viii) Papers / Articles presented & published (state, national & international level)

The numbers are in increasing order and are highest during the year 2008 – 09. The average publications of papers/articles published by the faculty are around 28 per year (Fig.8). The faculties are being motivated in this regard.

(ix) Cost of training per trainee day


The cost of training per trainee day is different in the different years and depends upon the number of trainee days (annual training workload) and the budget allotment. (Fig.9). This includes the expenditure on administration and maintenance of institute's estate. The average cost of training in last five years is around Rs. 3,900 per trainee day.


(x) Referencing WALMI Library


This indicates that use of library is increasing among the faculties, training participants and visitors (Fig.10).


(xi) Visitors in WALMI


The visitors in WALMI are increasing year after year which is a good indicator for the capabilities of the WALMI (Fig.11).





























Appendix-I

Abstract of guidelines issued by GOM for Benchmarking of Irrigation Projects

Government of Maharashtra, Water Resources Department vide Letter No. CDA 1004/(369/2004) CAD (works) dated 08.11.2004 issued guidelines while preparing Benchmarking report for the year 2003-04. Subsequently, additional instructions for the year 2004-05 were issued vide letter No. CDA 1004/ (369/2004) CAD – works dated 2.9.2005. Following procedure is adopted for preparation of Benchmarking report (2008-09) based on guidelines.

- Benchmarking is taken in hand after validation of data and linking it with water audit data and data submitted to Government for Irrigation Status Report 2008-09.
- 2) All Projects included in report for 2007-08 are considered for 2008-09.
- Indicators No. IX Man days for O & M per unit area is deleted as per suggestion of core group.
- 4) In equity performance the head, middle and tail reaches are decided dividing the command area in to three equal parts.
- 5) Potential Utilised and Created is linked with availability of water. Effective potential of each project is decided based on availability of water for irrigation during the year.
- 6) Agricultural output is calculated at 1998-99 prices.

The five year average values from 2003-04 to 2006-07 and values for 2007-08 are considered for comparison, for all the indicators. Absurd (nil or very high values) are not considered while calculating the average.

Revenue means the actual recovery from Irrigation, non-irrigation water cess, fishery, galper, tourism etc.

Appendix-II

State target values for indicators 2008-09

Fixing Target Values:

The State targets set for indicators mentioned in Chapter IV were introduced from the year 2002-03 and are decided based on studies and past performance. It is obvious that project size, available water storage in reservoir and agro-climatic, geographical, social conditions are different for different regions. Therefore, there will be difference in performance of irrigation projects but to improve overall State performance and for simplicity, single target for each indicator for the State is defined. Performance of projects in a circle against each indicator is collective performance.

In 2003-04, the values of some of the indicators are revised and for financial indicator of output per unit irrigated area and output per unit irrigation water supply, fixed prices of 1998-99 are considered to obviate effect of price rise. Also, for better monitoring and looking to the number of projects, the analysis is carried out considering irrigation circle as a unit and projects therein within similar plan groups of sub-basins.

The State target values set for Indicator I, III & IV are different; for different categories of the projects viz. (a) major & medium, (b) minor. For other Indicators, the targets are uniform for all types of projects.

I) Annual Irrigation Water Supply per Unit- Irrigated Area:

Irrigation system performance in Rabi and Hot weather season is 150 ha/Mm³ and 110 ha/Mm³ respectively. As there are Rabi and Hot weather crops in most of the major and medium project, average Irrigation system performance is (<u>150</u> +110)/2=130 ha/Mm³

Thus the water requirement per unit area = $1000000/130 = 7692 \text{ m}^3/\text{ ha}$.

In case of minor project as there are no crops irrigated in Hot weather the water requirement per unit area = $100000/150 = 6666.67 \text{ m}^3/\text{ ha}$. Say 6667 m³/ ha.

Hence in broad sense the water requirement per unit area works out to 7692 m³ per ha. in case of major and medium projects and 6667 m³ per ha. in case of minor projects.

II) Potential Created and utilized:

Utilization of created potential depends upon availability of water for irrigation. This availability further depends upon available yield & extent of Non Irrigation uses. Therefore, percentage of water available in the reservoir that can be used for irrigation should be the target for the project. The availability of water in different reservoirs is taken from water audit data for the year 2008-09.

III) Output per unit area:

The target is decided based on five years experience in 2004-05. The same targets are used for 2008-09.

The category wise values for different plan groups are as follows.

	Plan group	Major	Medium	Minor
	Highly deficit	21000	23000	16000
	Deficit	23000	25000	21000
	Normal	26000	25000	21000
	Surplus	25000	31000	27000
	Abundant	32000	40000	36000
IV) Output p	er unit Water Supp	lv:		
		·)·		
	Plan group	Major	Medium	Minor
		•	Medium 2.80	Minor 2.40
	Plan group	Major		
	Plan group Highly deficit	Major 2.69	2.80	2.40
	Plan group Highly deficit Deficit	Major 2.69 2.99	2.80 3.15	2.40 3.15
	Plan group Highly deficit Deficit Normal	Major 2.69 2.99 3.38	2.80 3.15 3.15	2.40 3.15 3.15

V) Cost Recovery Ratio:

Target is same for all categories and it is 1.

VI) Total O & M Cost Per Unit Area:

Total O & M cost includes maintenance cost as well as operation cost of the irrigation system. M & R charges are considered as per Govt. norms and establishment charges are taken for staff working in a section office for irrigation water management.

	Major	Medium	Minor
M & R	200	150	100
Establishment charges	1050	1050	1050
Total	1250	1200	1150

VII) Total O & M Cost Per Unit Water Supplied:

Total O & M cost per unit water supplied for irrigation and non-irrigation use is considered as follows.

Major	Medium	Minor
	(4000/7000) 0.40	(4450/0007) 0.47

(1250/7692) 0.16 (1200/7692) 0.16 (1150/6667) 0.17

VIII) Revenue Per Unit of Water Supplied:

The targets are fixed 10 percent more than O & M cost per unit of water supplied.

Major	Medium	Minor
0.18	0.18	0.19

The State targets for Revenue per unit of water supplied for irrigation is kept as Rs. $0.18/m^3$, however, for NI use the target is Rs. $0.9/m^3$ as charges of NI use are higher than irrigation use.

IX) Mandays For O & M Per Unit Area:

The Indicator is deleted.

X) Land Damage Index:

There is no target for this indicator. However, the percentage of land damaged to total ICA of the project should be minimum for all the projects.

XI) Equity Performance (head, middle and tail)

The head, middle and tail reaches is decided based on dividing the command in to 3 equal parts.

XII-I) Assessment Recovery Ratio (Irrigation)

State target is 1

XII-NI) Assessment Recovery Ratio (Non-Irrigation)

State target is 1

							Appendix-III	ll-xi						
				Overvi	Overview of Pr	rojects selected for Benchmarking	ected for I	Benchma		(Major Projects)	ects)			
Plan Group	Circle/ Project	Avg. Annual		Designed		Year of Commence	Culturable Command	Irrigable command	Live Storage	No. of villages in	Avg. farm	Main crops	Area covered under WUA Ha	rered JA Ha
/SB		Rainfall	L ive	Water use	Water	ment of				benefit	size		Dronocad Handed	рарисн
°Z		mm	Storage	for	use for	Irrigation	5	5	on 15th	zone	Ha		neendouu	over
			Mm ³	Irrigation	Non				October 2008					
				Mm	lirrigation Mm ³				0007					
-	2	3	4	5	6	7	8	6	10	11	12	13	14	15
Highl	Highly deficit													
	CADA Solapur													
18A ^A	18AA Bhima	500	1517.20	1444.70	116.43	1977	198035	182683	1675.14	384	1 to 2.5	Sorghum, Wheat, Groundnut. Sugarcane	119609	27309
Deficit	it						-					2		
	AIC Akola													
9	Katepurna	950	86.35	49.45	32.65	1972	11187	8325	15.40	30	1.5 to 2	1.5 to 2 Wheat, Peas, Cotton, Sunflower.	11187	7166
6	Nalganga	737	69.32	53.21	6.51	1963	9165	8604	19.11	31	1 to 2	Gram, Wheat, Cotton	9165	7493
	CADA Aurangabad													
5	Jayakwadi (PLBC)	755	2171.00	1064.96	329.04	1975-76	183560	141640	2170.94	355	1.5 to 2	Cottton, Wheat, Sorghum, Sunflower		
	CADA Beed												118070	47482
7	Jayakwadi (PRBC)	700	2171.00	331.39	29.68	1976-77	53910	41682	0.00	66	1.57	Cotton,Wheat,Sorghum, Sugarcane		
2	Majalgaon	840	312.00	680.28	46.88	1989-90	64295	54737	312.00	132	1 to 2	Wheat, Sorghum, Cotton, Sugarcane	21929	10597
4	Manjra	685	173.32	185.64	85.67	1980-81	23690	18223	176.96	80	2.03	-op-	5147	3259
4	Lower Terna	710	113.95	62.50	21.05	1997-98	14513	11610	91.22	63	1 to 1.5	Sorghum, Wheat, Sunflower, Groundnut, Gram	Q	
	CADA Jalgaon								-					
5	Girna	743	525.06	549.66	0	1962-63	79293	69350	484.59	195	3	Sugarcane, Banana, Cotton, Wheat, Sorghum	15936	116
	CADA Nashik													
5	Chankapur	1067	76.85	146.59	0	1973	19173	14042	76.85	48	0.5	Bajri, T wo seasonals, Paddy, Sorghum, Groundnut, Wheat, Gram	1861	0

	e	4	5	9	7	8	6	10	11	12	13	14	15
	910	80.79	275.18	54.37	1990	37785	28340	80.02	46	2.06	-op-	1069	0
	685	890.22	732.33	68.67	1968-69	78485	57988	267.05	232	1 to 2	Cottton, Wheat, Sorghum	24459	4486
	850	138.21	198.06	5.94	1968	27745	23310	39.22	96	1.55	Wheat, Gram, Sugarcane, Cotton, Groundnut, Sorghum	4523	4523
BIPC Buldhana											- - - - - -	-	
	891	81.96	78.57	20.08	1998-99	22525	15100	72.30	54	1.5	-op-	22525	11675
YIC Yavatmal													
	913	169.92	121.65	15.62	1995	24135	20515	23.87	73	2 to 3	Cotton, Wheat, Sugarcane	24135	366
	945	91.26	100.35	19.06	1972	13678	8215	75.85	40	1.5 to 3	Sugarcane, Sorghum, Wheat, Gram, Cotton, Groundnut.	11814	0
CADA Jalgaon													
	743	255.00	500.12	90.53	1983	47360	37838	255.00	82	1.2	Sugarcane, Banana, Groundnut	7282	0
CADA Nashik													
Bhandardara	3175	304.10	419.00	0	1926	63740	23077	328.10	110	4 to 5	Sorghum, Wheat, Grass, Maize, Sunflower, Sugarcane	0026	705
	500	608.92	540.27	87.90	1972	138792	82920	608.92	160	4 to 5		91719	28668
	746	60.32	31.59	2.19	1985	14856	10400	60.32	35	0.8	Wheat, Sorghum, Gram	7849	2143
	661	21.40	82.90	46.85	1976	60704	43154	21.24	144	0.8	Gram, Sorghum	50345	14144
	964	72.20	36.53	3.50	1981	9642	6750	70.86	23	0.6	Paddy, Onion, Vegetables, Groundnut, Bajri, Wheat, Gram, Sorghum	9557	9429
	550	202.43	135.73	66.67	1918	88822	33170	202.43	146	2	Sugarcane, Sorghum, Bajri, Wheat, Gram, Fruits	7906	6691
	500	159.42	86.78	117.07	1954	21900	15960	158.54	92	1.3	ф	3239	1834
	533	52.91	61.96	8.46	1997	15523	10117	52.91	42	0.47	-do-	465	345

-	2	e	4	5	9	2	8	6	10	11	12	13	14	15
	CADA Pune													
17	Kukadi (Complex)	062	864.39	951.29	0	1978	224699	156278	759.11	269	0.8 to 1	Wheat, Sorghum, Bajri, Vegetables, Sugarcane, Groundnut, Gram	57358	29369
17	Ghod	515	154.80	202.86	2.54	1965	41460	20500	154.80	54	-	Sugarcane, Sorghum, Bajri, Wheat, Grain	12155	301
	CIPC Chandrapur													
2	Bor	1327	127.42	109.29	6.35	1967	24055	13360	57.44	77	1.5 to 2	Cotton, Wheat	18169	10761
	NIC Nagpur													
2	Lower Wunna	1330	189.18	148.00	29	1991	21591	19500	126.84	109	2.5	Cotton, Wheat, Gram, Soybean, Sugarcane	17325	413
	NIC Nanded													
9	Upper Penganga	825	964.09	782.69	15.16	1984-85	139438	125495	411.27	356	1 to 2	Cottton, Wheat, Sorghum,	23589	7355
	PIC Pune													
17	Khadakwasla (Complex)	911	808.65	602.55	204	1970	83302	62146	800.57	96	0.5 to 5	Sorghum, Bajri, Maize, Wheat, Sugarcane	83302	3180
17	Pawana	2210	241.11	96.50	168.32	1975	7468	6365	241.22	30	0.5 to 2.5	Paddy, Sorghum, Bajri, Maize, Wheat, Sugarcane	Q	
18	Bhatghar Dam N.L.B.C.	1953	666.00	386.58	33.92	1893	68767	60656	665.57	87	1 to 2	Sorghum, Wheat, Bajri, Sugarcane	68767	1252
18	N.R.B.C. (Veer Dam)	1067	266.44	860.99	0	1938	181266	65506	266.44	214	1.7	Sugarcane, Sorghum, Bajri, Wheat, Other Perenials	181266	390
	UWPC Amravati													
2	Upper Wardha	840	548.14	302.78	99.72	1994-95	83300	75000	288.39	279	1.5	Cotton, Wheat, Hy. Jowar, Chilli, Groundnut	83300	340
Surplus	us													
	CADA Nagpur													
∞	Bagh (Complex)	1325	268.96	214.44	0	1971	0	0	76.06	0	1 to 2	-do-	29703	3511
Ø	Pench	1138	1374.00	689.00	243	1976	126913	101200	658.17	407	1 to 2	Paddy, Cotton, Chilly, Wheat, Gram, Sunflower, Soybean	126913	11180
8 Itiac	Itiadoh dant	1336	318.86	412.04	0	1971	22752	17500	51.75	100	1 to 2	Paddy	22752	2123
	CADA Pune													
15	Krishna	872	602.73	602.73	0	1978-85	81400	74000	602.73	146	1 to 2	Sugarcane, Sorghum, Wheat, Gram	30058	8243
						-			-			עעווכמו, כומוו	-	

-	2	в	4	5	9	7	ω	6	10	11	12	13	14	15
	CIPC Chandrapur													
6	Asolamendha	1147	56.38	52.00	0	1918	37945	9919	12.66	67	1.5 to 2 Paddy	Paddy	10317	0
ი	Dina	1315	67.54	55.94	0	1974	12494	7826	3.04	99	1.5 to 2	-do-	12494	0
	SIC Sangli													
15	Radhanagari	3638	219.97	203.87	24.35	1955	35422	26560	214.67	91	0.5 to	0.5 to Sugercane, Paddy, Wheat,	47288	366
											1.5	Vegetables		
15	Tulashi	1870	91.92	91.92	42.50	1978	5711	4720	91.92	23	0.5 to 2	-do-	4495	0
15	Warna	2092	779.35	578.05	6.46	1986-87	123463	96919	746.52	332	0.8	-do-	148972	0
15	15 Dudhganga	2636	679.11	622.11	57	1993-94	46976	38388	678.09	125	1 to 2	1 to 2 Sugarcane, Paddy, Wheat	61032	2000
	TIC Thane	-		_							_		-	
21	Surya	2286	285.31	145.42	31.06	1981-82	30547	14696	175.43	64	0.25	Paddy	400	0
21	Bhatsa	2589	942.10	511.86	389.03	1985-86	29378	23000	787.26	149	0.39	-do-	DN	
22	Kal-Amba	3020	528.13	156.41	54.70	1973-74	9558	7965	405.21	127	0.20	-do-	351	0
	ND= No Data													

-						-	0	0	1							0	0			0	
.	red under (ha)	Handed		16					No Data	No Data	No Data	No Data	No Data	No Data	0	270			No Data		No Data
	Area covered under WIJA (ha)	Proposed	L L L	15			540	300	No Data	No Data	No Data	No Data		No Data	296	628	617	1017	No Data No Data	697	ta
	Main crops			14			Groundnut, Sorghum, Sunflower, Wheat	Sorghum, Sunflower, Wheat, Pulses	ę	Soghum, Wheat, Groundnut, Sugarcane, Maize, Sunflower	Soghum, Wheat, Groundnut, Sugarcane, Sunflower	Soghum, Wheat, Groundnut, Sugarcane, Maize, Sunflower	ę	Groundnut, Sorghum, Sunflower, Wheat	-op-	Groundnut, Sugarcane, Sorghum, Sunflower, Wheat	Soghum, Wheat, Groundnut, Sugarcane, Maize, Sunflower	Groundnut, Sorghum, Sunflower, Wheat	Sorghum, Wheat, Vegetables, Sucarcane	-0-	Soghum, Wheat, Groundnut, Sugarcane, Maize, Sunflower
	Avg. tarm size	3120 (ha)		13			1 to 3	2 to 3	2 to 3	1 to 1.5	0.5 to 4	1 to 1.5	2 to 3	1 to 3	2 to 3	2 to 3	1 to 1.5	1 to 3	1 to 1.5	2 to 3	0.5 to 1.5
:	No. of villages in	benefit	zone	12			5.00	10.00	4.00	5.00	4.00	5.00	15.00	10.00	2.00	9.00	8.00	7.00	5.00	9.00	4.00
Projects)	of farmers villages in			11			545	1716	1500	1407	578	1013	1372	810	1300	4331	2780	585	1059	923	530
g (Medium	Storade		on 15th October 2008	10			4.96	16.18	0.00	8.55	5.21	1.37	13.04	4.49	5.24	32.28	8.60	5.33	9.88	3.93	3.23
3enchmarkin	Irrigable	area	(ha)	6			906	2024	1584	1214	1084	972	2146	1471	830	3644	4048	963	1862	2355	668
Overview of Projects selected for Benchmarking (Medium Projects)	Culturable	Area	(ha)	8			964	2891	1600	1804	1190	1047	3575	1710	1328	6414	5007	1017	1943	3140	760
of Projects s	Year of Commence	ment of	Irrigation	7			1975	1966	1979	1970	1965	1958	1954	1981	1974	1968	1966	1977	1938	1994	1960
Overview	Water use	for Non	irrigation (Mm ³)	6			0.59	3.11	0.00	0.18	0.00	0.00	2.55	0.00	0.00	4.81	0.00	0.00	0.48	0.00	0.00
	Water use	for Irrigation	use (Mm ³)	5			6.35	20.59	7.43	8.38	5.47	3.10	13.30	11.28	5.24	32.18	12.98	6.50	6.09	15.17	3.23
	Designed Live	Storage	(Mm ³)	4			4.96	21.58	7.96	8.56	5.47	3.1	13.04	8.78	5.24	32.28	12.98	5.34	6.57	13.48	3.23
	Annual	Rainfall	(mm)	е			685	270	770	589	589	589	770	685	770	270	589	685	589	770	589
i	Circle/ Proiect			2	Highly Deficit	CADA Beed	Banganga	Chandani	Jakapur	Kada	Kadi	Kambli	Khasapur	Khendeshwar	Khandala	Kurnoar	Mehakari	Ramganga	Rooty	Sakat	Talwar
i	Plan droun/	SB No		-	Highly		19	19	19	19	19	19	19	19	19	19	19	19	19		19

-	2	e	4	5	9	7	8	6	10	11	12	13	14	15	16
19	Turori	770	6.2	5.73	1.70	1984	006	830	1.00	006	8.00	2 to 3	-9-	No Data	No Data
	CADA Solapur														
19A	Mangi	500	30.40	27.50	0	1966	4000	3117	17.40	1577	21	0.5 to 4	Sorghum, Groundnut. Sugarcane, Maize, Sunflower	931	
19	Ekrukh	500	61.15	43.21	15.95	1871	6858	2610	0.79	2000	5	1 to 1.5	Sorghum, Wheat, Vegetables, Sugarcane	No Data	No Data
18 AA	18 AA Buddhihal	500	27.95	15.08	0.00	1966	5448	4251	00.0	1883	ω	0.5 to 1.5	Sorghum, Wheat, Groundnut, Sugarcane, Maize, Sunflower	5444	0
19	Hingni (P)	500	32.00	37.83	1.68	1977	6482	5629	32.00	5000	15	1 to 1.5	-do-	5714	2228
19	Javalgon	500	29.18	29.37	6.15	1997	5372	5341	17.80	4500	13	1 to 1.5	-qo-	4635	1245
	PIC Pune			ſ	ſ										
19	Khairy	682	13.74	17.83	0	1989	2718	2318	12.64	1150	14	2	Sorghum, Bajri, Wheat, Groundnut	2318	0
16	Nher	508	11.79	11.79	0	1886	4324	2636	3.46	3440	18	-	Bajari, Sorghum, Wheat other Non Perennial	4324	0
19	Sina	562	52.3	67.09	0.2	1984	9677	8445	52.3	9500	26	-	Sorghum, Bajri, Wheat, Maize, Kadwal	8445	0
18	Mhaswad	533	46.21	46.21	0	1881	5804	4049	44.33	2500	1	-	Sorghum, Bajri, Groundnut	5804	0
18	Ranand	538	6.42	1.83	0	1953	3886	1093	6.42	1100	9		Kadwal, Wheat, Sorghum	3886	0
18 Deficit	Tisangi	508	24.46	24.46	0	1965	5068	4049	24.46	2697	0	~	Sorghum, Bajri,	5132	0
	AIC Akola														
10	Dnyanganga	732	33.93	33.80	8.69	1971	4494	4249	20.10	2962	21	1.5 to 2	Wheat, Gram, Cotton	4494	158
10	Mas	696	22.04	21.48	8.09	1982	6107	4415	7.85	2900	22	2 to 3	-ob-	6100	0
7	Morna	827	41.46	46.50	0.00	1972	6464	4633	8.65	2228	29	1 to 3	Wheat, Gram, Cotton, Hy.Jawar	6539	1935
7	Nirguna	812	28.85	34.50	0.00	1979	6377	5836	14.48	4574	20	1 to 2	Wheat, Gram, Cotton, Hy.Jawar, Groundnut	6377	2565
10	Paldhag	766	7.51	10.40	0.37	1978	3082	1932	7.56	1534	14	1 to 2	Wheat, Gram, Cotton	3032	563
10	Shahanur	1440	46.04	41.12	12.45	1990	9330	7466	32.93	7347	47	1.27	Cotton, Sorghum, Wheat, Gram, Orange	9330	0
10	Uma	818	11.68	10.23	0.92	1982	3007	2241	0.24	1996	21	1 to 3	Wheat, Gram, Cotton, Hy.Jawar	3007	267
	BIPC Buidnana	101	00 00	07.17	000	1000.00	LOTO	1001	1	0100		L C		1010	0
6	Mun	761	36.83	45.10	0.00	1992-93	9735	7804	17.50	2782	32	2.5	Cotton, Chilly, Sunflower	9735	0
10	Torna CADA Aurandahad	711	7.9	7.75	0.11	1994-95	1725	1465	6.91	753	7	2.5	-qo-	1725	0
1	Alintha Andhari	650	7.65	5.27	2.38	1984	1967	1578	1.08	500	e	3.93	-0-	294	0
e	Dhamna	677	8.51	8.34	0.15	1973	1682	1280	-1.32	510	æ	2.5	-do-	696	0

16	1449	No Data	278	0	0	0	0	No Data	0	0	510	0		No Data	0				287		0		0	No Data	No Data			No Data	0	2625		0			
15	1449	No Data	2309	1318	434	850	1655	No Data	590	484	805	1735		No Data	3542				287		1664		1370	No Data	No Data			No Data	100	2625		1005			
14	-op-	Sorghum, Wheat, Cotton, Tur	-op-	-do-	ę	-qo-	Wheat, Sorghum, Sunflower	- 0 -	ę	-op-	- 0 -	-op-		Sorghum, Wheat, Gram, Sunflower	Sugarcane, Groundnut,	Sorghum, Cotton,	Maize, Paddy, Vegetable, Wheat,	Gram	Sugarcane, Groundnut,	Sorghum, Bajri, Cotton, Sunflower	Sorghum, Bajri, Cotton, Sunflower,	Groundnut	-do-	-op-	Sorghum, Chilli,	Groundnut, Maize, Paddy,	Vegetables, Wheat, Gram	Sorghum, Sunflower Wheat	Sugarcane	Sorghum, Chilli, Groundnut, Maize,	Paddy, Vegetables, Wheat Gram	Sorghum, Chilli,	Groundnut, Maize, Paddy,	Vegetables,	Wheat, Gram, Fodder
13	1.77	1 to 2	0.77	2.5	2.5	3	ę	1.5	4.08	0.96	1.5	2.73		2.04	2.10				3.91		1.73		1.30	1.20	2.18			1.72	1.50	1.40		2.15			
12	4	12	10	9	14	ი	6	7	1	4	7	14		7	14				13		11		8	7	7			19	ი	14		7			
11	820	1200	4447	908	880	800	420	1980	1210	1384	2067	1150		920	1347				1009		260		1261	250	945			2105	1469	1741		829			
10	4.64	7.90	15.60	5.14	2.60	12.22	8.30	8.37	3.31	4.31	8.99	9.79		2.47	22.45				37.69		3.18		11.26	8.61	8.34			18.42	19.66	11.00		8.27			
6	1180	2200	3443	1064	2206	2020	1377	2151	2429	1092	2591	2511		1882	2834				2964		1364		1700	1650	2064			3603	1652	2348		1760			
8	1448	2812	3443	2589	2636	2693	1557	2862	4935	1323	3502	3136		2853	3542				3927		1678		2267	1893	2174			4907	1928	2654		1809			
7	1971	1964	1990	1964	1960	1986	1972	1974	1967	1977	1982	1968		1997	1969				1988		1996		1992	1994	1996			1983	1964	1978		1983			
9	0.67	4.34	6.57	0.00	2.00	3.03	0.00	2.80	6.33	1.59	3.94	1.93		0.00	0.00				0.33		0.00		0.28	1.72	0.00			3.92	4.81	0.00		0.00			
5	3.97	7.08	14.66	6.14	6.22	7.35	8.42	21.03	4.74	3.72	23.44	16.56		7.12	23.78				37.83		11.54		8.57	5.80	8.40			10.98	10.84	21.19		9.93			
4	4.64	13.84	21.25	6.13	6.03	12.22	8.47	24.9	11.07	5.31	27.13	18.49		10.680	22.460				37.690		13.590		11.260	8.610	10.950			20.340	19.663	15.290		8.270			
3	840	598	762	668	647	567	663	760	650	688	780	688		838	716				753		673		770	770	850			744	0//	684		880			
2	Gadadgad	Galhati	Girija	Jivrekha	Jui	Kalyan	Kalyan Girija	Karpara	Khelna	Lahuki	Masoli	Sukhana	CADA Beed	Devarjan	Gharni				Kundlika		Masalga		Raigavhvan	Rui	Sakol			Tavarja	Terna	Tiru		Vhati			
-	11	7	е	ო	ო	ო	ю	e	m	m	7	e		4	4				7		4		4	4	4			4	4	4		4			

-	2	e	4	5	9	7	8	6	10	11	12	13	14	15	16
4	Wan	533	19.34	19.31	7.64	1967	7125	5262	19.34	4630	52		Sorghum, Wheat, Sunflower, Cotton, Groundnut	265	0
	CADA Jalgaon														
11		743	2.76	2.90	0.58	1987	960	605	2.76	375	e	0.75	-q-	480	0
13 AA	Bhokarbari	694	6.54	8.15	0.00	1993-94	1790	1205	3.14	603	5	1.5	-op-	No Data	No Data
13 AA Bori	Bori	694	25.15	31.30	7.08	1985-76	6504	4553	25.15	2277	15	2	-op	839	0
13 AA Burai	Burai	200	14.21	19.23*	0.87	1984-85	2981	2760	14.21	2524	2	~	Wheat, Cotton, Gram, Bajri, Sorghum, Onion,	1297	155
													Maize		
13 AA	13 AA Kanoli	660	8.45	10.50	0.00	1974-75	1620	1363	8.45	1500	œ	1 to 2	Wheat, Cotton, Gram, Bajri, Sordhum	449	0
1	Hiwara	810	9.6	12.30	0.00	1997	2923	2231	9.60	608	e	0.8	, 6	1580	0
11	Manyad	750	40.27	45.30	00.0	1973-74	6500	4864	40.55	4245	12	7	Sugarcane, Banana, Cotton	1908	0
13 AA	13 AA Rangavali	1055	12.89	23.05*	0.00	1983-84	5130	3134	12.89	1400	21	2 to 2.5	Sorghum, Wheat, Cotton, Vegetables	1261	0
13 AA	13 AA Tondapur	763	4.64	4.77	0.85	1998	1597	1060	0.98	712	2	0.8	-0-	380	0
	CADA Nashik									-					
	G.Pargaon	685	8.5	12.36	0.00	1984	2142	1660	4.76	1792	15	3 to 4	-op	747	0
11	Haranbari	795	33.02	47.66	0.00	1988-89	12966	9726	33.02	11150	55	0.5	Paddy, Sorghum, Groundnut, Wheat, Gram, Sugarcane	632	491
	Kelzar	687	16.2	16.51	0.00	1988-89	5583	3394	16.22	2594	19	0.5	Bajri, Two seasonals, Paddy, Sorghum, Groundnut, Wheat, Gram	630	630
11	Nagya Sakya	528	11.24	13.72	0.00	1992.93	2400	2400	11.24	2125	,	0.5	Paddy, Sorghum, Groundnut, Wheat, Gram, Sugarcane	0	0
	NIC Nanded														
	Karadkhed	650	11.01	11.34	6.56	1976	2510	1780	7.78	1298	1	1.93	-do-		1652
2	Kudala	700	4.35	5.54	1.38	1974	676	567	4.29	428	5	1.23	-do-	No Data	No Data
4	Kundrala	630	10.41	12.81	4.21	1981	1265	1012	3.65	784	7	1.61	Wheat, Gram, Sugarcane, Cotton, Groundnut, Sorghum	1277	1277
4	Mahalingi	775	4.78	4.06	1.68	1980	1015	784	1.29	568	9	1.8	-do-	1449	784
4	Pethwadaj	850	9.04	13.52	1.31	1977	1970	1478	2.86	1985	13	-	-do-	No Data	No Data
Norma	VIC Vevatmal														
9	Adan	798	67.25	69.67	11.14	1979	10067	7804	3.81	14000	32	0.56	Cotton, Tur, Sugarcane, Groundnut	10067	0
7	Nawargaon	1067	12.47	13.28	2.71	1999	2574	2056	12.34	2680	15	0.56	-do-	2574	0

16		3028	0	127	0	,	0	764		0	0	0		0	0	0	0	0	3639		0		0	0	0	0
15		3028	2625	5067	6740	2	3239	3293		1467	580	472		580	2154	1899	647	1231	5124		2000		1512	1837	500	2427
14		Groundnut, Cotton, Sorghum, Wheat, Gram, Pulses	Wheat, Gram	Cotton, Sorghum, Wheat, Groundnut	Sugarcane.	Cotton, Sorghum, Wheat, Gram, Pulses, Vegetables	Cotton, Sorghum, Wheat, Gram, Pulses, Vegetables	Hy. Jawar, Sunflower, Cotton,	wneat, Gram	þ	-þ	-op-		-op-	Wheat, Groundnut, Cotton	- 0 -	- 0 -	Maize, Bajra, Wheat	Groundnut, Pulses, Sorghum, Cotton		Wheat, Cotton, Orange, Gram, Vegetables		Sorghum, Wheat, Grass, Bajri, Groundnut, Maize	Vegetables, Grapes, Sorghum, Sugarcane, Wheat, Gram	Bajri, Wheat, Sorghum, Gram	Sorghum, Wheat, Grass, Maize, Sunflower, Sugarcane
13		1.5 to 3	1 to 2	1 to 2	2 to 4	2	1.5 to 3	1 to 2		2.26	2.07	3.02		0.8	0.5	0.4	0.5	0.8	6.0		1.33		3 to 4	ю	1.7	3 to 4
12		9	11	26	29	1	8	46		10	15	4		2	10	14	15	25	ω		10		16	8	24	15
11		980	1700	4125	1653		1132	2347		1050	1725	350		450	3402	2200	2675	6500	1467		279		3646	2000	4000	2830
10		1.69	9.29	1.90	54.34		27.18	0.00		11.43	9.99	2.92		6.02	59.21	18.04	11.33	35.63	39.85		12.39		27.60	27.46	10.11	8.78
6		2271	2429	4061	6600		3116	2447		2147	2712	472		1115	7180	4534	1587	6868	5128		1214		3914	6296	4500	2266
8		3028	2625	5067	7606		3895	3496		2375	3564	1056		1403	9201	7027	2674	7328	8647		2000		6427	7408	4580	2833
7		1992	1964	1981	1990		1972	1981		1979	1961	1967		1985	1976	1968	1972	1976	1985		1968		1977	1985	1973	1983
9		0.35	0.76	0.00	2.42		4.38	00.0		2.50	5.60	0.60		0.00	8.50	0.62	0.00	0.71	0.00		11.55		0.00	5.67	2.55	0.00
5		10.86	9.08	15.12	70.50		24.77	17.95		6.92	6.55	2.63		7.13	*62	21.39	15.02	72.66*	45.47		9.49		38.74	21.00	8.15	13.16
4		6.61	11.97	20.7	59.63		27.18	16.92		9.42	11.53	3.23		6.02	59.21	21.39	11.32	35.63	39.85		21.64		27.6	27.46	10.22	8.78
в		988	986	660	852		1098	860		650	600	600		750	026	960	780	780	774		1100		500	614	393	600
2	AIC Akola	Borgaon	Ekburji	Koradi	Lower Pus		Saikheda	Sonal	CADA Aurangabad	Ambadi	Dheku	Kolhi	CADA Jalgaon		Aner		_	Panzara	Suki	CADA Nagpur	Wunna	CADA Nashik	Adhala	Alandi	Bhojapur	Mand Ohol
~		ဖ	9	9	9	•	Q	10		-	-	-		13 A	13 A	13 A	13 A	12	13 A		2		~	~	-	-

16	0	0	1974	0	No Data	1008	0		0		679	0	0	617	0	0	0	0	0	0		0	0	0	0	0	0	0	0	0
15	3771	2024	2667	10910	No Data	1008	665		5564		2566	1266	9839	10117	13246	3378	9709	937	112267	3144		8088	3512	3390	1423	1030	1305	1194	1553	1902
14	Wheat, Cotton, Gram	Wheat, Cotton,	Cotton, Wheat	-qo-	-0-	-ob-	-0-		Paddy, Wheat		Paddv	-op-	- 0 -	-op-	ç	-0-	HW Groundnut, Cotton, Soybean, Wheat, Gram, Vegetables	-op-	-op-	Cotton, Wheat, Gram, Orange,	Sugarcane, HW Groundnut, Soybean, Vegetables.	, þ	Paddy, Cotton, Chillies, Wheat, Sorghum, Gram, Soybean, Veoetables	-0-	Orange, W heat, Gram, Vegetables, Cotton	Paddy, Chillies, Wheat, Gram, Soybean, Sunflower.	ę	-þ-	-op-	Wheat, Cotton, Orange, Gram, Vegetables, Groundnut
13	1.5 to 2	1.5 to 2	1.5 to 2	1.5 to 2	1.02	1.8	4.68		0.15 to 1		0.85	0.75	0.21	0.9	0.35		n	1.6		1.5		2.1	1.33	0.35	2.1	2.18	0.75		0.75	5
12	22	11	14	33	7	5	9		26		10	4	36	40	25	21	3	7	31	14		43	29	11	ω	12	7	7	8	ω
11	1280	725	1375	1821	1788	561	269	-	4415		1296	672	6283	8274	1210	2929	7121	126	6400	1829		2829	2625	1006	406	754	1044	1409	943	749
10	16.24	7.35	9.82	50.03	8.12	8.47	6.45		30.39		0.13	0.00	1.75	0.10	0.98	2.63	18.00	0.63	1.23	8.68		17.65	4.08	4.04	0.93	3.33	0.65	0.16	0.00	4.76
6	2962	2024	1822	8948	1377	830	960		2000		1798	1315	4047	6271	4047	3167	33/1	780	6109	2610		5940	5477	1700	1315	862	870	1094	933	1195
8	4710	2024	2262	10910	1835	1008	1260		5564		1887	1266	14665	10117	13246	3378	c184	937	11271	3810		8088	5835	3390	1423	1044	1305	1536	1553	1802
7	1981	1987	1976	1984	1981	1983	1983	-	1990		1974	1989	1917	1916	1917	1976	9/61	1976	1915	1987		1984	1980-81	1970	No data	1974-75	1977	1969	1972	1971-72
9	0.00	0.00	0.00	0.00	0.91	0.00	2.92		0		0.00	0.00	2.73	0.00	0.00	0.00	4.13	0.00	0.00	0.00		1.21	1.45	0.00	0.05	2.15	0.00	0.46	0.00	0.00
5	19.52	5.87	8.43	34.72	9.51	11.55	6.18	:	22.18		4.11	3.67	16.45	28.87	20.80	16.82	22.03	4.28	12.22	29.54		41.23	27.37	7.83	4.91	14.51	5.86	8.87	5.73	5.85
4	24.48	7.35	10.39	34.72	8.38	8.81	6.56		30.39		4.535	3.666	19.73	28.87	22.04	21.46	20.49	3.93	16.48	23.81		31.32	25.9	7.05	4.95	13.14	3.57	3.868	5.733	5.14
e	1218	1103	1103	1100	1150	1150	1150		2845		1146	1186	1281	1200	1267	1384	1004	979	870	963		978	963	1609	1016	1290	1138	1281	1255	1064
2			Т	Pothral NIC Nanded				- L	Vadiwale	CADA Nacinitr					Т		Kannolibara	Kesarnala	Khairbanda	Khekranala		Kolar			Mordham	Pandharabodi	Rengepar			
-	~	~	~	~	9	9	9	!	17	Snidine	0	8	ø	80	∞	ø	x	8	8	ø		00	ω	8	œ	ω	8	8	8	ø

16	0
15	3181
14	Orange, Wheat, Gram, Vegetable, Cotton
13	2.1
12	15
11	106
10	0.73
6	2604
8	3181
7	1974-75
9	0.02
5	8.25
4	8.262
3	1016
2	Chandrabhaga
٢	ω


16		0	0			608	0	0		0		0		0	0			0	0		0			0			No Data
15		2565	884			608	4961	2329		2050		6833		9160	4457			9066	<u> 9</u> 995		9170			10000			No Data No Data
14		-do-	Paddy, Wheat			-op-	Paddy	-do-		0.02 to 0.05 Paddy, Groundnut, Pulses, Mango		Sugercane,	Paddy, Wheat, Vegetables	-do-	Sugercane,	Maize,Chilly Wheat,Potato,	GrouNo Datanut	-do-	Sugercane,	Paddy, Wheat	Sugercane, Wheat	Groundnut,	Sunflower	Sugercane, Paddy Wheat			-9-
13		1.5 to 2	1.5 to 2			1.5 to 2	1.5 to 2	1.5 to 2		0.02 to 0.05		1 to 2		0.55	0.1			0.8	1 to 1.5		0.10 to 1			1 to 2		400	0.25
12		14	12			6	65	23		18		27		54	10			52	61		51			44		Paddy	17
11		1.12	8.799			328	7181	3097		3629		1326		2590	8000			2211	3197		1773			3525		0.20	1526
10		13.66	8.80			4.39	2.77	0.97		26.33		37.18		52.73	26.87			70.56	77.96		68.08			104.77		35	33.16
6		2056	1500			631	3846	1888		2050		5630		5850	3700			9219	5458		8711			8100		0.00	2044
8		2565	1946			972	12868	5035		2139		6833		9160	4450			9908	9995		9170			10000		2542	3066
7		1983	1983			1974	1923	1922		1984	-	2001		2001-02	1996-97			2001	1989		2001			1996		3050	1984.85
9		0.00	0.00			0.00	0.00	0.00		0.00	-	0.00		0.00	6.84			0.00	0.00	-	1.68		_	26.19		1958-59	0.00
5		9.28	11.98			3.17	35.00	4.29		27.23		43.05		64.45	26.37			70.56	61.57		74.81			78.58		0.00	35.94
4		21.58	19.87			4.44	43.16	10.23		27.230		43.06		52.73	33.21			70.56	77.96		76.5			104.77		32.00	35.938
3		1205	1285			1100	1285	1147		3632		1074		1524	2190			3418	4560		4985			3486		339.140	2540
2	CIPC Chandrapur	Chandai	8 Chargaon	ant	CIPC Chandrapur	Dongargaon(Wardha)	Ghorazari	Naleshwar	KIC Ratnagiri	Natuwadi	SIC Sangli	Chikotra		Chitri	Jangamhatti			Kadavi	Kasari		Kumbhi			Patgaon	TIC Thane	Rajanala	Wandri
٢	-	8	ø	Abunda	-	7	6	6		23		15 0			15 ,				15		15			15	ĺ	1	21

				Overvie	ex of Projects	s selected for	Overview of Projects selected for Benchmarking (Minor Projects)	ng (Minor Pr	ojects)				
Plan Group/	Circle/ Project	Avg.	Designed	Designed	Designed	Year of	Culturable	Irrigable	Live Storage	No. of	Avg. farm	Main crops	Area
SB No		Rainfall	Storage	tor Irrigation	for Non	ment of	Area	area	15th October	benefit	(ha)		over to
		(mm)	(Mm ³)	(Mm3)	irrigation (Mm3)	Irrigation	(ha)	(ha)	2008	zone			WUA (ha)
-	2	e	4	5	9	7	8	6	10	11	12	13	14
Highly Deficit													
	CADA Beed												
19	Bagalwadi	685	1.33	1.65	0	1971	441	340	1.33	с	1 to 3	Sorghum, Groundnut. Wheat Sunflower	0
19	Inchama	589	1.93	1.93	0	1971	615	555	1.93	7	0.5 to 4	Sorghum, Groundnut,	No Data
												Sugarcane, Maize Sunflower	
19	Kini	589	1.24	1.24	0	1967	385	380	1.24	ю	0.5 to 4	Sorghum, Groundnut, Sugarcane, Maize	No Data
												Sunflower	
19	Titraj	685	1.14	1.47	0	1985	367	275	1.14	б	1 to 3	Sorghum, Groundnut. Wheat Sunflower	No Data
	Cada Solapur												
19	Pathari	500	11.62	10.63	0.99	1905	1012	647	11.62	~	0.5 to 4	Sorghum, Groundnut. Sugarcane, Wheat, Sunflower	0
18 AA	18 AA Padawalkar wadi	500	2.12	2.12	0.00	1973	458	352	0.24	2	1 to 1.5	-do-	458
	PIC Pune												
19A Deficit	Chincholi patil	500	2.17	2.17	0	1977	569	455	2.17	e	0.83	Sorghum, Grain, Sunflowar, Maze	0
e	Ancharwadi-1	737	2.34	2.66	0	1985	607	370	0.25	7	1 to 2	Wheat, Gram, Cotton	No Data
10	Jamwadi	1196	2.16	2.16	0	1978	580	406	1.45	4	1 to 2	Wheat, Gram, Cotton, Sorghum	0
10	Mozari	695	2.93	2.35	0	1977	675	475	0.00	5	1 to 2	Wheat, Gram, Cotton, Hy.Jawar.	928
10	Shekdari	911	4.56	4.88	0	1981	1975	1331	1.17	2	1.2	Cotton, Sorghum, Wheat, Gram, Orange.	1208
10	Vyaghra	747	7.14	7.86	1.35	1991-92	1993	1615	2.19	ø	1.5	Cotton, Chilly, Sunflower	40

-	2	e	4	5	9	7	8	6	10	11	12	13	14
	BIPC Buldhana												
	Adol	850	11.89	7.06	2.45	1991-92	1506	1585	3.22	10	3.0	-do-	329
10	Brahamanwada	753	6.18	6.08	0.00	1995-96	1495	1196	2.93	4	3.0	Cotton, Chilly, Sunflower	0
	Kardi	766	4.89	5.52	0.00	1991-92	1197	958	0.00	∞	1.5	Cotton, Chilly, Sunflower	40
	Masural	776	8.25	7.88	2.92	1990-91	841	734	1.00	പ	1.0	Cotton, Chilly, Sunflower	0
	Mohagavan	800	5.86	4.14	0.52	1998-99	1048	206	0.34	ъ	3.0	Cotton, Chilly, Sunflower	190
	Sawakhed Bhoi	66	3.7	2.61	0	1988-99	589	445	3.78	2	3.0	Cotton, Chilly, Sunflower	589
	Shivan kd.	793	4.18	2.58	0	1995-96	712	605	0.33	9	2.0	-op-	0
	Vidrupa	590	3.41	0.00	0.00	1990-91	1020	840	3.41	9	1.5	Cotton, Chilly, Sunflower	0
10	Vishwamitri	772	10.01	13.91	1.25	1993-94	1882	1392	7.37	7	3.0	-do-	0
	CADA Aurangabad												
	Tandulwadi	653	1.994	1.99	0.00	1972	566	474	1.99	ĸ	1.15	Wheat, Sorghum, Cotton, Gram Groundnut	No Data
	CADA Beed												
	Bhutekarwadi	855	2.870	3.37	0	1969	1013	808	2.87	4	1.90	Sorghum, Chilli, Maize, Vegetables, Wheat, Cotton	809
	Dhanori	770	1.389	1.41	0	1974	467	343	0.35	-	1.10	Sugarcane	No Data
	Hiwarsinga	675	1.280	1.27	0	1989	299	257	0.86	~	1.16	Sorghum, Bajri, Cotton, Sunflower, Groundnut	No Data
	CADA Jalgaon												
	Bambrud	743	2.18	1.97	0	1975	579	461	0.00	-	0.8	-op-	No Data
	Chavdi	482	4.38	4.38	0	1972	388	323	2.04	7	1 to 2	Wheat, Gram, Onion, Groundnut	323
11	Dudhkheda	6350	3.366	3.37	0	1972	480	303	3.37	4	0.4	Wheat, Cotton, Gram	0
	Galan	743	1.87	2.01	0	1968	425	340	1.87	-	0.75	Cotton, Groundnut	No Data
	Hatgaon-1	743	1.4	1.52	0	1974-75	441	267	1.26	~	1.5	Cotton, Vegetables	No Data
	Kunzar-2	743	1.01	1.21	0	1991-92	223	178	0.45	-	1.5	-do-	0
	Waghala-1	743	1.21	1.21	0	1976-77	313	223	1.10	~	1.5	-do-	No Data
	Wakdi	743	0.98	0.93	0	1975	228	183	0.49	-	0.8	-op-	No Data

-	c	¢		4	ų	~	0	c	4		¢	, ,	
-	CADA Nashik	2	r	2		-	5	0	2	=	2	2	t
4	Kuttarwadi	618	1.46	2.12	0	1993	370	297	1.46	2	2 to 3	Sorghum, Wheat, Grass, Bajri, Groundnut, Maize,	No Data
	NIC Nanded												
4	B.Hipperga	850	2.05	2.93	0	1973	481	481	2.05	3	2.09	-do-	No Data
	Daryapur	875	1.028	1.57	0	1973	230	222	0.00	з	1.35	-do-	230
2	Koshtewadi	850	0.77	1.05	0	1966	190	190	0.38	÷	1.05		No Data
	Panshewadi	850	1.58	2.02	0	1975	320	263	1.58	с	1.16	-do-	No Data
	Purjal	830	2.656	2.66	0	1975	631	558	0.00	4	0.9		601
	Wasur	830	0.88	1.18	0	1971	213	171	0.39	7	3.32	Wheat, Gram, Sugarcane, Cotton, Groundnut,	213
Norma													
	YIC Yavatmal												
9	Majara	924	3.23	2.50	0	1994	1425	1269	3.23	9	2.5 to 3	Cotton, Tur, Wheat	0
	AIC Akola												
٥	Singdoh	714	1.22	1.22	0	1976	246		0.07	m	1 to 2	Wheat, Gram, Cotton, Hy. Jawar.	0
	CADA Nashik												
-	Mahirawani	600	2.52	2.52	0	1974	949	576	2.52	ი		Wheat, Gram Kh.Vegetables	No Data
	PIC Pune												
17	Rahu	364	9.79	9.79	0	1993	2300	1887	9.79	ъ	0.5 to 5	Sorghum, Bajri, Wheat, Maize, Vegetables, Paddy, Sugarcane	No Data
18	Tambve	500	4.85	4.85	0	1968	1354	750	4.85	7	0.4	Bajri, Sorghum, Kadwal	No Data
	CIPC Chandrapur												
~	Bhatala	1175	1.55	1.40	0	No Data	415	350	1.55	e	1.5 to 2		0
2	Ashti	1100	1.62	1.36	0	1965	455	364	0.72	4	1.5 to 2	Wheat, Cotton, Gram	No Data
	NIC Nanded												
9	Hirdi	82	1.34	1.34	0	1983	353	283	1.34	2	0.9	-do-	No Data
٥	Nichpur	1150	2.2	2.26	0.32	1973	525	385	2.15	N	4.77	Wheat, Gram, Sugarcane, Cotton, Groundnut, Sorghum	No Data
9	Pimprala	750	2.43	3.39	0	1968	749	672	1.39	5	2.2	-do-	0
9	Pota	650	1.67	2.13	0	1972	718	432	0.07	4	3.43	-do-	No Data
9	Sawana	804	2.154	1.65	0.51	1979	431	410	1.88	e	-	-do-	431
5	Amthana	755	1.16	1.47	0	1966	413	344	0.00	4	2.9	þ	No Data

	-	2	e	4	5	9	7	8	6	10	1	12	13	14
OD Magnut Imagnut	Surplu	s												
adbhadiga 1284 2.99 2.95 0.19 1975 800 1265 1012 1.16 6 2 Mneut, Gram, Mneut, Mneut, Mneut, Gram, Mneut, Mneut, Mneut, Gram, Mneut, Mneut, Mneut, Gram, Mneut, Mneut, Mneut, Mneut, Gram, Mneut, Mn		CADA Nagpur												
undapar 1214 4.75 7.0 1990 1265 1012 1.76 6 2 Padoly Chilly, Interaction min 1190 2.021 1.98 0 1983 526 405 1.15 5 6 0 Nineat, Gram min 1190 2.021 1.98 0 1983 526 405 1.15 5 6 0 Nineat, Gram PC Chandrapur 1287 2.01 1.990 1.97 2.021 1.960 2.015 2.015 2.015 2.045 PC Chandrapur 1283 0 1979 421 2.00 3.680 2.660 405 1.07 5 60 2.05 406 406	∞	Bhadbhadya	1284	2.89	2.85	0.19	1975	800	674	1.84	e	1.11	Paddy	No Data
ani 1190 2.021 1.98 0 1983 5.26 405 1.15 5 0.05 40- bit 1267 2.03 2.88 0 1992 442 402 1.15 5 0.05 40- per Chandrapur 1283 3.42 3.41 0 No Data 344 315 5 0.05 40- per Chandrapur 1283 3.42 3.43 315 3.42 402 1.17 5 0.05 40- per Chandrapur 1283 3.42 0 1979 4.21 200 3.68 2 1.5 0.05 60- per 3800 3.680 2.35 0 1979 4.21 200 3.68 2 1.5 0.05 60- per 1260 4.47 6 1.47 6 0.5 Pady, per 13200 1.46 1.46 0 194465	8	Urkudapar	1214	4.75	4.75	0	1980	1265	1012	1.76	9		Paddy, Chilly,	No Data
mi 1190 2.021 1.98 0 1992 442 405 1.15 5 6 -00- ni 1267 2.03 2.88 0 1992 442 402 1107 5 0.085 -00- ni 1267 2.03 2.88 0 1992 442 402 1107 5 0.085 -00- no 1283 3.42 3.41 0 No Data 344 315 3.42 4 1.510 Pady, no 1283 3.42 3.41 0 No Data 344 315 3.42 341 16													Wheat, Gram	
Initial 1267 2.03 2.88 0 1992 442 402 107 5 0.85 do- PC Chandrapur 7		Wani	1190	2.021	1.98	0	1983	526	405	1.15	5	5	-do-	No Data
FC chandragur i		Wahi	1267	2.03	2.88	0	1992	442	402	1.07	5	0.85	-do-	No Data
CIPC Chanterput	Abund	ant												
Lagam 1283 3.41 0 No Data 344 315 3.42 4 15 to 0.05 coont, facanu, fac		CIPC Chandrapur												
NIC Ramagiri <	ი	Lagam	1283	3.42	3.41	0	No Data	344	315	3.42	4	1.5 to 2	Paddy,	No Data
Shiwal 3800 3.580 2.35 0 1979 421 200 3.68 7.15 0.0.0 Coconut. NKIPC Thane 1 1 1 1 1 1 1 1 1 1 0.0 1 1 1 1 1 1 1 0.0 1		KIC Ratnagiri												
NKIPC Thate NKIPC Thate NKIPC Thate Notestand Aresand, Pepper. NKIPC Thate 2200 4.478 4.20 0 1984-85 457 340 4.47 6 0.5 Padyi. Panchanadi 3320 1.46 1.46 0 1984-85 114 91 1.46 0.5 Padyi. Panchanadi 3320 1.46 1.46 0 1984-85 114 91 1.46 0 5 Padyi. Panchanadi 3320 1.46 1.46 0 1984-85 114 91 1.46 0 5 Padyi. Panchanadi 3320 1.46 1.46 0 1984-85 114 91 1.46 0 5 Padyi. Panchanadi 3320 1.46 1.46 0 1984-85 1178 1 1.46 0 5 Padyi. Panchanadi 1400 1.784 1.78 0 198 1.46 0	23	Shirwal	3800	3.680	2.35	0	1979	421	200	3.68	2).15 to 0.05	Coconut,	0
NKIPC Thane Spices, Paddy NKIPC Thane 2200 4.478 4.20 0 1984-85 457 340 4.47 6 0.5 Paddy, Dhasai 2200 4.478 4.20 0 1984-85 114 91 1.46 0 Paddy, Panchanadi 3320 1.46 1.46 0 1984-85 114 91 1.46 0.5 Paddy, Panchanadi 3320 1.46 1.46 0 1984-85 114 91 1.46 0 Paddy, Panchanadi 3320 1.46 1.9 1984-85 114 91 1.46 3 0.2 Bendy, Sic Sangli 1400 1.784 1.78 1.78 1.46 0 1996 366 1.78 1 1.5102 Sorpum, Benkee 1158 1.84 0 1996 270 1.81 1.502 201 Moddy, In													Arecanut, Pepper,	
NKIPC Thane N <th< td=""><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td>Spices, Paddy</td><td></td></th<>													Spices, Paddy	
Minication 2200 4.476 4.20 0 1984-85 4.57 340 4.47 6 0.5 Paddy, regetables & fritts Panchanadi 3320 1.46 1.46 0 1984-85 114 91 1.46 3 0.2 Paddy, regetables & fritts Panchanadi 3320 1.46 1.46 0 1984-85 114 91 1.46 3 0.2 Paddy, fritts Panchanadi 3320 1.46 0 1984-85 114 91 1.46 3 0.2 Paddy, fritts Storbardi 3320 1.46 0 1984-85 114 91 1.46 3 0.2 Paddy, fritts Benikre 1400 1.784 1.78 1.78 1.76 3 0.2 Paddy, fritts Benikre 1158 1.84 0 1990 358 286 1.78 1 1.510 2001 1.400 Tobesplar 1158 1.84 0														
Dhasai 2200 4.478 4.20 0 1984-85 457 340 4.47 6 0.5 Paddy, Vegetables & Funits Panchanadi 3320 1.46 1.46 0 1984-85 114 91 1.46 3 0.5 Paddy, Vegetables & Funits Panchanadi 3320 1.46 1.46 0 1984-85 114 91 1.46 3 0.2 Beetlenut, funits Benikre 1400 1.784 1.78 0 1984-85 114 91 1.46 3 0.2 Beetlenut, funits Benikre 1400 1.784 1.78 0 1984-85 1.46 3 0.2 Beetlenut, funits Benikre 1400 1.784 1.78 0 1984 1.46 3 0.2 Beetlenut, Wheat CADA Pune 1.40 1.784 1.84 0 1996 306 270 1.81 1.5102 Sorphum, Wheat CADA Pune 247 2.419 </td <td></td>														
	21	Dhasai	2200	4.478	4.20	0	1984-85	457	340	4.47	9		Paddy, Vegetables &	No Data
													fruits	
SIC Sangli Image: Marce marc marce ma	22	Panchanadi	3320	1.46	1.46	0	1984-85	114	91	1.46	ო	0.2	Beetlenut, Coconut, Paddy	No Data
Benikre 1400 1.784 1.78 1.78 1 1.5 to 2 Sorghum, Groundhut, Neat CADA Pune 1400 1.784 1.78 1.78 1.78 1.76 2 Sorghum, Groundhut, Neat CADA Pune 158 1.84 0 1996 306 270 1.81 2 0.1 Paddy, Sorghum, Groundhut, Neat Thoseghar 1158 1.84 0 1996 306 270 1.81 2 0.1 Paddy, Sorghum, Groundhut, Neat Thoseghar 1158 1.84 0 1996 306 270 1.81 2 0.1 Paddy, Sorghum, Antestin, Thoseghar 3223 4.190 0 1996 206 213 3 0.3 0.3 0.3 0.3 Kondgaon 3872 3.641 3.64 3.64 5 NA -do- Kondgaon 3872 3.641 3.64 5 NA -do- Sorghum 3.77 2.000 2.173 <		SIC Sangli												
ADA Pune Figure Groundnut, Neest CADA Pune 1.84 1.84 0 1996 306 270 1.81 2 0.1 Paddy, Sorghum Thoseghar 1158 1.84 1.84 0 1996 306 270 1.81 2 0.1 Paddy, Sorghum Thoseghar 2472 2.400 1.62 0 1974 216 1.81 2 0.1 Paddy, Sorghum Bhoj 2377 2.4190 4.19 0 1976-77 126 105 4.19 4 0.35 -do- Khandpe 2377 2.000 2.00 1974-77 126 105 4.19 4 0.20 Paddy Khandpe 2377 2.000 2.00 1976-77 126 105 2.10 1.76 4 0.20 Paddy Khandpe 2377 2.000 2.00 1976-77 126 105 2.00 2.40 40- Molkhurd	15	Benikre	1400	1.784	1.78	0	1990	358	286	1.78	-	1.5 to 2	Sorghum,	No Data
CADA Pune 1158 1.84 0 1996 306 270 1.81 2 0.1 Paddy, Sorghum Thoseghar 1158 1.84 0 1996 306 270 1.81 2 0.1 Paddy, Sorghum Thoseghar 2272 2.400 4.19 0 1976-77 126 135 2.13 3 -0.40 Khabte Mokashi 3623 4.190 4.19 0 1976-77 126 105 4.19 4 0.20 Paddy Kabte Mokashi 3872 3.641 3.64 0 1976-77 126 126 2.13 4.74 6-46- Kondgeon 3872 3.641 3.64 0 1976-50 126 120 2.00 2.00 -46- Monknucd 3872 3.641 1.79 0 1979-50 2.12 188 3.64 -60- Pabhre 370 4.74 0 1978-79 173 1.73 1.79<													Groundnut,	
Thoseghar 1158 1.84 1.84 0 1996 306 270 1.81 2 0.1 Paddy, Sorghum TIC Thane 2.72 2.400 1.82 2.400 1.82 0.35 -de- - Kabre Mokashi 3623 4.190 4.19 0 1976-77 126 105 4.19 4 0.20 Paddy, Sorghum Kabre Mokashi 3623 4.190 4.19 0 1976-77 126 105 4.19 4 0.20 Paddy Kandgeon 3872 3.641 3.64 0 1976-30 120 2.00 2.00 2.040 -de- Kondgeon 3872 3.641 3.64 0 1976-30 188 3.64 5 0.40 -de- Policiture 3370 4.740 0 1979-30 173 1.73 4.74 5 0.35 -de- Policiture 3370 4.74 0 173 1.73		CADA Pune											VVIICAL	
TC Thane TC Than TC T	15	Thoseghar	1158	1.84	1.84	0	1996	306	270	1.81	2	0.1	Paddy, Sorghum	0
Bhoj 2472 2.400 1.62 0 1974 216 135 2.13 3 0.35 -do- Kalote Mokashi 3623 4.190 4.19 0 1976-77 126 105 4.19 4 0 200 Paddy Khandpe 2377 2.000 2.00 0 1976-77 126 105 4.19 4 0.20 Paddy Khandpe 2377 2.000 2.00 0 1975-80 212 120 2.00 20.40 -do- Mokndgaon 3720 4.740 4.74 0 1975-80 212 188 3.64 5 -do- Pabhe 32070 4.740 1.79 0 1978-79 173 4.74 5 0.20 -do- Pabhe 3427 1.79 0 1978-79 173 1.79 3 0.20 -do- Note: Necessary changes for some projects in sub-basin, Plan group and type are incorporated in the above overview. 3		TIC Thane												
Kalote Mokashi 3623 4.190 4.19 0 1976-77 126 105 4.19 4 0.20 Paddy Khandpe 2377 2.000 2.00 0 1976-77 126 105 4.19 4 0.20 Paddy Khandpe 2377 2.000 2.00 0 1985 202 120 2.00 2 0.40 -do- Mondgan 3872 3.641 3.64 0 1979-80 212 188 3.64 5 0.46 -do- Moknurd 3070 4.740 4.74 0 1975 213 173 4.74 5 0.35 -do- Pabrie 32070 4.77 1.79 0 1978-79 173 1.79 3 0.20 -do- Note: Necessary changes for some projects in sub-basin, Plan group and type are incorporated in the above overview. 3 0.20 -do-	21	Bhoj	2472	2.400	1.62	0	1974	216	135	2.13	e	0.35	-op-	160
Khandpe 2377 2.000 2.00 0 1985 202 120 2.00 20 -do- Kondgeon 3872 3.641 3.64 0 1979-80 212 188 3.64 5 NA -do- Mohkund 3070 4.740 4.740 1.79 0 1975 213 173 4.744 5 0.35 -do- Pabhre 347 1.79 0 1978-79 174 133 1.79 5 0.35 -do- Note: Necessary changes for some projects in sub-basin, Plan group and type are incorporated in the above overview. 3 0.20 -do-	22	Kalote Mokashi	3623	4.190	4.19	0	1976-77	126	105	4.19	4	0.20	Paddy	105
Kondgaon 3872 3.64 0 1979-80 212 188 3.64 5 NA -do- Mohknurd 3070 4.740 4.74 0 1975 213 173 4.74 5 0.35 -do- Pabhre 3429 1.779 0 1978-79 174 133 1.79 5 0.20 -do- Note: Necessary changes for some projects in sub-basin, Plan group and type are incorporated in the above overview. 1.79 3 0.20 -do-	21	Khandpe	2377	2.000	2.00	0	1985	202	120	2.00	2	0.40	-op-	120
Mohknurd 3070 4.740 4.74 0 1975 213 173 4.74 5 0.35 -do- Pabhre 3429 1.787 1.79 0 1978-79 174 133 1.79 3 0.20 -do- Note: Necessary changes for some projects in sub-basin, Plan group and type are incorporated in the above overview. 3 0.20 -do-	22	Kondgaon	3872	3.641	3.64	0	1979-80	212	188	3.64	5	AN	-do-	0
Pabhre 3429 1.787 1.79 0 1978-79 174 133 1.79 3 0.20 -do- Note: Necessary changes for some projects in sub-basin, Plan group and type are incorporated in the above overview. 0.20 -do- 0	21	Mohknurd	3070	4.740	4.74	0	1975	213	173	4.74	5	0.35	-do-	0
-	22	Pabhre	3429	1.787	1.79	0	1978-79	174	133	1.79	ю	0.20	-do-	0
		Note: Necessary chai	-	ne projects in	sub-basin, P	lan group and	I type are incor	porated in the	above overview					



Appendix-IV

River Basins & Agro- Climatic zones of Maharashtra

River Basins

The State is mainly covered by the basins of Krishna, Godavari and Tapi except the west-flowing rivers of Konkan strip. A small portion on north comes under Narmada basin. There are in all 380 rivers in the State and their total length is 19269 km. Most of the land is undulating and hilly. Comparatively, continuously hilly plateau lands are very few. Because of this, flow canal systems in Maharashtra are very expensive, though there are large numbers of suitable sites for building water storage reservoirs.

Number of rivers originates from Sahyadri at about 500 to 700 m elevation and flow westward to Arabian Sea through the Konkan strip. Damanganga, Surya, Vaitarna, Ulhas, Karla, Kundalika, Kal, Savitri, Vashishthi, Shastri, Gad, Karli, Tillari and Terekhol are the prominent rivers. These rivers are of shorter length holding fair amount of water during monsoon but run totally dry during summer. The natural calamities such as land erosion, salt water intrusion, land subsistence etc. are often inflicted upon Konkan.

Tapi and Narmada are the two west-flowing rivers coming from Madhya Pradesh and flowing down to Gujarat State through Maharashtra. Narmada forms 54 km long common boundary of the State along northern border. Total length of Tapi in Maharashtra is 208 km. These rivers and tributaries have rendered the land of Khandesh¹ fertile.

Wainganga flows in north-south direction. The length of Waiganga in Maharashtra is 476 km. Godavari is the principal east-flowing and longest river in Maharashtra (968 km).

South-east flowing Bhima and mainly north-south flowing Krishna are the major rivers of South Maharashtra. The length of Bhima in Maharashtra is 451 km. It joins Krishna on the Karnataka-Andhra Pradesh boundary near Raichur.

Krishna rises near Mahabaleshwar. Krishna is 282 km long in the State. Basin-wise water availability – (Maharashtra – India)	

	Das	m-wise water	availability	/ – (manarasi	ili a – iliulaj	
Sr.	Basin	Geographical	Culturable	Average	75%	Permissible
No		Area (Mha)	Area	Annual	Dependable	Use As Per
			(Mha)	Availability	Yield (BCM)	Tribunal
				(BCM)		Award
						(BCM)
1	Godavari	15.430	11.256	50.880	37.300	34.185
2	Тарі	5.120	3.731	9.118	6.977	5.415
3	Narmada	0.160	0.064	0.580	0.315	0.308
4	Krishna	7.010	5.627	34.032	28.371	16.818
5	West flowing	3.160	1.864	69.210	58.599	69.210
	Rivers					
	Total:	30.88	22.542	163.820	131.562	125.936

Sub-basin wise planning

As per the recommendations laid down in the National Water Policy – 2002 and Maharashtra Water and Irrigation Commission's Report, the State Water Policy has been adopted by GOM in 2003.

The objectives of the Maharashtra State Water Policy are to ensure the sustainable development and optimal use and management of the State's water resources, to provide the greatest economic and social benefit for the people of the State of Maharashtra and to maintain important ecological values within rivers and adjoining lands.

The Maharashtra State Water Policy mentions that -

'To adopt an integrated and multi-sectoral approach to the water resources planning, development and management on a sustainable basis taking river basin/sub basin as a unit.'

The water resources of the State shall be planned, developed, managed with a river basin/ sub basin as a unit, adopting multicultural approach and treating surface and sub-surface water with unitary approach.'

The geographical area of the State is 308 lakh ha and cultivable area is 225 lakh ha. This geographical area is divided mainly into five major river basins of Godavari, Krishna, Tapi, Narmada and basin groups in Konkan. There are 22 narrow basins of west flowing rivers in Konkan.

The Maharashtra Water and Irrigation Commission has proposed delineation of five river basins basically into 25 distinct sub basins for planning of water resources development in the State. The categorisation of sub basins proposed is solely on the basis of natural availability of water. The basic characteristics of sub basins are dictated by the hydrological regime, which in turn, is a function of climate, rainfall distribution and the draining area.

Sr. No.	River Basin	Names of Sub basins	Abbreviated name	Categorisation for planning on the basis of availability of natural water
Ι	Godavari	1) Upper Godavari (Up to Paithan Dam)	Upper Godavari	Normal
		2) Lower Godavari (D/S of Paithan Dam)	Lower Godavari	Deficit
		3) Purna (including Dudhana)	Purna Dudhana	Deficit
		4) Manjra	Manjra	Deficit
		5) Godavari-Sudha-Swarna	Remaining Godavari	Normal
		6) Painganga	Painganga	Normal
		7) Wardha	Wardha	Normal
		8) Middle Wainganga	Middle	Surplus
			Wainganga	
		9) Lower Wainganga	Lower Wainganga	
	Тарі	10) Purna (Tapi)	Purna Tapi	Deficit

The sub basins are as follows:


Sr. No.	River Basin	Names of Sub basins	Abbreviated name	Categorisation for planning on the basis of availability of natural water
		11) Girna	Girna	Deficit
		12) Panzara	Panzara	Normal
		13) Middle Tapi	Middle Tapi	Deficit
III	Narmada	14) Narmada	Narmada	Surplus
IV	Krishna	15) Upper Krishna (West)	Upper Krishna (W)	Abundant
		16) Upper Krishna (East)	Upper Krishna (E)	Highly Deficit
		17) Upper Bhima (Up to Ujjani)	Upper Bhima	Normal
		18) Remaining Bhima	Remaining Bhima	Normal
		19) Sina-Bori-Benetura	Sina-Bori- Benetura	Highly Deficit
V	West Flowing	20) Damanganga-Par	Damanganga-Par	Abundant
	Rivers in	21) North Konkan	North Konkan	Abundant
	Konkan	22) Middle Konkan	Middle Konkan	Abundant
		23) Vashishthi	Vashishthi	Abundant
		24) South Konkan	South Konkan	Abundant
		25) Terekhol – Tillari	Terekhol – Tillari	Abundant

Categorization of sub basins for planning, on basis of naturally available quantum of water, is given below:

Sr. No.	Plan Group	Per ha availability	Percent of cultivable
		(m ³)	area of State
i)	Highly Deficit Area	Below 1500	13
ii)	Deficit area	1501-3000	32
iii)	Normal area	3001-8000	34
iv)	Surplus area	8001-12000	06
v)	Abundant area	Above 12000	15

A graph showing basin wise availability of water is appended herewith.

The performance of a circle (herein called service provider) very much depends upon the availability of water, which in turn is governed by the type of subbasin in which the project is located. Some circles are having projects located in more than one category of plan group of sub-basins. Therefore, these circles will appear more than once, in graphical representation of indicators.



Water Availability per ha of Culturable Area

Climate

Maharashtra is having mostly a seasonal climate. Four distinct seasons are noticeable in a year viz. (1) Monsoon: The rains start with the south - west winds. Mainly it rains during the four months from June to September, but it often extends up to October. (2) Post-monsoon season: October to mid December is a fair weather season with meagre rains. These are the initial months of the post-monsoon, *Rabi* crops and the condition of later depends upon the weather during these months. (3) Winter: It is generally a period of two or two-and-a-half months, from mid-December until end of February. Most of the *Rabi* crops are harvested during these months. (4) Summer: It lasts for at least three months - March to May.

There is considerable variation in weather and rainfall among the five different geographical regions of Maharashtra.

1 The coastal districts of Konkan experience heavy rains but mild winter. The weather, however, is mostly humid throughout the year.

The maximum and minimum temperatures here range between 27^oC and 40^oC and 14^oC to 27^oC respectively. The relative humidity is 81% to 95% during June to August while 30% to 65% during January - February.

2 The western parts of Nashik, Pune, Satara and Kolhapur districts show a steep reduction in rainfall from the mountainous regions towards the East. The maximum temperature ranges between 26° C to 39° C and the minimum temperature between 8° C to 23° C. The relative humidity is 81% to 99% in August and only 20% to 39% in March.

3 The eastern part of the above four districts together with Ahmednagar, Sangli, Solapur, Aurangabad, Jalna, Beed and Osmanabad districts fall under the rain

shadow of Sahyadri Mountains and therefore the beginning and end of the rainy season is quite uncertain in these parts. The rainfall is also meagre. The climate is extreme. The summer temperature is high (maximum temperature 36^oC to 41^oC) but winter temperature is low (minimum temperature. 10^oC to 16^oC). The relative humidity in August is between 82% to 84% but only 19% to 26% in April. The rainfall increases as we go towards east viz. Parbhani, Nanded and Yavatmal. Many a times the eastern winds during the end of monsoon cause precipitation here.

4 Likewise the Tapi basin, the southern parts of Satpuda ranges and Dhule-Jalgaon districts towards west is low rainfall part like that of rain shadow region. But towards east Buldhana, Akola and Amravati districts experience a heavy rainfall. Summer temperature in this region is quite high (39^oC to 43^oC) and minimum winter temperature is found to be 12^oC to 15^oC. Relative humidity between May to August is 82% to 87% whereas in March-April it is 12% to 31%.

The Wainganga basin on east of Maharashtra and the hilly region still farther east is, on the whole, a zone having good rainfall, but as it is some what low lying area, the climate is even more extreme. The summer temperature is very high $(39^{\circ}C)$ to $45^{\circ}C$) while it is cooler in winter as compared to other regions $(12^{\circ}C \text{ to} 14^{\circ}C)$.

Rainfall

Maharashtra gets rain both from the south-west and the north-east monsoon winds. The proportion of the rainfall derived from the north-east monsoon increases towards east.

The average rainfall of the State is approximately 1360 mm. nearly 88% of the total average rainfall occurs between June to September, while nearly 8% occurs between October to December and 4% after December. There is a considerable variation in the reliability of the rains in different parts of the State.

The steep decline in the rainfall to east of Sahyadri is strikingly noticeable. In the 30 to 50 km wide belt the average rainfall is observed to be less than 650 mm (as low as only 500 mm at some places). Thereafter, the rainfall increases steadily towards east and the average rainfall in the easternmost districts is observed to be 1400 mm.

The pre-monsoon rain during March to May is maximum in Western Maharashtra (5%) while in Marathwada it is 4%, in Vidarbha it is 3% and the minimum is in Konkan (1%).

The number of average annual rainy days is maximum 95 in Konkan, 55 in Vidarbha, 51 in Western Maharashtra and the minimum 46 in Marathwada.

Out of the total cultivable land in Maharashtra about 53% is under *Kharif* and about 30% is under *Rabi* crops. These mostly comprise of food grains and oilseeds. The rainfall during June to September affects both the *Kharif* and the *Rabi* crops. That is why the regularity of rainfall during this period is of importance. But it is seen that there is considerable fluctuation in the number of rainy days as well as the amount of rainfall from year to year. The fluctuation in rainfall is observed to be 25%, 40% and between 20% to 30% in Konkan, Central Maharashtra and Vidarbha respectively. Crop management on fields during this period thereby becomes quite difficult.

Appendix-V

Abstract of Water Rates for Irrigation Domestic and Industrial Use for the
year 2008-09

	Irrigation	Rate Rs./ha (From 1/7/2004)
1	Flow Irrigation	,
	Crops	
А	Kharif	
	Seasonals & paddy (Agreement)	238
	Groundnut, Hy. Seeds etc.	476
В	Rabi	
	Seasonals (except Wheat and Groundnut)	358
	Wheat	476
	Cotton,Groundnut,Paddy etc.	724
С	Hot Weather	
	Ground Nut	1438
	Seasonals	724
D	Two Seasonals	
_	Kharif and Rabi	357
	Rabbi & Hot Weather	605
F	Perenial	
-	Sugarcane,Banana	6298
2	Lift Irrigation (water lifted from)	
Ā	Canal	
	Kharif Crops	85
	Rabi Crops	120
	Hot Weather Crops	240
	Perenial (Sugarcane, Banana)	1810
	Other Perenial Crops	1200
В	Reservoir	
	Kharif Crops	40
	Rabi Crops	60
	Hot Weather Crops	120
	Perenial	910
	Other Perenial	605
С	River	
	Kharif Crops	35
	Rabi Crops	35
	Hot Weather Crops	60
	Perenial	450
	Other Perenial	310
3	Lift Irrigation (Volumetric basis)	Rs/Thousand m ³
-	From canal at minor head	
А	Kharif	47.60
В	Rabi	71.40
C	Hot Weather	144.80
D	If water users contributed for construction (Royalty) for all seasons	23.80

1 A B C	Non Irrigation water rates Domestic Supply From reservoirs, canals and rivers downstream of dams In case Capital Investment is done by user or contributed in proportion of water use	1.50 5.80 1.30
2	Industrial Supply	
A	For Colddrinks, breverages, mineral water etc. From reservoirs,	170.00
В	For Colddrinks,breverages,mineral water etc from canals and rivers downstream of dams	410.00
C	In case Capital Investment is done by user or contributed in proportion of water use	60.00
3	Other use	Rs/10000 Litre.
A	From reservoirs	33.00
В	Canals and rivers downstream of dams	82.00
С	In case Capital Investment is done by user or contributed in proportion of water use	12.00
